Special Meeting Agenda

Tuesday, August 8, 2023
Zoom and In-Person Meeting
Community Center
31 Tiffany Street Upper Level
6:00 p.m.

In-Person: Community Center 31 Tiffany Street Upper Level, B	rooklyn, CT
Online: Click link below: https://us06web.zoom.us/j/83921116459 OR	Go to Zoom.us , click Sign In On the top right, click Join a Meeting Enter meeting ID: 839 2111 6459
Phone: Dial 1 646 558 8656 US Toll Enter meeting number: 839 2111 6459 You can bypass attendee number by pressing #	

Call to Order:

Roll Call:

Staff Present:

Seating of Alternates:

Public Commentary:

Additions to Agenda: None.

Approval of Minutes: Site Walk Minutes June 19, 2023

Regular Meeting Minutes July 11, 2023

Public Hearings:

1. IWWC 23-009 A. Kausch & Sons, Church Street, Map 37, Lot 21, RA Zone; Single-family house with driveway crossing; 2,100 sq ft of proposed wetlands alteration.

Old Business:

- **1. IWWC 23-009 A. Kausch & Sons, Church Street, Map 37, Lot 21, RA Zone;** Single-family house with driveway crossing; 2,100 sq ft of proposed wetlands alteration.
- **2.** IWWC 23-005 Townsend Development Associates LLC, 538 Providence Road, Map 41, Lot 16, PC Zone; Modification to existing approved Special Permit to construct approximately 16,100 sf of Self Storage in two buildings, and 19,360 sf of commercial space.

- **3. IWWC 23-006 Ryan Kelleher. 404 Wolf Den Road, Map 18, Lot 22, RA Zone;** Improvement of an existing gravel driveway through a wetland to construct a single-family home on 41 acres of land.
- **4.** IWWC **23-007** Tripp Hollow Investments LLC, Tripp Hollow Road, Map **14**, Lot **10-1 RA Zone**; Proposed single-family house, well, septic system and site grading in the upland review area on a subdivision lot created in 2004.
- 5. IWWC 23-008 Wal-Mart Real Estate Business Trust, 450 Providence Road, Map 41, Lot 10, PC Zone; Online grocery pickup addition with parking modifications.

New Business:

253 Wolf Den Road – Janessa Choquette. Show Cause Hearing for Wetlands Violation.

Other Business:

Discussion on special meeting dates: There is no need to vote. It is anticipated that the next regular meeting will be held at the Green Building. Until we meet at the Green Building, meetings at Tiffany Street will be special meetings.

183 Barrett Hill Road – Erica and Ryan Murphy. New horse barn, no wetlands permit needed.

Jake Kausch - 409 & 411 Church Street driveway. Millings have been added to the driveway.

FCR Realty LLC - FCR Gravel Pit, Map 41, Lot 6 and Map 35, Lot 7. The 3/3/22 Enforcement Order has been closed.

Communications:

- 1. Wetlands Agent Monthly Report.
- 2. Budget Update.

Public Commentary:	
Adjourn:	
Richard Oliverson, Chairman	

Brooklyn IWWC

June 19, 2023 Sitewalk Minutes

5:30 PM

Site walk location: Day Street, Map 43, Lot 6; Jeffrey Weaver, #SUBD 22-001

Members present: Adam Brindamour, Demian Sorrentino, James Paquin, Janet Booth

Others present: Jeffrey Weaver

Meeting started: 5:30 PM

Mr. Weaver escorted the members onto the property to show the location of the proposed activity. The members viewed the area of proposed activity: Installation of common driveway to access two rear lots and site work for the construction of two new homes.

Meeting ended: 5:47 PM

Respectfully submitted,

James Paquin, Member Brooklyn IWWC

Brooklyn Inland Wetlands and Watercourses Commission Special Meeting Minutes

Tuesday, July 11, 2023
Zoom and In-Person Meeting
Community Center
31 Tiffany Street Upper Level

Call to Order: 6:00 pm

Roll Call: Richard Oliverson, Adam Brindamour, Janet Booth, Demian Sorrentino, Jason Burgess and James Paquin. Adam Tucker was absent with notice.

Staff Present: Margaret Washburn, Lisa Lindia Recording Secretary, Terry Mahanna

Attendance: Jeffrey Weaver, Paul Archer, Archer Surveying and Jeff Bord, Bohler Engineering

Seating of Alternates: None

Public Commentary: None

Approval of Minutes: Regular Meeting Minutes June 13, 2023, meeting with the following changes.

Page 2/5, the statement "Jim Paquin made a motion Demian Sorrentino seconded the motion" and the following paragraph might be combined to match the others, such as "Jim Paquin made a motion that the 68SF, Demian Sorrentino seconded...." The statement should read: "James Paquin made a motion to lift Cease & Desist Order. Demian Sorrentino seconded the motion. APPROVED 6/0."

Page 3/5 "Adam Brindamour and Demian Sorrentino continue to the next..." should be revised. The statement should read: "Adam Brindamour moved to continue to the next scheduled meeting, July 11, 2023, which will be held at the Community Center. Demian Sorrentino seconded the motion. APPROVED 6/0."

Public Hearings: Not available at this time.

Old Business:

1. SUBD23-001 Jeffrey Weaver, Day Street, Map 43, Lot 6, R-30 and RA Zones; 2-lot subdivision. Richard Oliverson – recuses himself as an abutter.

Jeff Weaver – Is present to answer questions regarding the application.

A site walk was done on 6/19/23. Joe Theroux delineated the wetlands. The only regulated area is on one lot. The pipe is outside the regulated area. The only work to be approved is in the Upland Review Area. The house on the westerly side is out of the 125 feet regulated area.

Adam Brindamour – Is the foundation of the new house under construction the source of water flowing down the hill?

Jeff Weaver – I have zero water coming out of the foundation. The curtain drain has been in for about month and half. The water is not coming from the house, it is residual water that is funneling down across the lot. The silt fence did treat a substantial amount of water.

Janet Booth – Asked if the pipe will handle the flow.

Jeff Weaver – We don't want to create a dam.

Demian Sorrentino - There is protection on both sides of the pipe, the water will reach the wetland.

Margaret Washburn – The water originates from the sky, shallow subsurface flow and surface runoff.

Janet Booth – Is the pipe our jurisdiction?

Demian Sorrentino – No, there is a swale, not a wetland.

Paul Archer – No, that would go to PZC.

James Paquin – There is not much cover over the pipe, according to Syl Pauley.

James Paquin made a motion to approve with Standard Conditions. Jason Burgess seconded the motion. APPROVED 5/0.

Richard Oliverson – returns to the table.

2. IWWC 23-005 Townsend Development Associates LLC, 538 Providence Road, Map 41, Lot 16, PC Zone; Modification to existing approved Special Permit to construct approximately 16,100 sf of Self Storage in two buildings, and 19,360 sf of commercial space.

Demian Sorrentino made a motion to table to the next meeting Janet Booth seconded the motion. No discussion. The motion passed 6-0

New Business:

1. IWWC 23-006 Ryan Kelleher. 404 Wolf Den Road, Map 18, Lot 22, RA Zone; Improvement of an existing gravel driveway through a wetland to construct single-family home on 41 acres of land.

Application was received 7/11/23. No one was present to represent the project.

2. IWWC **23-007** Tripp Hollow Investments LLC, Tripp Hollow Road, Map 14, Lot 10-1 RA Zone; Proposed single-family house, well, septic system and site grading in the upland review area on a subdivision lot created in 2004.

Application was received 7/11/23. No one was present to represent the project.

3. IWWC 23-008 Wal-Mart Real Estate Business Trust, 450 Providence Road, Map 41, Lot 10, PC Zone; Online grocery pickup addition with parking modifications.

Jeff Bord Engineer, Bohler Engineering – The purpose of the project is an expansion of a 59,050 square-foot addition for an online pick-up area in the northeast corner. The reconfiguration will eliminate 12 parking spaces and reduce 680 square feet of impervious area by adding new landscaped areas where the work is proposed to be done. The work in the upland review is the landscape. They are +/- 100 feet away from the storm water pond.

Margaret Washburn – Is there any work being done outside the existing pavement footprint?

Jeff Bord - There is no work being done outside of the existing pavement.

Margaret Washburn – Is there any bump out on the back of existing building?

Jeff Bord – Not to my knowledge. The aerial is a current display, and nothing is shown with bump outs on the building.

Demian Sorrentino – Is there any chance that sediment will reach the pond?

Jeff Bord – No, I do not see it being an issue; we are not working in that area. Some utility easements that are being maintained. We will have to go to PZC next and to the DOT for an updated approval.

Margaret Washburn – Asked about the plans in the file.

Jeff Bord – Stated there is an existing condition plan; no proposed work is shown on it.

4. IWWC 23-009 A. Kausch & Sons, Church Street, Map 37, Lot 21, RA Zone; Driveway with wetland crossing with 1,340 sq ft of wetlands fill proposed for a single-family house with attached garage, porch, deck, septic system, well and associated grading all in the upland review area.

Paul Archer, Archer Surveying – Questioned where the 1,340 square feet and 760 square feet came from of proposed wetlands being filled.

Margaret Washburn – Explained that it is written on the application that was submitted.

Demian Sorrentino – Does Mr. Kausch still own the driveway from 411 Church Street? Using this would have been a feasible and prudent alternative.

Paul Archer – No, he does not. His son owns the driveway now.

Demian Sorrentino – Did Mr. Kausch contemplate developing this lot before selling the shared driveway?

Paul Archer – No.

James Paquin – Is it possible that Mr. Kausch will consider asking his son for an easement?

Margaret Washburn - Mr. Kausch also owns more land, at the rear of the property, for a third house. Shared driveways are limited to three houses.

Monday 7/31/23 at 8:30 am, Paul Archer will be at the site to meet Adam Brindamour, Janet Booth and Margaret Washburn for a site inspection.

Demian Sorrentino made a motion to schedule a public hearing on 8/8/23 due to significant activity. Adam Brindamour seconded the motion. APPROVED 6/0.

IWWC 23-006 Ryan Kelleher. 404 Wolf Den Road, Map 18, Lot 22, RA Zone

No Hearing was scheduled for 404 Wolf Den Rd. James Paquin asked to have the plans passed around.

Demian Sorrentino – Questioned where is the 20-scale plan from the road to the stone wall?

Drainage calculations? Watershed analysis?

Will Margaret forward a list of my comments to the design engineer?

Margaret Washburn - Yes.

Communications:

- 1. Wetlands Agent Monthly Report.
- 2. Budget Update.
- 3. Public Commentary: None

Adjourn: 6:57 p.m. James Paquin made a motion to adjourn. Adam Brindamour seconded the motion. APPROVED 6/0.

Submitted By: Lisa M Lindia Recording Secretary



Brooklyn Land Use Department

69 South Main Street Brooklyn CT 06234 (860) 779-3411 x 31

Inland Wetlands Zoning Enfo	rcement Blight Enforcement
SITE INSPECTION NUMBE	R 1 2 3 4 5
Lot 21 ChurchSt	7/31/23
Address	Date
I met adam Bri	ndamour and Janet Booth,
- Unspecied and t	ook photos of the new
proposed house	site off the existing
driveway to	# 409 + # 41/ Churchst.
Jake Kausch	met us, Paul archer
failed to appea	1 although the site
walk was sch	reduled on 7/11,
Jake called	Paul archer, P. archer
failed to repla	cethe wetlands
1/	e anything according
to Jake Kausch	Jake did not know
- that there is a pul	lic hearing on 8/8, 1
	at Paul Orcher's failure
to do the staking / fl	ag rylacing may cause delays.
Commission Representative	
Owner or Authorized Signature	





INLAND WETLANDS & WATERCOURSES COMMISSION TOWN OF BROOKLYN, CONECTICUT

Date		Application #	_

APPLICATION -- INLAND WETLANDS & WATERCOURSES

APPLICANT A HOUSCH & SONS MAILING ADDRESS 15 Blach VIEW FX + Volunto APPLICANT'S INTEREST IN PROPERTY OWNEY PHONE 800-230-7928 EMAIL C
PROPERTY OWNER IF DIFFERENTPHONE Mailing AddressEMAIL
ENGINEER/SURVEYOR (IF ANY) Archer Surveying UC (Paul Archer) ATTORNEY (IF ANY)
PROPERTY LOCATION/ADDRESS Church Street MAP # 37 LOT # 21 ZONE RA TOTAL ACRES 4.18 ACRES OF WETLANDS ON PROPERTY 2.97
PURPOSE AND DESCRIPTION OF THE ACTIVITY RESIDENTIAL DEVELOPMENT (HOUSE, SEPTIC SYSTEM, WELL, ANYEWAY)
WETLANDS EXCAVATION AND FILL: FILL PROPOSED CUBIC YDS SQ FT
MITIGATION MEASURES (IF REQUIRED): WETLANDS/WATERCOURSES CREATED: CY SQFT ACRES
IS PARCEL LOCATED WITHIN 500FT OF AN ADJOINING TOWN? No. 1F YES, WHICH TOWN(S) POMENTED IN CT GENERAL STATUTES 25-32A? NO.
THE OWNER AND APPLICANT HEREBY GRANT THE BROOKLYN IWWC, THE BOARD OF SELECTMAN AND THEIR AUTHORIZED AGENTS PERMISSION TO ENTER THE SUBJECT PROPERTY FOR THE PURPOSE OF INSPECTION AND ENFORCEMENT OF THE IWWC REGULATIONS OF THE TOWN OF BROOKLYN. IF THE COMMISSION DETERMINES THAT OUTSIDE REVIEW IS REQUIRED, APPLICANT WILL PAY CONSULTING FEE.
NOTE: DETERMINATION THAT THE INFORMATION PROVIDED IS INACCURATE MAY INVALIDATE THE IWWC DECISION AND RESULT IN ENFORCEMENT ACTION. APPLICANT: DATE DATE DATE 15/23

JUL - 6 2023

REQUIREM	<u>IENTS</u>
And the second second	APPLICATION FEE \$ STATE FEE (\$60.00)
	COMPLETION OF CT DEEP REPORTING FORM
	ORIGINAL PLUS COPIES OF ALL MATERIALS REQUIRED - NUMBER TO BE DETERMINED BY STAFF
	PRE-APPLICATION MEETING WITH THE WETLANDS AGENT IS RECOMMENDED TO EXAMINE THE SCOPE OF THE ACTIVITY
	SITE PLAN SHOWING LOCATION OF THE WETLANDS WITH EXISTING AND PROPOSED CONDITIONS. APPLICANT MAY BE REQUIRED EXTIFIED SOIL SCIENTIST IDENTIFY THE WETLANDS.
***************************************	COMPLIANCE WITH THE CONNECTICUT EROSION & SEDIMENTATION CONTROL MANUAL
	IF THE PROPOSED ACTIVITY IS DEEMED TO BE A "SIGNIFICANT IMPACT ACTIVITY" A PUBLIC HEARING IS REQUIRED ALONG WITH THE
	 Names and addresses of abutting property owners Additional Information as contained in IWWC Regulations Article 7.6
ADDITIONA	AL INFORMATION/ACTION NEEDED:
	Inland Water Resources Division 79 ELM St. HARTFORD, CT. 06106 1-860-424-3019 ARTMENT OF THE ARMY CORPS OF ENGINEERS 696 VIRGINIA ROAD CONCORD, MA. 01742 1-860-343-4789
STAFF USE ONLY:	
Ds	ECLARATORY RULING: AS OF RIGHT & NON-REGULATED USES (SEE IWWC REGULATIONS SECTION 4)
PE	ERMIT REQUIRED: AUTHORIZED BY STAFF/CHAIR (NO ACTIVITY IN WETLANDS/WATERCOURSE AND MINIMAL IMPACT)
	CHAIR, BROOKLYN IWWC WETLANDS OFFICER AUTHORIZED BY IWWC SIGNIFICANT ACTIVITY/PUBLIC HEARING
Ne	O PERMIT REQUIRED
	OUTSIDE OF UPLAND REVIEW AREA NO IMPACT
	CHAIR, BROOKLYN IWWC WETLANDS OFFICER
Ti	MBER HARVEST



GIS CODE #:	Evenomen.	-	minuscom.	-	 	
For DEEP Use Only						

79 Elm Street • Hartford, CT 06106-5127

www.ct.gov/deep

Affirmative Action/Equal Opportunity Employer


Statewide Inland Wetlands & Watercourses Activity Reporting Form

Please complete and mail this form in accordance with the instructions on pages 2 and 3 to:

DEEP Land & Water Resources Division, Inland Wetlands Management Program, 79 Elm Street, 3rd Floor, Hartford, CT 06106

Incomplete or incomprehensible forms will be mailed back to the inland wetlands agency.

Samuela	
	PART I: Must Be Completed By The Inland Wetlands Agency
1.	DATE ACTION WAS TAKEN: year: month:
2.	ACTION TAKEN (see instructions, only use one code):
3.	WAS A PUBLIC HEARING HELD (check one)? yes no
4.	NAME OF AGENCY OFFICIAL VERIFYING AND COMPLETING THIS FORM:
	(print name) (signature)
	PART II: To Be Completed By The Inland Wetlands Agency Or The Applicant
5.	TOWN IN WHICH THE ACTION IS OCCURRING (print name): BYOOKIUM
	does this project cross municipal boundaries (check one)? yes no no
	if yes, list the other town(s) in which the action is occurring (print name(s)):
6.	LOCATION (see instructions for information): USGS quad name: DOVICISON or number: 43
	subregional drainage basin number:
7.	NAME OF APPLICANT, VIOLATOR OR PETITIONER (print name): A KOUSCH & SONS
8.	NAME & ADDRESS / LOCATION OF PROJECT SITE (print information): Church St. (37 - 21)
	briefly describe the action/project/activity (check and print information): temporary permanent description:
9.	ACTIVITY PURPOSE CODE (see instructions, only use one code):
10	. ACTIVITY TYPE CODE(S) (see instructions for codes):,
11	. WETLAND / WATERCOURSE AREA ALTERED (must provide acres or linear feet):
	wetlands: 0.05 acres open water body: acres stream: linear feet
12	. UPLAND AREA ALTERED (must provide acres): acres
13	AREA OF WETLANDS / WATERCOURSES RESTORED, ENHANCED OR CREATED (must provide acres):
D	ATE RECEIVED: PART III: To Be Completed By The DEEP DATE RETURNED TO DEEP:
Water Strategy	
F	ORM COMPLETED: YES NO FORM CORRECTED / COMPLETED: YES NO



REFERENCE IS MADE TO:

- Soll Survey of Mindham County Connecticut, U.S.D.A. Soil
- 2. Install and maintain erosion and sedimentation control devices as shown on these plans. All erosion control devices shall be inspected by an agent of the Town. Any additional erosion control devices required by the Town's Agent shall be installed and inspected prior to any construction on site. (See silt fence installation notes.) Prior to any work on site, the limits of disturbance shall be clearly flagged in the field by a Land Surveyor, licensed in the State of Connecticut. Once the limits of clearing are flagged, they shall be reviewed and approved by an agent of the Town.
- Install construction
- Construction will begin with clearing, grubbing and rough grading of the proposed site. The work will be confined to areas adjacent to the proposed building, septic system and ariveway. Topsoll will be stockpiled on site and utilized during final grading.
- 6. Disturbed areas shall be seeded and stabilized as soon as possible to prevent erosion Begin construction of the house, septic system

The site will be graded so that all possible trees on site will be saved to provide buffers to lots.

- Development of the site will be performed by the individual lot owner, who will be responsible for the installation and maintenance of erosion and sediment control measures required throughout construction.
- The sedimentation control mechanisms shall remain in place from start of construction until permanent vegetation has been established. The representative for the TOWN WIII be notified when sediment and erosion control structures are initially in place. Any additional soil \$\pi\$ erosion control measures requested by the TOWN or its agent, shall be installed immediately. Once the proposed development, seeding and planting have been completed, the representative shall again be notified to inspect the site. The control measures will not be removed until this inspection is complete.
- All stripping is to be confined to the immediate construction area. Topsoil shall be stockpiled so that slopes do not exceed 2 to 1. A hay bale sediment barrier is to surround each stockpile and a temporary vegetative cover shall be provided.
- Dust control will be accomplished by spraying with water and if necessary, the application of calcium chloride.
- The proposed planting schedule is to be adhered to during the planting of disturbed areas throughout the proposed construction site.
- T FENCE INSTALLATION AND MAINTENANCE:
- 2. Position the posts on the downhill side of the barrier and drive the posts 1.5 feet into the Dig a 6" deep trench on the uphill side of the barrier location
- Lay the bottom 6" of the fabric in the trench to prevent undermining Inspect and repair barrier after heavy rainfall
- Inspections will be made at least once per week and within 24 hours of the end of a storm amount of 0.5 inch or greater to determine maintenance needs.
- Sediment deposits are to be removed when they reach a height of I foot behind the barrier or half the height of the barrier and are to be deposited in an area which is not regulated by the inland wetlands commission.
- Replace or repair the fence within 24 hours of observed failure. Failure of the fence sediment fails to be retained by the fence because: the fence has been overtopped, undercut or bypassed by runoff water, the fence has been moved out of position (knocked over), or the geotextile has decomposed or been damaged.
- HAY BALE INSTALLATION AND MAINTENANCE:
- Bales shall be placed as shown on Each bale shall be securely anchored with at least 2 stakes and gaps between bales shall be wedged with straw to prevent water from passing between the bales.
- Inspect bales at least once per week and within 24 hours of the end of a storm with a rainfall amount 0.5 inches or greater to determine maintenance needs.
- Remove sediment behind the bales when it reaches half the helght of the bale and deposit in an area which is not regulated by the inland Wetlands Commission.

SEED SELECTION

Grass species shall be appropriate for Figure TS-2 in the 2002 Guidelines.

- eed with a temporary seed mixture within 7 days after the suspension of grading work in here the suspension of work is expected to be more than 30 days but less than I year.

SITE PREPARATION

- nstall needed erosion control mea and grassed waterways.
- Grade according to plans and allow for the use of appropriate equipment for seedbed preparation, seeding, mulch application, and mulch anchoring. SEEDBED PREPARATION
- Loosen the soil to a depth of 3-4 inches with a slightly roughened surface. If the area has been recently loosened or disturbed, no further roughening is required. Soil preparation can be accomplished by tracking with a buildozer, discing, harrowing, raking or dragging with a section of chain link fence. Avoid excessive compaction of the surface by equipment traveling back and forth over the surface. If the slope is tracked, the cleat marks shall be perpendicular to the anticipated direction of the flow of surface water.
- f soil testing is not practical or feasible on small or variable sites, or where timing is critical, fertilizer may be applied at the rate of 300 pounds per acre or 7.5 pounds per 1,000 square feet of 10-10-10 or equivalent. Additionally, lime may be applied using rates given in Figure TS-1 in the 2002 Guidelines.
- MULCHING Apply seed uniformly by hand cyclone seeder, drill, cultipacker type seeder or for the selected specles. Increase seedling rates by 10% when hydroseedling.
- Temporary seedings made during optimum seeding dates shall be mulched according to the recommendations in the 2002 Guidelines. When seeding outside of the recommended dates, increase the application of mulch to provide 45%-100% coverage. MAINTENANCE
- Where seed has moved or where soil erosion has occurred, determine the cause of the failure. Repair eroded areas and install additional controls if required to prevent reoccurrence of erosion. Inspect seeded area at least once a week and within 24 hours of the end of a storm with of 0.5 inch or greater for seed and mulch movement and rill erosion.
- Continue inspections until the grasses are firmly established. Grasses shall not be considered establish until a ground cover is achieved which is mature enough to control soil erosion and to survive severe weather conditions (approximately 80% vegetative cover).

Refer to Permanent Seeding Measure in the 2002 Guidelines for specific applications and details related to the installation and maintenance of a permanent vegetative cover. In general, the following sequence of operations shall apply:

Topsoil will be replaced once the excavation and grading has been completed. Topsoil will be spread at a minimum compacted depth of $4^{\rm n}$.

Once the topsoil has been spread, all stones 2" or lar dimension will be removed as well as debris.

Apply agricultural ground limestone at a rate of 2 tons per acre or 100 lbs. per 1000 s.f. Apply 10-10-10 fertilizer or equivalent at a rate of 300 lbs. per acre or 7.5 lbs. per 1000 s.f. Mork lime and fertilizer into the soil to a depth of 4".

4. Inspect seedbed before see retill compacted areas. Apply the chosen grass seed mix. The recommendare: April I to June 15 & August 15 - October 1. ted the soil, ding dates

Following seeding, firm seedbed with a roller. Mulch immediately following seeding. If a permanent vegetative stand cannot be established by September 30, apply a temporary cover on the topsoll such as netting, mat or organic mulch.

PRINCIPLES OF EROSION AND SEDIMENT CONTROL EROSION AND SEDIMENT CONTROL NARRATIVE:

The primary function of erosion and sediment controls is to absorb erosional energies and reduce runoff velocities that force the detachment and transport of soil and/or encourage the deposition of eroded soil particles before they reach any sensitive area.

KEEP LAND DISTURBANCE TO A MINII

and potential and potential and potential ly involves also the duration reduling are inct sections over distinct a subsequent der in which ar phase. A things first" and it things first" and is should address ad should address and be in conflict

Limit areas of clearing and grading. Protect natural vegetation from construction equipment with fencing, tree armoring, and retaining walls or tree wells.

Route traffic patterns within the planted vegetation. to avoid existing or newly

Sequence the construction of storm drainage systems so that they are operational as soon as possible during construction. Ensure all outlets are stable before outletting storm drainage flow into them. Phase construction so that areas which are actively being developed at any one time are minimized and only that area under construction is exposed. Clear only those areas essential for construction.

Schedule construction so that final grading and stabe completed as soon as possible. lization is

Detachment and transport of eroded soil must be kept to a minimum by absorbing and reducing the erosive energy of water. The erosive energy of water increases as the volume and velocity of runoff increases. The volume and velocity of runoff increases during development as a result of reduced infiltration rates caused by the removal of existing vegetation, removal of topsoil, compaction of soil and the construction of impervious surfaces. Use diversions, stone dikes, silt fences and similar m break flow lines and dissipate storm water energy. asures to

KEEP CLEAN RUNOFF SEPARATED Avoid diverting one drainage system into another without calculating the potential for downstream flooding or erosion.

Clean runoff should be kept separated from sediment lade should not be directed over disturbed areas without addit Additionally, prevent the mixing of clean off-site generate sediment laden runoff generated on-site until after adequote on-site waters has occurred. en water and tional controls. ed runoff with vate filtration

REDUCE ON SITE POTENTIAL INTERNALLY AND INSTALL PERIMETER Divert site runoff to keep it isolated from wetlands, and drainage ways that flow through or near the de the sediment in that runoff is trapped or detained. watercourses velopment until

CONSTRUC

TION ENTRANCE

While it may seem less complicated to collect all waters to one point of discharge for treatment and just install a perimeter control, it can be more effective to apply internal controls to many small sub-drainage basins within the site. By reducing sediment loading from within the site, the chance of perimeter control failure and the potential off-site damage that it can cause is reduced. It is generally more expensive to correct off-site damage than it is to install proper internal controls.

rainage area ontend with d deposited in

Direct runoff from small disturbed areas to adjoining undisturbed vegetated areas to reduce the potential for concentrated flows and increase settlement and filtering of sediments. afely conveyed vays, diversions,

Concentrated runoff from development should be so to stable outlets using rip rapped channels, waterw storm drains or similar measures. basins are Iding is planned

Determine the need for sediment basins. Sediment baren required on larger developments where major grading and where it is impossible or impractical to control ersource. Sediment basins are needed on large and smaken sensitive areas such as wetlands, watercourses, would be impacted by off-site sediment deposition. Esediment basins in wetlands or permanent or intermittate watercourses. Sediment basins should be located to runoff prior to its entry into the wetland or watercourses.

Grade and landscape aro divert water away from th

SEPTIC SYSTEM CONSTRUCTION NOTES

The building, septic system and well shall be accurately staked in the field by a licensed Land Surveyor in the State of Connecticut, prior to construction. Topsoil shall be removed and in the area of the primary leaching field scarified, prior to placement of septic fill. Septic fill specifications are as follows:



|-|12" MIN. |-|DEPTH

RIBS INSIDE

KNOCKOUT INLET AND OUTLET OPENINGS

ANGLE IO° UP SLOPE FOR STABILITY AND SELF CLEANING

PERCENT PASSING
(NET SIEVE)
100%
100% - 100%
10% - 50%
0% - 20%
0% - 5% GRADATION OF FILL (MINUS GRAVEL)

Ill material shall be approved by the sanitarian prior to placement. shall be compacted in 6" lifts and shall extend a minimum of shall be compacted in 6" lifts and shall extend a minimum of shall be compacted in 6" lifts and shall extend a minimum of off. PPTIC tank shall be two compartment precast 1250 gallon tank with as deflector and outlet filter as manufactured by Jolley Precast, or equal.

T FENCE

stribution boxes shall be 4 hole pre Jolley Precast, Inc. or equal. crete as mar

l precast structures such as septic tanks, distribution boxes, etc. all be set level on six inches (6") of compacted gravel base at the evations specified on the plans.

IIId distribution pipe shall be 4" diameter PVC meeting ASTM D-3034 XR 35 with compression gasket joints. It shall be faid true to the 25 and grades shown on the plans and in no case have a slope less 27 0.125 inches per foot.

forated distribution pipe shall be 4" diameter PVC meeting ASTM D-2729 ASTM D-3350, 1500 lb. minimum crush.

orce main pressure pipe from pump chamber to the leaching field nall be 2" diameter pvc meeting ASTM D 2241 SDR 21. er pipe from the foundation wall to the septic tank shall be alule 40 PVC meeting ASTM D 1785. It shall be laid true to the des shown on the plans and in no case shall have a slope less 0.25 inches per foot.

Solid footing drain outlet pipe shall be 4" Diameter PVC meeting ASTM D 3034, SDR 35 with compression gasketed joints. Footing drain outlet pipe shall not be backfilled with free draining naterial, such as gravel, broken stone, rock fragments, etc.

(2)-2"x2"X3" STAKI EACH BALE ——


EINISHED GRADE

4" CONCRETE AC COVER (TYP.)

IF MORE THAN 12" OF COVER—
S REQUIRED IN THE FIELD, PROVIDE
ACCESS COVERS TO GRADE.

CAST CONCRETE COVERS

HAYBALE BARRIER



4" SCHEDULE #40 INLET BAFFLE

BATTLE WITH FIL

DEFLECTO


3" VENT


XX.


CROSS


SECTION


CONTINUOUS HOT ASPHALT SEAL











TRENCH SECTION

the sts ate	25"-80" Grey sandy loa MOTTLES:
ds or permanent or intermittent basins should be located to intercept	MOTTLES:
nto the wetland or watercourse.	GROUNDWATER:
ound buildings and septic systems to hem.	LEDGE:

RESTRICTIVE: 25" RESTRICTIVE:	ROOTS: 16" ROOTS:	LEDGE: NA LEDGE:	GROUNDWATER: 78" seeps @58" GROUNDWATER:	25"	0"-10" Topsoil 10"-25" brown sandy loam 25"-80" Grey sandy loam, mottled, hardpan mottled	TEST PIT: 1 TEST PIT: 2		PERFORMED BY: Donovan Moe WITNESSED BY: Northeast District Department of Health	DEEP TEST PIT DATA / SOIL DESCRIPTIONS
20"	18"	NA	seeps @61"	20"	Topsoil brown sandy loam Grey Sandy Loam hardpan,			DATE: 6/22/2023	RIPTIONS
RESTRICTIVE: 26"	ROOTS: 24"	LEDGE: NA	GROUNDWATER: NA	MOTTLES: 26"	0"-7" Topsoil 7"-26" brown sandy loam 26"-80" Grey Sandy Loam hardpan, mottled	TEST PIT: 3			
NOTES: PERCOLATION TEST PERFORMED ON 6/22/2023 PERFORMED BY D. Moe				PERCOLATION RATE > 5.0 MIN./IN	9:19 9:24 9:29 9:34 9:39 9:44 17		9:05 0.5	TIME Reading (INCHES)	PERCOLATION DATA PERC A - DEPTH 28"



Prepared For:

A. Kausch & Sons LLC

Church Street

Brooklyn, Connecticut



RCHER Surveying LC

18 Providence Road, Brooklyn, (860) 779-2240 CT

Sheet No. July 5, 2023

2 OF 2 Project No. AS 2162 Date:

MAY 0 3 2021

CLA Engineers, Inc.

Civil • Structural • Survey

317 MAIN STREET

NORWICH, CT 06360

(860) 886-1966

(860) 886-9165 FAX

May 3, 2021

Inland Wetlands Commission Town of Brooklyn 69 South Main Street Suite 22 Brooklyn, CT 06234

RE:

CLA 6639 Subdivision

Church Street Brooklyn CT

To the Commission:

CLA Engineers was retained by A. Kausch & Sons LLC to conduct a wetlands investigation and functional assessment on the parcel of land, located on Church Street in Brooklyn CT that is proposed to be developed for a residences. The approximate site location is shown on the cover sheet of the site plans. The purposes of the investigation were to: establish the wetland delineation, provide background data in the form of determining wetland functions, and assess the potential for wetland impacts due to the proposed development.

Wetlands were delineated by Robert Russo of CLA Engineers according to the State of Connecticut statutory definition as described in Section 22a of the State Statutes. CLA conducted field work in October of 2020 amd March of 2021.

After wetland delineation was complete, the wetland resources of the site were surveyed by conducting a deliberate walk through of the site, traversing each wetland in order to collect data characteristic of that wetland. During the walk through, vegetation identifiable was noted, and described.

Site Setting

Much of the site had been used for agriculture up until the 20th century as demonstrated by abundant stonewalls. The presence of numerous Japanese barberry (*Berberis thumbergii*) Indicates that the site was likely used for cattle grazing in the past as this plant is ignored by cattles and soon takes over. The site currently has two vegetative cover types that were established after farming ceased. Both cover types, wooded upland and wooded swamp, are dominated by mixed hardwoods.

The areas of upland have mixed hardwoods such as red maple, red oak, white oak, black cherry and black birch. The wetlands are dominated by red maple trees with other species such as yellow birch and pin oak in lesser numbers.

The land uses surrounding the site include residential, agricultural and woodland. The residential development is primarily located to the north and south along Church St and to the west along Pomfret Landing Rd. Undeveloped farmland and woodland also occurs surrounds the site to the north, west and south.

Throughout the site slopes vary from moderate to nearly flat. The surface water drains both south westward and south eastward off of the site.. The slopes on the east and west side of the site are gentle at the edge of the wetland and are not prone to erosion.

Surficial Geology and Soils

Southern New England was overlain by glacial ice as recently as 12,000-15,000 years ago. The materials that the glaciers deposited over top the local bedrock determine the surficial geology of the region and of the site. Connecticut's glacial deposits are generally divided into three categories: glacial till (un-stratified sand, silt and rock), glaciofluvial (water sorted, stratified sand and gravel), and glaciolacustrine (stratified sand, silt and clay that settled out in lakebeds). Only glacial till is present on the site of the proposed residences. soils formed in till deposits typically have sandy loam to silt loam textures and in this case they are the coarser, sandy loams. The slopes are moderate to flat throughout the site and this leads to differences in soil mapping classification as listed by the NRCS.

Table 1 is a summary table of the soils found on the site.

Table 1 - Soil Types and Properties at the Church Street Site

Soil Series	Parent Material	Drainage Class	Texture/Characteristics
*2 Ridgebury	Glacial Till	Somewhat poorly to very poorly drained	Stony sandy loam
61 Canton and Charlton	Glacial till	Well drained	Sandy loam
46 Woodbridge	Glacial Till	Moderately Well Drained	Sandy loam

^{*} Wetland soil types

Wetland Descriptions and Functions

In the area of the proposed development there is a wetland system that occupies a broad lowland that stretches from Church Street north westward. The wetland itself varies from approximately 100 to 400 feet wide. It is nearly level but has hummocky microtopography Under the USFWS system is a palustrine deciduous swamp (PF01) that is seasonally flooded/saturated. This designation reflect its vegetation which is dominated by mature trees, and its hydrology which has shallow standing water in the winter and after storm events. The wetland lacks standing water in the summer and was not found to contain a perennial stream or vernal pool.

The typical vegetation of the wetlands includes: trees such as red maple trees and saplings, yellow birch trees and saplings; shrubs such as Japanese barberry, spice bush, highbush blueberry, winterberry holly, sweet pepperbush, clammy azalea, alder and plants such as skunk cabbage, cinnamon fern, sphagnum, royal fern, and sensitive fern.

The principle functions of this wetland system are typical to local red maple swamps and the wetland is generally undisturbed with an undisturbed wooded upland buffer. The CTDEEP NDDB (December 2020) shows no known habitat of threatened, endangered or special concern species.

The functions were found to include:

- Wildlife habitat
- Floodwater retention/detention
- Groundwater recharge/discharge
- Biomass production export
- Aesthetics

These values associated with the wetland and are supported by several important features of that wetland:

- Areas of undeveloped buffer
- Limited development within the watershed
- Evidence of use by a diversity of wildlife species.

Potential for Impacts

As shown on the project plans there are proposed activities in the inland wetlands. Three wetland crossing are proposed for the driveway that will provide access to the two houses. These activities are limited to impacts necessary to provide the driveway and are purposed

located in the narrowest reaches of wetland in order to minimize impacts. This lot has significant developable area that cannot be accessed without wetland impacts. The width of the driveway has been kept to the minimum required and the use smaller diameter culverts assists in keeping the elevation of the driveway low, minimizing the side slopes needed for the crossing. CLA believes that the proposed driveway crossing is the most feasible and prudent alternative.

As shown on the plans, work in the wetland will include:

- Clearing and grading
- Construction of driveways and placement of culverts
- Installation of erosion and sedimentation controls
- Construction of utilities

The activities in the wetland have been minimized in order to limit wetland disturbance.

As shown on the plans, work in the upland review zone will include:

- Clearing and grading
- Construction of driveways
- Installation of erosion and sedimentation controls
- Construction of utilities

These activities in the upland review zone present limited potential for wetland impacts. The site has only moderate slopes and short length of slope. CLA believes that the Best Management Practices (BMPs) measures shown on the plans for erosion and sediment control and storm water management will be adequate in preventing wetland impacts if properly installed and maintained.

CLA notes that in order to minimize the potential for impacts to wetlands, the E&S has been designed in compliance with the CTDEEP 2002 E&S Manual.

Alternatives

CLA examined alternative to the proposed wetland crossings. Note that the property has frontage on Pomfret Landing Rd, which could be used to gain access via a driveway, but wetland impacts would also be required. CLA conducted a field to determine the feasibility of a driveway crossing walk of this location. CLA determined that a driveway crossing in this location is not the most feasible and prudent alternative based on the following observations.

1. The wetland that would have to be crossed has a perennial stream, indicating that is a more valuable wetland than those to be impacted by coming off of Church Street.

- 2. The wetland to be crossed is 12 to 14 feet lower in elevation than the access strip off of Pomfret Landing Rd. This would necessitate a wide wetland fill to accomplish the crossing.
- 3. The wetland to be crossed is over 100 feet wide and continues, north and south, as a wildlife travel corridor. This characteristic is lacking in the wetlands that would be disturbed by gaining access from Church Street.
- 4. Due to the width of the wetland and elevation change, present, a wetland crossing at the Pomfret Land access would create a substantial fragmentation of the wetland and reduce its habitat values significantly. This would not be the case with the Church Street acess.

Based on these field observations, CLA believes that the proposed wetland crossings represent the most feasible and prudent alternative.

Summary


The proposed development activities will directly impact wetlands. The work in the upland review zone can be managed with BMPS so as to not impact wetlands during construction. In summary, if the proposed erosion and sedimentation control measures are adhered to, CLA believes that the wetland impacts will be limited to what is necessary to provide a driveway for the building lost.

Please contact me if you have any questions.

Very truly yours,

R C Russon

Robert C. Russo Soil Scientist



Natural Resources Conservation Service

Web Soil Survey National Cooperative Soil Survey

,^

MAP LEGEND

Sonil Area		C ciclis oper	Very Stany Spot	ुं Wet Spot	△ Other	Special Line Features	Water Features	Streams and Canals	Transportation	Rails	Interstate Highways			major Noaus	Local Roads Rackground	Aerial Photography	ľ					
Area of Interest (AOI)	Area of Interest (AOI)		Soil Map Unit Polygons	Soil Map Unit Lines	Soil Map Unit Points		Blowout	Borrow Pit	Clav Snot		Closed Depression	Gravel Pit	Gravelly Spot	Landfill	Lava Flow Bac	Marsh or swamp	Mine or Quarry	Miscellaneous Water	Perennial Water	Rack Outcrop	Saline Spot	
Area of In		Soils			厥	Special	9	00	3 é	ξ 4	٥	×	v.*	E 9	rates		K	0	0	Þ	+	

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:12,000

Warning: Soil Map may not be valid at this scale,

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed

Please rely on the bar scale on each map sheet for map measurements. Source of Map: Natural Resources Conservation Service Web Soil Survey URL:

Coordinate System: Web Mercator (EPSG:3857)

distance and area. A projection that preserves area, such as the Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: State of Connecticut Survey Area Data: Version 20, Jun 9, 2020

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger. Date(s) aerial images were photographed: Mar 30, 2011—May 1, 2011

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Severely Eroded Spot

(

Sandy Spot

Slide or Slip

A 10

Sinkhole

(Ç)

Sodic Spot

Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
2	Ridgebury fine sandy loam, 0 to 3 percent slopes	5.6	3.89
3	Ridgebury, Leicester, and Whitman soils, 0 to 8 percent slopes, extremely stony	0.4	0.39
23A	Sudbury sandy loam, 0 to 5 percent slopes	4.1	2.8%
38C	Hinckley loamy sand, 3 to 15 percent slopes	29.8	19.8%
45A	Woodbridge fine sandy loam, 0 to 3 percent slopes	4.9	3.3%
45B	Woodbridge fine sandy loam, 3 to 8 percent slopes	28.7	19.1%
46B	Woodbridge fine sandy loam, 0 to 8 percent slopes, very stony	15.4	10.2%
50B	Sutton fine sandy loam, 3 to 8 percent slopes	6.5	4.3%
51B	Sutton fine sandy loam, 0 to 8 percent slopes, very stony	2.8	1.9%
52C	Sutton fine sandy loam, 2 to 15 percent slopes, extremely stony	1.4	0.9%
61B	Canton and Charlton fine sandy loams, 0 to 8 percent slopes, very stony	9.5	6.3%
2C	Canton and Charlton fine sandy loams, 3 to 15 percent slopes, extremely stony	0.7	0.5%
2D	Canton and Charlton fine sandy loams, 15 to 35 percent slopes, extremely stony	4.6	3.0%
3C	Charlton-Chatfield complex, 0 to 15 percent slopes, very rocky	14.7	9.8%
4C	Paxton and Montauk fine sandy loams, 8 to 15 percent slopes	2.0	1.3%
5B	Paxton and Montauk fine sandy loams, 3 to 8 percent slopes, very stony	3.0	2.0%
03	Rippowam fine sandy loam	13.6	9.1%
05	Udorthents-Pits complex, gravelly	2.5	1.6%

A CANADA BOOK

Map Unit Symbol Map Unit Name Acres in AOI Percent of	
	OI .
Totals for Area of Interest 150,2	100.0%



July 28, 2023

Jana Butts Roberson, AICP
Director of Community Development / Town Planner
Town of Brooklyn
69 South Main Street, Suite 22
Brooklyn, CT 06234

RE: Special Permit Modification

Townsend Development Associates, LLC

SP 15-006

Jana,

Below is an itemized response to the July 5, 2023 and July 10, 2023 Review Comments received from Northeastern Connecticut Council of Governments. For clarity original comments are in normal text and CHA responses are in **Bold**.

July 5, 2023 - Engineering Site Plan & Drainage Report Review

Drawing No. 2 (Sheet 1 of 1) – Improvement Location Plan

1. Are all of the abutting property owners shown on the 2017 plan present today? If not, a new large scale plan or drawing needs to be included in the plan set with current owners, similar to the "inset site installation drawing" included in Drawing No. 13.

Drawing 2 has been updated to revise the current Owners.

Drawing No. 3 – Layout Plan

- 1. Not all sidewalks shown are dimensioned. All sidewalk widths need to be specified on the plan.

 Additional dimensions have been added to the plan set.
- If the sidewalk at the south end of the proposed crosswalk is not flush with the pavement, a sidewalk ramp will need to be constructed there and a construction detail provided — see Type 17 on CT DOT "Sheet 6 – Sidewalk Ramps."

A new sidewalk ramp and detail are now provided.

3. The layout plan is missing some dimensions for curb radii, tangents, aisle widths, loading zone width, etc. All dimensions need to be shown to be able to call this a true layout plan. Scaling dimensions off the plan where no dimensions are shown is unacceptable as this is prone to reading error and distortion in a paper printing process.

Additional dimensions have been added to the plan set.

- 4. The "Commercial Space" building footprint is missing dimensions; however, the "Self Storage" units do have dimensions shown. Add all dimensions to the commercial space.
 - Additional dimensions have been added to the plan set.
- 5. The wood guard rail end treatments on the west side of the development need to be described on this plan or on the Construction Details plan.
 - An end treatment detail has been added to Sheet 11 of the plan set.
- 6. If the wood guard rail is struck by a vehicle, has the impact to the segmental retaining wall adjacent to the posts been evaluated? The distance a post will be located from the back side of the wall needs to be shown in a construction detail. Furthermore, has the condition of the wall been inspected with respect to the development of this project and in consideration of the traffic (vibration) of heavy construction vehicles travelling close by?
 - On similar previous projects, a minimum separation of 3'-3" from the face of retaining wall to the back of the guardrail posts (± 4 ' from face of wall to traffic face of guardrail) has been required by the wall designer/manufacturer to handle the potential impact loads. The location of the proposed guardrail has been moved to be 18-inches from face of curb to face of guardrail, providing at least 4' from face of existing retaining wall to face of proposed guardrail. Notes have been added to the wood guardrail detail to clarify this.

The condition of the existing wall has been visually inspected, and no apparent defects were noted. This wall is the result of modern construction (c. 2007) associated with the original development approval granted to Townsend Development Associates, and was originally intended to have the paved roadway immediately adjacent to the back of the wall. The completion of the site development is not anticipated to negatively impact the existing wall.

- 7. If a tractor-trailer truck will be delivering merchandise/supplies to the restaurant and commercial space, a diagram needs to be submitted showing that it can maneuver throughout the site, especially for the 60± foot long loading zone to the rear of the restaurant portion of the proposed building.
 - A Turning Demonstration Plan has been added to the Plan Set.
- 8. Will this development be phased construction?

At this time, it is anticipated that the Self-Storage facility would begin construction as soon as feasible following anticipated approvals. The Commercial Space is still seeking defined tenants and would likely follow a construction season, or more, behind.

Drawing No. 4 – Grading Plan

- Elevations need to be shown for the top of wall on each side of the Loading Zone.
 Provided.
- 2. What does the bold line around the scour hole at the rear of the property represent? This needs to be clarified on the plan.
 - This line has been removed.



3. Elevations on the entire top of the existing wall at the west boundary of the property need to be included on the plan.

Existing top of wall elevations are now provided.

4. There is inadequate information identifying existing contour lines to evaluate the proposed grading. The plan must be updated to include existing elevations on all existing contour lines and resubmitted for review.

Additional contour labels have been added.

Drawing No. 5 - Drainage Plan

1. Direction of flow arrows need to be included on the plan.

Flow arrows have been added to the plan set.

Drawing No. 6 - Utility Plan

1. For the restaurant operation, it is not evident from the plan where a bulk fat/oil/grease (FOG) recovery tank will be located on the site close to the restaurant. This location needs to be added to the plan in an enclosed area.

The Dumpster Area has been expanded to accommodate this tank.

2. Who is going to be responsible for the maintenance of certain utilities (water, gas, electric, telephone, cable, etc.) on site? If utility companies will be responsible for maintenance and ownership, are easements necessary for their infrastructure on private property? If so, they need to be shown on the plan similar to the sewer maintenance easement.

Utility Providers already have mains extended onto the property. Based on initial conversations with Connecticut Water and Eversource, easements are not expected to be required for the service connections.

3. In addition to the Brooklyn Water Pollution Control Authority, has the Killingly Water Pollution Control Authority provided written approval on accepting the additional anticipated sewage flow for from the proposed development?

The proposed Project has not yet been reviewed by the Brooklyn or Killingly WPCA; however, the proposed development represents a decrease in anticipated flows based on the previously approved developments, as the Self-Storage facility will not generate any discharge.

Drawing No. 9 - Construction Details

1. In the "1,000 Gallon Grease Trap" detail, add a note that it is H20 load rated. Also, show risers at each access opening noting material spec and dimensions. It is not anticipated that buoyancy needs to be taken into account.

Provided.



Drawing No. 11 – Construction Details

- The "Depressed Curb Ramp" detail is lacking information in order to construct it. The ramp needs a
 "landing" and shall be modeled after a Connecticut Department of Transportation (CT DOT) 48" wide
 ramp with landing detail drawing that can be found on their "Sheet 1 Sidewalk Ramps."
 CT DOT details are now provided.
- 2. In the "Typical Cross Section for Matching Existing and Proposed Pavement," the thickness of the new pavement is shown to be 3¼". Is this correct, as I have never ever seen pavement thickness called out to the quarter (1/4) inch? Incidentally, in the "Bituminous Concrete Pavement" detail, the total pavement thickness is only three (3) inches. Which detail is correct?

The Matching Existing and Proposed Pavement detail has been modified to 3-inches.

- 3. Any reference to State of Connecticut Department of Transportation Form 816 shall be changed to the most recent publication, Form 818.
 - References to 816 have been revised to 818 throughout.
- 4. In the "Concrete Encasement" detail, the length of concrete encasement on each side of the centerline of the crossing needs to be specified.
 - A note has been added to the detail.
- In the "Wood Guard Rail" detail, the depth of bury of the wood post needs to be specified as well as typical spacing between posts. Also, metal fasteners need to be specified as stainless steel.
 Depth of Bury and spacing for the posts are now specified.
- 6. Termination ends of the guard rail need to be shown in a construction detail.

 A detail is now provided on Sheet 11 of the plan set.
- 7. There is a "Finish Course Standard Mold 6" Concrete Lip Curbing Detail" on this plan sheet, however, where this is located is not shown on any of the site plans. Where is this used? If it is not used it should be removed.

This detail is for the Extruded Concrete Curb proposed for the site. The title of the detail has been revised for clarity.

Drawing No. 13 – E&S Control and Stormwater Maintenance Plan

1. Any reference to State of CT DOT Form 816 shall be changed to the most recent publication, Form 818. **References to 816 have been revised to 818 throughout.**



2. Straw wattles need to be installed in a shallow trench due to their light weight, which minimizes movement from heavy rain. Furthermore, the contractor responsible for digging the trench may neglect to dig the trench and will result in an improper installation. To avoid this and for better sediment control, replace straw wattles with silt socks, which are heavier and do not require a shallow trench to install but do need to be staked when installed on a bed of earth, and revise the detail and inset site installation drawing to reflect this.

The straw wattle has been replaced with a silt sock as suggested.

3. The "construction entrance pad" location in the site inset drawing is unacceptable. It is in conflict with traffic movements generated by the existing pharmacy (Lot 16-2) and existing commercial space. Movement of heavy equipment to and from the construction site presents a safety hazard, accumulation of site debris (mud, rocks, etc.) that have the potential to damage customer vehicles, has a tight if not undoable turning egress movement, and poses an impediment to active businesses. The construction entrance needs to be relocated to the paved driveway with a center island along the west boundary line of the site to be developed to minimize these impacts as much as possible.

Construction Entrance has been relocated as indicated.

Drainage Report

1. No comments.

Acknowledged.

July 10, 2023 - Drainage Report Review for Compliance with Zoning Regulation 7.H. - Stormwater Management

7.H.3.1a. Pollutant Reduction in accordance with 2004 Connecticut Stormwater Quality Manual (CSQM) Section 7.4

1. The CHA Drainage Report addresses pollutant reduction with Water Quality Volume calculations using the CSQM formula.

Acknowledged.

7.H.3.1b. Groundwater Recharge and Runoff Volume Reduction in accordance with 2004 Connecticut Stormwater Quality Manual Section 7.5

1. A "groundwater recharge calculation" could not be found in the Drainage Report. CHA needs to address this and submit this as an addendum to their Report.

It should be noted that the expanded drainage system serving this development is a "closed system," having one outlet in an existing swale along the north edge of the property, which flows in a northwesterly direction to a wetland. However, the swale and wetland will provide an unknown quantity of groundwater recharge.

The "runoff volume reduction" is in the Report but not identified as such and utilizes an identical calculation as the "water quality volume" formula in the CSQM and also found in the CHA Report. In essence, they are one in the same.

Pursuant to the design calculations prepared by J&D (attached and included in the Drainage Report) the design of the water quality swales included "Full Build Out of Klotz Property". Based



on these calculations, the Retention Basin (serpentine swale) provides water quality treatment (and recharge) of ±42,000 CF, based on 0.5-inches of runoff from ±21 acres of collected impervious area, that was previously untreated. Pursuant to the CSQM Section 7.5.1, the required Groundwater Recharge Volume for sites on Hydrologic Soil Group 'B' (portion of the developed lot is mapped as 'D') would be 0.25-inches from the impervious areas. Therefore, the existing water quality swale is believed to satisfy the groundwater recharge volume requirements for the proposed development.

7.H.3.1c. Peak Flow Control in accordance with 2004 Connecticut Stormwater Quality Manual Section 7.6 for the 10-year, 25-year and 100-year storm events

1. The Drainage Report provides calculations for the 2, 10, 25 and 100-year storm events for the post-development condition. The Report does not evaluate the pre-development condition that would be used to see if the "peak flow control" is met. However, in the Summary of the consultant's Report it is stated that "As part of an agreement between a previous property Owner and the Town of Brooklyn (see Section G), the proposed stormwater treatment system is not required to attenuate peak flows versus existing conditions, but must only treat the runoff for water quality (80% Total Suspended Solids removal). Because peak stormwater flow reduction is not a requirement, pre-development stormwater analysis has not been provided."

I believe this agreement pertains to the serpentine water quality basin to the rear of the Berkshire Bank and is not applicable to this project, which does not empty into the serpentine basin—the basin only treats drainage captured along Providence Road (Route 6) collected in the State of Connecticut drainage system. I base this on what I have gleaned from the plans and evaluation of the serpentine basin included in the CHA Report, especially the J&D Civil Engineers' report "Evaluation and Selection of BMP's," dated April 2003 with revision date of May 2003, which was to be used as a part of a Town of Brooklyn Stormwater Management Plan.

Because the drainage from the expansion of development on the Townsend property does not empty into the serpentine basin, it is my opinion that the consultant needs to calculate the pre- development condition to evaluate existing condition vs. the developed condition to meet the requirement of 7.H.3.1c. and submit it for review.

The Drainage and Conservation Easement Documents, included as an attachment to the Drainage Report, include:

- Drainage and Conservation Easement (on file in the Town's Land Records, Book 365 Pages 0285 through 0288)
- 2. Sheets 4 and 5 of the Plan Set entitled "Klotz Property Regional BMP's, Town of Brooklyn, CT, Stormwater Management Plan, Prepared by J&D Civil Engineers, Dated June 2003.
- 3. Evaluation and Selection of BMP's, Town of Brooklyn Stormwater Management Plan, Prepared by J&D Civil Engineers, Dated April 2003, Revised June 2003.

Based on these documents, and the previous approvals granted for development of the Townsend Development Property, the Applicant, and their Consulting Engineer, believe that both the serpentine swale and the linear swale along the northern boundary are included in this agreement and that the only stormwater treatment required of the development is pretreatment prior to



discharge to the Town's Regional Water Quality Swales. The following excerpts from the Drainage and Conservation Easement are provided to support this, with commentary in italics below:

Article I Grantor's Rights and Responsibilities, Item a. states: "The Grantor shall allow the
Grantee to construct the water quality swales as shown on the plan entitles, "Klotz
Property Regional BMP's, Town of Brooklyn, CT Stormwater Management Plan Sheets 4 &
5, by J&D Civil Engineers, Scale 1" = 40', dated June 30, 2003.

Sheet 4 of the J&D Plan Set clearly shows both swales being constructed on the Townsend Development Property, and Sheet 5 includes cross sections of both swales.

Also noted:

- 1. The Limits of the Easement described in Schedule 'A' (Book 365, Page 289, attached) and depicted on the existing conditions plan, clearly include the limits of both swales.
- 2. This Item of the Easement indicates swales (plural) where other items (Article 1.c. for example) are singular and specific to one swale.
- 3. Both Swales were constructed at the same time by the same Contractor and would require the Town to have an easement for construction on private property.
- Article I Grantor's Rights and Responsibilities, Item f. states: "Grantor shall have the right
 to discharge its stormwater runoff into the water quality swales and the drainage and
 conservation easement in one or more locations subject to the approval of appropriate
 Town Commissions.
- Article I Grantor's Rights and Responsibilities, Item g. states: "Grantor shall provide pretreatment of stormwater from the developed portion of the Grantor's property prior to discharging to the water quality swales. The following performance standards for stormwater discharge shall apply.
- Stormwater management conveyance systems must be designed to remove 80% on the annual average load of Total Suspended Solids (TSS). It shall be presumed that this standard is met when stormwater management best practices (BMPs) are sized to treat 0.5 inches of runoff times the impervious area of the post-development project site. TSS removal rates of BMPs must be documented from current EPA or Connecticut DEP design guidelines.
- 2. Rooftop runoff except from flat industrial roofs made of galvanized metal or copper, may be considered uncontaminated and not require pre-treatment prior to discharge to the drainage and conservation easement.
 - Article II Grantee's Rights and Responsibilities, Item c. states: "To allow the Grantor to discharge stormwater from the developed portion of the property into the Town's regional stormwater quality swales in one or more locations subject to the approval of appropriate Town Commissions. The Grantor shall not be required to construct stormwater detention facilities to reduce peak discharges.



July 28, 2023 Townsend Response to Comments Page **8** of **8**

7.H.3.2.

The CHA drainage design incorporates an additional Hydrodynamic Separator to one that already
functions in the existing drainage system and some hooded catch basins will be constructed. These
enhancements to the drainage system serve to reduce Total Suspended Solids, hydrocarbons and other
deleterious floatables from discharging into the environment at the system outfall.

Acknowledged.

7.H.4. Modifications

1. To the best of my knowledge, CHA has not requested any modifications or waivers involving the stormwater system.

Acknowledged, no modifications or waivers are requested.

Please contact me (parent@chacompanies.com, 860-885-1052) if you have any questions or additional comments.

Thank You,

Pete Parent, P.E.



STATE OF CONNECTICUT

	COUNTY OF NEW LONDON)				
	PATTERSON CORPORATION, signer	S KLOTZ, President of THE DOWNES- r and sealer of the foregoing instrument and act and deed, and the free act and deed of THE ON, before me.			
•		C1.00.11.L			
		Commissioner of the Superior Court Notary Public			
	STATE OF CONNECTICUT)	_			
	COUNTY OF WINDHAM)	<u>luguer 2, 2005</u>			
	BROOKLYN, signer and scaler of the f	of the TOWN OF foregoing instrument and acknowledged the same rice act and deed of the TOWN OF BROOKLYN,			
		Show Colons			
		Commissioner of the Superior Court			
		Notary Public wing (10, 7) and 10 311			
. 7	7	Attachment A			
	No. Grosvenordale, CT, entitled "Commission	assument: A tract of land shown as "Drainage and of Brooklya" on a plan prepared by I &t D Civil Engineers, a Plan showing Drainage and Conservation Ensurement to be Patterson Corporation, Roote 6 East Main Street, " = 50" bounded and described as follows:			
	Beginning at the north westerly corner of herein described drainings and conservation encountait, bounded northerly by n/f Town of Brooklyn and westerly by n/f Kennoth and Condy Cardinal;				
	Thence N 70° 13' 16" E 707.58' to an iron pipe;				
	Theore N 70° 13' 16" E \$1.17' to a point which is the north cost corner of said exercent;				
	Thouse \$ 19° 54' 12" E 35.00' to a point;				
	Thence 2 70° 13' 16" W 509.11' to a point;				
	Thence \$ 20° 24' 11" W 196.48' to a point;	•			
	Thence \$ 19° 49' 27" E 240.00' to a point;	•			
	Thenes \$ 70° 10' 33" W 185.51' to a point,				
٠	Thence N 15" 25' 28" W 367.33' to see iron;	p ipe,			
	Themes N 15° 25' 28" W 59.16' to the corne	r at the point of beginning.			
	•				

)B N ATE YP		ENGINEERS Of RAVENELLE ROAD Oorth Grosvenordale, CT 06255	SHEET NO: 10FZ JOB SUBJECT_DRAINAGE
⊀'D	9 BY(8	ALITY CALCULATION	CLIENT BROOKLYN
,	SEE WATERSHED		
	INSTALL STRUCTU DEVELOPMENT 1 F-2 1 E.	LARGE WETLAND I	REPU COMMERCIAL N DRAWAGE BASINS
	TOTAL DRAINAGE	APEA UP TO W	SI OHAJTE
t	22 AC (F-1).	+ 17 AC = 39 (PORTION F-2 UP T	AC OWETUAD)
	FOR RUNOFF VO	(WQV)	ATED TO WATER QUALITY
: !	IMPERVIOUS A	(REAT = ZI ACRES	JAN2
	* ASSUMES	FULL BUILD OUT O	F KLOJZ PROJEFTY
	· IF TREAT O.	5 IN RUNOFF VO	DLUME TO BE TREATED:
	(0.5 17)	(21 AC) 43S60 FT ² AC	$= \frac{38,115 \text{ Ft}^3}{}$
	· ·		= 0.88 A C-FT
		" PUNOFF VOLUM	E =
	<u>7</u> 1.	6,230 FT ³ 75 AC-FT	
	FOR WQU TQ	BETREATED FOR S	EDIMENT TRAP

FOR WQV TO BETREATED FOR SEDIMENT TRAP

(FOREBAY) FROM 'JOB LOT' PROPERTY

IMPERVIOUS D.A = 6.8 AC

MA DEP GUIDLINES RECOMMEND TREATING O.I"

O.I IN (6.8 AC) (43560 FT²) (FT)

12 IN (AC)

JOB NO	T Q_ T CIVIL	SHEET NO. 2 OF 7
DATÉ	J & D ENGINEERS	JOB .
BY	401 RAVENELLE ROAD	SUBJECT
CH'D BY	North Grosvenordale, CT 06255 (860) 923-2920 FAX (860) 923-3487	CLIENT

DESIGN SEDIMENT FOREBAY FOR PUNOFF FROM JOB LOT PLAZA

COMMENTS: CONC BOTTOM PREFERABLE FOR MAINTAINENCE

OPEN UNIT EASIER TO MAINTAIN BUT NOT AS SAFE

IF DEPTH = 4' THE BOTTOM AREA = $\frac{2470}{4}$ = 617 FT²
OR ABOUT 15' × 40'

WITH THIS LARGE SIZE CONC BOTTOM OR CLOSED UNITS PROBABLY NOT FINANCIALLY FEASIBLE OPEN, RIPPAP UNIT SIMILAR TO

SEE DESIGN PLAN: SET BOTTOM ELEV @ 221 W/ OVERFLOW EL INTO STORMWATER QUALITY SWALE @ 225,0

CHECK SIZE OF WATER QUALITY SWALE

EFFECTIVE SIZE FROM EL 218-222

ELEV.	AREA(FT2)	AVE AREA	YOL(F)	(3) COM VOL (F
218	3100		0	
220	9820	6460	12,920	12,920
222	19,440	14,630	29,260	42,180

> 38,115 .. OK= 42,180 FT3

Northeastern Connecticut Council of Governments

DRAINAGE REPORT REVIEW FOR COMPLIANCE WITH ZONING REGULATION 7.H. — STORMWATER MANAGEMENT PERTAINING TO A SPECIAL PERMIT SITE DEVELOPMENT PLAN (ASSESSOR'S MAP 41, LOT 16) PROVIDENCE ROAD (ROUTE 6) BROOKLYN, CT

(July 10, 2023)

The comments contained herein pertain to my review of a Drainage Report, consisting of four hundred fifty-five (455) pages Prepared for Townsend Development Associates, LLC, Providence Road (Route 6), Brooklyn, Connecticut, Dated: May 24, 2023," prepared by engineering consultant CHA. The purpose of this review is to determine whether or not portions of Brooklyn Zoning Ordinance 7.H., Stormwater Management, have been met for this commercial project.

7.H.3.1a. Pollutant Reduction in accordance with 2004 Connecticut Stormwater Quality Manual (CSQM) Section 7.4

The CHA Drainage Report addresses pollutant reduction with Water Quality Volume calculations using the CSQM formula.

7.H.3.1b. Groundwater Recharge and Runoff Volume Reduction in accordance with 2004 Connecticut Stormwater Quality Manual Section 7.5

A "groundwater recharge calculation" could not be found in the Drainage Report. CHA needs to address this and submit this as an addendum to their Report.

It should be noted that the expanded drainage system serving this development is a "closed system," having one outlet in an existing swale along the north edge of the property, which flows in a northwesterly direction to a wetland. However, the swale and wetland will provide an unknown quantity of groundwater recharge.

The "runoff volume reduction" is in the Report but not identified as such and utilizes an identical calculation as the "water quality volume" formula in the CSQM and also found in the CHA Report. In essence, they are one in the same.

7.H.3.1c. Peak Flow Control in accordance with 2004 Connecticut Stormwater Quality Manual Section 7.6 for the 10-year, 25-year and 100-year storm events

The Drainage Report provides calculations for the 2, 10, 25 and 100-year storm events for the post-development condition. The Report does not evaluate the pre-development condition that would be used to see if the "peak flow control" is met. However, in the Summary of the consultant's Report it is stated that "As part of an agreement between a previous property Owner and the Town of Brooklyn (see Section G), the proposed stormwater treatment system is not require to attenuate peak flows versus existing conditions, but must only treat the runoff for water quality (80% Total Suspended Solids removal). Because peak stormwater flow reduction is not a requirement, pre-development stormwater analysis has not been provided."

I believe this agreement pertains to the serpentine water quality basin to the rear of the Berkshire Bank and is not be applicable to this project, which does not empty into the serpentine basin—the basin only treats drainage captured along Providence Road (Route 6) collected in the State of Connecticut drainage system. I base this on what I have gleaned from the plans and evaluation of the serpentine basin included in the CHA Report, especially the J&D Civil Engineers' report "Evaluation and Selection of BMP's," dated April 2003 with revision date of May 2003, which was to be used as a part of a Town of Brooklyn Stormwater Management Plan.

Because the drainage from the expansion of development on the Townsend property does not empty into the serpentine basin, it is my opinion that the consultant needs to calculate the predevelopment condition to evaluate existing condition vs. the developed condition to meet the requirement of 7.H.3.1c. and submit it for review.

7.H.3.2.

The CHA drainage design incorporates an additional Hydrodynamic Separator to one that already functions in the existing drainage system and some hooded catch basins will be constructed. These enhancements to the drainage system serve to reduce Total Suspended Solids, hydrocarbons and other deleterious floatables from discharging into the environment at the system outfall.

7.H.4. Modifications

To the best of my knowledge, CHA has not requested any modifications or waivers involving the stormwater system.

By: Syl Pauley, Tr., P.E.


Syl Pauley, Jr., P.E., NECCOG Regional Engineer


SPECIAL PERMIT SITE DEVELOPMENT PLAN


PREPARED FOR

TOWNSEND DEVELOPMENT ASSOCIATES, LLC


PROVIDENCE ROAD (U.S. ROUTE 6) BROOKLYN, CONNECTICUT MAY 5, 2023 REVISED JULY 21, 2023







Drawing Copyright © 2015 400 Capital Boulevard, Suite 301 Rocky Hill, CT 06067 860-257-4557 | www.chacompanies.com



PROPERTY OWNER & APPLICANT: TOWNSEND DEVELOPMENT ASSOCIATES, LLC

BROOKLYN, CT 06234

ZONING DISTRICT: PC = PLANNED COMMERCIAL ZONE

EXISTING USES: COMMERCIAL/MEDICAL OFFICE

PROPOSED USES: 19,640 S.F. COMMERCIAL SPACE 16,100 S.F. SELF STORAGE SPACE

DIMENSIONAL REQUIREMENTS			
ZONING CRITERIA REQUIRED PROVIDED			
LOT SIZE	30,000 SF	±326,125 SF	
LOT FRONTAGE	100 FEET	65.92 FEET (REAR LOT)	
FRONT YARD SETBACK	30 FEET / 45 FEET*	50.8 FEET	
SIDE YARD SETBACK	20 FEET	30.4 FEET	
REAR YARD SETBACK	20 FEET	105.7 FEET	
LOT COVERAGE	65% IMPERVIOUS	±54% IMPERVIOUS	
BUILDING HEIGHT	30 FEET / 40 FEET**	<30 FEET	

* IF PARKING OR DRIVEWAY IS BETWEEN BUILDINGS AND STREET ** 30' FOR 1 & 2 STORY BUILDINGS, 40' FOR 3 STORY BUILDINGS

SELF STORAGE REQUIREMENTS		
ZONING CRITERIA REQUIRED PROVIDED		
LOT	SITED ON A REAR LOT	SITED ON A REAR LOT
SETBACK	150' TO STREET LINE	>200' TO PLAZA STREEET
DENSITY	4,000 SF/ACRE	±1,965 SF/ACRE
MAXIMUM BUILDING SIZE	>20,000 SF	8,400 SF

PARKING CALCULATIONS			
BUILDING PARKING REQUIREMENT SPACES REQUIRED SPACES PROVIDE			SPACES PROVIDED
RETAIL USES (7.B.2.2)		38 SPACES	
PERSONAL SERVICES USES (7.B.2.2)	3 SPACES PER 1,000 SF	8 SPACES (EXISTING USE)	
LICENSED HEALTH SERVICES (7.B.2.4)		8 SPACES (EXISTING USE)	
RESTAURANT USES (7.B.2.5)	1 SPACE PER 3 SEATS	80 SPACES (ASSUMING 240 SEATS)	
	TOTAL	134 SPACES	134 SPACES (41 EXISTING)

PER ADA STANDARDS, PARKING AREAS WITH 101 TO 150 PARKING SPACES MUST PROVIDE A MINIMUM OF 5 ACCESSIBLE PARKING SPACES. THERE ARE 3 EXISTING AND TWO PROPOSED ACCESSIBLE SPACES TO MEET THIS REQUIREMENT.

ADJACENT POTENTIAL OVERFLOW PARKING			
BUILDING	BUILDING GROSS SQUARE FOOTAGE SPACES REQUIRED SPACES PROVIDED		
PHARMACY PRIOR APPROVAL	13,225 SF	67 SPACES	73 SPACES
BANK PRIOR APPROVAL	3,000 SF	15 SPACES	21 SPACES
	TOTAL	83 SPACES	94 SPACES

PER SECTION 8-26c OF THE <u>CONNECTICUT GENERAL STATUTES</u>, AS AMENDED APPROVAL AUTOMATICALLY EXPIRES ______, IF ALL PHYSICAL IMPROVEMENTS REQUIRED BY THIS PLAN ARE NOT COMPLETE BY THIS DATE.

REVIEWED BY THE TOWN ENGINEER


FIRST SELECTMAN DATE


ENDORSED BY THE BROOKLYN INLAND WETLANDS COMMISSION


CHAIRMAN OR SECRETARY


APPROVED BY THE BROOKLYN PLANNING & ZONING COMMISSION


CHAIRMAN OR SECRETARY
































BACKFILL -


ROOTBALL ON

UNDISTURBED

SUBGRADE

1. AFTER THE GUARANTEE PERIOD THE CONTRACTOR WILL BE RESPONSIBLE FOR THE REMOVAL OF STAKES AND GUY WEBBING.

EVERGREEN TREE PLANTING DETAIL



FINISH GRADE

PLANT WITH

SHRUB'S ROOT

FINISH GRADE

2 x ROOTBAL

DIAMETER (MIN)

SHRUB PLANTING DETAIL

NOT TO SCALE

COLLAR 2" ABOVE

- CUT AND REMOVE BURLAP


AND WIRE BASKET FROM

TOP 1/3 OF ROOTBALL.

FOLD UNDER, SO AS NOT


TO EXPOSE ABOVE GRADE

NOT TO SCALE




NOTE: LOCATE BEDLINE AS SHOWN ON PLAN.

BEDLINE EDGE DETAIL NOT TO SCALE



CONTAINER GROWN TREE AND SHRUB PLANTING DETAIL NOT TO SCALE



PERENNIAL PLANTING DETAIL NOT TO SCALE

REVIEWED BY THE TOWN ENGINEER FIRST SELECTMAN DATE

ENDORSED BY THE BROOKLYN INLAND WETLANDS COMMISSION

CHAIRMAN OR SECRETARY DATE

APPROVED BY THE BROOKLYN PLANNING & ZONING COMMISSION

CHAIRMAN OR SECRETARY DATE

GENERAL NOTES:

ALL PLANT MATERIAL MUST BE TAGGED IN THE GROUND, AT THE NURSERY BY THE LANDSCAPE ARCHITECT. ALL PLANT MATERIAL SHALL BE COMMERCIALLY OBTAINED AND SHALL MEET THE AMERICAN ASSOCIATION OF NURSERYMAN STANDARDS FOR NURSERY STOCK, LATEST EDITION, AND ITS AMENDMENTS. PLANT ONLY DURING SEASON NORMAL TO THE PARTICULAR VARIETY. ALL PLANT INSPECTIONS WILL BE AT THE EXPENSE OF THE CONTRACTOR. PERMANENT SEALS WILL BE REQUIRED.

- 2. COVER ALL PLANTING BEDS WITH 3" SHREDDED HARDWOOD BARK MULCH WITHIN A SEVENTY-TWO HOUR PERIOD AFTER PLANTING. SEE PLAN FOR BED LAYOUT.
- 3. ALL EXISTING AND PROPOSED TREES SHOWN IN LAWN AREAS SHALL RECEIVE A 6' DIAMETER MULCH BED. MULCH SHALL BE PLACED TO A DEPTH OF 3". REMOVE ALL SOD, ROOTS, STICKS AND STONES PRIOR TO PLACEMENT OF
- 4. ALL PLANT MATERIALS FURNISHED BY THE CONTRACTOR SHALL BE GUARANTEED FOR A PERIOD OF ONE YEAR FROM FINAL ACCEPTANCE OF LANDSCAPE WORK.
- 5. STAKE ALL TREES OVER 5' AS SHOWN ON DETAILS.
- 6. REMOVE STAKES AT THE END OF THE GUARANTEE PERIOD.
- 7. THE CONTRACTOR IS RESPONSIBLE FOR KEEPING THE SITE CLEAN OF MISCELLANEOUS DEBRIS THROUGHOUT THE CONSTRUCTION PERIOD. ALL WASTE MATERIAL IS TO BE DISPOSED OF IMMEDIATELY TO AN OFF-SITE LOCATION, UNLESS OTHERWISE INDICATED ON THE PLANS.
- 8. THE CONTRACTOR SHALL PERFORM ALL WORK IN ACCORDANCE WITH ALL LOCAL, STATE, AND FEDERAL REGULATIONS, AND SHALL OBTAIN ALL NECESSARY PERMITS FOR THIS PROJECT.
- 9. LAYOUT: ALL NOTES AND DIMENSIONS ARE TYPICAL UNLESS OTHERWISE NOTED. ALL DIMENSIONS ARE SQUARE (PARALLEL OR PERPENDICULAR) UNLESS OTHERWISE NOTED. THE CONTRACTOR SHALL NOTIFY THE OWNER/OWNER'S REPRESENTATIVE IMMEDIATELY IN THE EVENT OF ANY DISCREPANCIES FOUND IN THE CONTRACT DOCUMENTS AND/OR IN THE FIELD, OR OF CONDITIONS UNCOVERED IN THE WORK WHICH ARE NOT REFLECTED IN THE PLANS.
- 10 LOAM: LOAM MOVED DURING THE COURSE OF CONSTRUCTION SHALL BE RETAINED AND DISTRIBUTED WITHIN THE SITE IN ACCORDANCE WITH THE LANDSCAPE PLAN. STOCKPILED LOAM SHALL NOT BE MIXED WITH ANY SUBSOIL OR UNSUITABLE MATERIALS. ALL EXCESS LOAM SHALL REMAIN ON THE PROPERTY OF THE OWNER. NEW LOAM IF REQUIRED TO PROVIDE THE SPECIFIED DEPTH, SHALL BE A FERTILE, FRIABLE MEDIUM TEXTURED SANDY LOAM FREE OF MATERIAL TOXIC TO HEALTHY PLANT GROWTH. LOAM SHALL ALSO BE FREE OF ALL STUMPS, ROOTS, STONES AND OTHER EXTRANEOUS MATTER AN INCH (1") OR GREATER IN DIAMETER. THE PH SHALL BE BETWEEN 5.5 AND 7.5 WHEN TESTED.
- 11. LAWN PREPARATION: REMOVE ALL DEBRIS AND OTHER INORGANIC MATERIALS ON THE PREPARED SUBGRADE, RESHAPE AND DRESS ANY DAMAGED OR ERODED AREA PRIOR TO SPREADING THE LOAM. SCARIFY AND LOOSEN SUBGRADE IN ANY AREAS WHERE COMPACTION MAY HAVE OCCURRED. SPREAD STOCKPILED AND OFF-SITE LOAM ON ALL DISTURBED AREAS TO PRODUCE A DEPTH OF 6". FINE GRADE LOAMED AREAS TO PRODUCE A SMOOTH AND UNBROKEN FINISH GRADE TO THE REQUIRED DEPTH. APPLY A STARTER FERTILIZER (10-20-10) AT A RATE OF 20 LBS. PER 1000 SQUARE FEET AND LIME AT A RATE OF 40 LBS. PER 1000 SQUARE FEET. ONCE SPREAD, THE FERTILIZER AND LIME SHALL BE THOROUGHLY INCORPORATED INTO THE LOAM. THE LOAM SHALL BE ROLLED, AND DEPRESSION SHALL BE TOP DRESSED AND RAKED IO CREAIE A SMOOTH SURFACE.
- 12. PROTECTION OF EXISTING PLANTINGS: MAXIMUM EFFORT SHOULD BE MADE TO SAVE TREE OR OTHER PLANT SPECIMENS WHICH ARE LARGE FOR THEIR SPECIES, RARE TO THE AREA, OR OF SPECIAL HORTICULTURAL OR LANDSCAPE VALUE, CONTACT OWNER/LANDSCAPE ARCHITECT BEFORE REMOVING ANY SPECIMEN OF THIS TYPE UNLESS OTHERWISE NOTED ON THE PLANS. NO MATERIAL OR TEMPORARY SOIL DEPOSITS SHALL BE PLACED WITHIN THE DRIP LINE OF SHRUBS OR TREES DESIGNATED ON THE LANDSCAPE PLAN TO BE RETAINED. PROTECTIVE BARRIERS ARE TO BE INSTALLED AROUND EACH PLANT AND/OR GROUP OF PLANTS THAT ARE TO REMAIN ON THE SITE. BARRIERS SHALL NOT BE SUPPORTED BY THE PLANTS THEY ARE PROTECTING, BUT SHALL BE SELF SUPPORTING. THEY SHALL BE OF MINIMUM OF FOUR FEET (4') HIGH AND CONSTRUCTED OF A DURABLE MATERIAL, SUCH AS SNOW OR SILT FENCE, THAT WILL LAST UNTIL CONSTRUCTION IS COMPLETED.
- 13. PRUNING: THE CONTRACTOR SHALL CAREFULLY PRUNE BRANCHES IN THE WAY OF CONSTRUCTION BY USING ONLY APPROVED METHODS AND TOOLS. THE USE OF AXES FOR TRIMMING OR SPURS FOR CLIMBING WILL NOT BE PERMITTED.
- 14. EXISTING UTILITIES: IN ACCORDANCE WITH "CALL BEFORE YOU DIG" AT (1-800-922-4455), THE CONTRACTOR SHALL CONTACT ALL APPLICABLE UTILITY COMPANIES AND VERIFY UTILITY LINE LOCATIONS. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ANY/ALL UTILITY DAMAGE. RECORD LOCATIONS OF "CALL BEFORE YOU DIG" UTILITY LINE MARKINGS ON PROJECT RECORD DOCUMENTS.
- 15. DISTURBED AREAS: ANY AREAS DISTURBED DURING THE COURSE OF CONSTRUCTION ARE TO BE RESTORED TO ORIGINAL (OR BETTER) CONDITION BY CONTRACTOR BEFORE COMPLETION OF THE PROJECT, AND ARE SUBJECT TO APPROVAL BY LANDSCAPE ARCHITECT AND OWNER. ALL GRASS AREAS DISTURBED DURING CONSTRUCTION SHALL BE YORK RAKED TO REMOVE STONES AND LOAMED AND SEEDED AS PER SPECIFICATIONS.
- 16. DRAINAGE SYSTEMS: CONTRACTOR IS RESPONSIBLE FOR GENERAL CLEAN-OUT OF ALL CATCH BASINS, MANHOLES, AND/OR OTHER DRAINAGE FEATURES ON THE SITE WHICH HAVE ACCUMULATED SEDIMENT AS A RESULT OF CONSTRUCTION ACTIVITIES.
- 17. CLEANING: CONTRACTOR IS RESPONSIBLE FOR KEEPING SITE CLEAN OF MISCELLANEOUS DEBRIS THROUGHOUT THE CONSTRUCTION PERIOD. ALL WASTE MATERIAL IS TO BE DISPOSED OF IMMEDIATELY TO AN OFF-SITE LOCATION, UNLESS OTHERWISE INDICATED ON THE PLAN.
- 18. PLANT MATERIAL SUBSTITUTIONS ALL PLANT SUBSTITUTIONS ARE SUBJECT TO APPROVAL BY LANDSCAPE ARCHITECT AND OWNER.
- 19. IRRIGATION TO BE PROVIDED ON ALL PLANTING BEDS AND LAWN AREAS. IRRIGATION PLAN BY OTHERS.

No. Submittal / Revision App'd. By Date

PMP 07/21/202

REVIEW COMMENTS

Drawing Copyright © 2015

Rocky Hill, CT 06067

860-257-4557 | www.chacompanies.com

SITE DEVELOPMENT PLAN

PREPARED FOR:

TOWNSEND

DEVELOPMENT

ASSOCIATES

PROVIDENCE ROAD (RT 6)


BROOKLYN, CT


IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY AR ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, ARCHITECT, LANDSCAPE ARCHITECT OR LAND SURVEYOR TO ALTER AN ITEM IN ANY WAY, IF AN ITEM BEARING STAMP OF A LICENSED PROFESSIONAL IS ALTERED, THE ALTERIS ENGINEER, ARCHITECT, TO LAND SURVEYOR SHALL STAMP THE DOCUMENT AND INCLUDE THE NOTATION "ALTERED BY" FOLLOWED BY THEIR SIGNATURE, THE DATE OF SUCH ALTERATION, AND A SPECIFIC DESCRIPTION OF THE ALTERATION.

CONSTRUCTION DETAILS

Designed By: Drawn By: Checked By: PMP Issue Date: | Project No: | 05/05/2023 AS NOTE 080849

Drawing No.:





SITE DEVELOPMENT PLAN PREPARED FOR: TOWNSEND DEVELOPMENT **ASSOCIATES** PROVIDENCE ROAD (RT 6) BROOKLYN, CT

Drawing Copyright © 2015

Rocky Hill, CT 06067

860-257-4557 | www.chacompanies.com


IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, ARCHITECT, LANDSCAPE ARCHITECT OR LAND SURVEYOR TO ALTER AN ITEM IN ANY WAY, IF AN ITEM BEARING TO STAMP OF A LICENSED PROFESSIONAL IS ALTERED, THE ALTERING ENGINEER, ARCHITECT, LANDSCAPE ARCHITECT OR LAND SURVEYOR SHALL STAMP THE DOCUMENT AND INCLUDE THE NOTATION "ALTERED BY" FOLLOWED BY THEIR SIGNATURE, THE DATE OF SUCH ALTERATION, AND A SPECIFIC DESCRIPTION OF THE ALTERATION.

No. Submittal / Revision App'd. By Date REVIEW COMMENTS

E&S CONTROL AND STORMWATER MAINTENANCE PLAN

Designed By: Drawn By: Checked By Issue Date: Project No: Scale: 05/05/2023 080849 AS NOTED

Drawing No.:



SILT FENCE AT TOE OF SLOPE APPLICATION NOT TO SCALE

SILT SOCK INSTALLATION

REVIEWED BY THE TOWN ENGINEER

DATE

FIRST SELECTMAN

ENDORSED BY THE BROOKLYN INLAND WETLANDS COMMISSION

CHAIRMAN OR SECRETARY DATE CHAIRMAN OR SECRETARY DATE

APPROVED BY THE BROOKLYN PLANNING & ZONING COMMISSION

THIS PROJECT CONSISTS OF THE CONSTRUCTION OF 35,600 SF OF RETAIL/OFFICE SPACE AND A 5,000 SF RESTAURANT ON ±9.8 ACRES IN THE TOWN OF BROOKLYN, CONNECTICUT. THE LOCATION OF THE SITE IS ON THE NORTH SIDE OF PROVIDENCE ROAD (RT 6) APPROXIMATELY 1,300 FEET WEST OF DAY STREET. THIS PROJECT WILL CONSIST OF PAVED PARKING, DRAINAGE PIPING AND STRUCTURES, AND UNDERGROUND

IT IS ANTICIPATED THAT APPROXIMATELY 4.8 ACRES OF THE 9.8 ACRE SITE WILL BE DISTURBED DURING THE CONSTRUCTION OF THE FACILITY.

THE PROJECT SHALL BE DEVELOPED IN A SINGLE PHASE, HOWEVER, DISTURBED AREAS SHALL BE STABILIZED AT MILESTONE POINTS DURING CONSTRUCTION. ALL WORK SHALL BE SCHEDULED SUCH THAT STABILIZATION COINCIDES WITH THE ABILITY TO VEGETATE DISTURBED AREAS, APRIL 1 THROUGH JUNE 15 AND AUGUST 15 THROUGH OCTOBER 1

THIS PROJECT REQUIRES THE FOLLOWING PERMITS: PLANNING & ZONING SPECIAL PERMIT IWWWC PERMIT

ESTIMATED CONSTRUCTION SCHEDULE

- A. INSTALL EROSION AND SEDIMENT CONTROL SYSTEMS APRIL, 2016
- B. ROUGH GRADE SITE APRIL, 2016
- C. INSTALL STORMWATER AND UTILITY SYSTEMS MAY/JUNE, 2016
- E. CONSTRUCT BUILDING STRUCTURES APRIL-SEPTEMBER, 2016

D. CONSTRUCT ACCESS ROADWAYS & PARKING - JULY, 2016

F. FINISH GRADE SITE AND INSTALL LANDSCAPING - SEPTEMBER, 2016

GENERAL NOTES

- 1. ELEVATIONS ARE BASED ON AN ASSUMED DATUM.
- 2. INLAND WETLAND BOUNDARIES WERE DELINEATED IN THE FIELD BY CME
- 3. ALL UTILITIES SHALL BE APPROVED BY LOCAL UTILITY COMPANIES PRIOR TO CONSTRUCTION; ALL UTILITIES SHALL BE CONSTRUCTED TO UTILITY COMPANY SPECIFICATIONS.
- 4. ALL CONSTRUCTION SHALL BE TO TOWN SPECIFICATIONS & REGULATIONS.
- 5. NO CHANGES CAN BE MADE TO THESE PLANS WITHOUT THE TOWN ENGINEER'S APPROVAL.
- 6. CONTRACTOR SHALL OBTAIN ALL REQUIRED LOCAL & STATE PERMITS PRIOR TO BEGINNING ANY CONSTRUCTION.
- 7. FIELD CHANGES SHALL HAVE PRIOR APPROVAL OF THE TOWN ENGINEER.
- 8. CATCH BASIN TOPS SHALL NOT BE CEMENTED DOWN UNTIL FINAL GRADES ARE
- 9. UNLESS OTHERWISE NOTED OR SPECIFIED, ALL ROADWAYS & STORM DRAINAGE SHALL BE CONSTRUCTED IN CONFORMANCE WITH THE STATE OF CONNECTICUT, D.O.T. "STANDARD SPECIFICATIONS FOR ROADS, BRIDGES, AND INCIDENTAL CONSTRUCTION, FORM 818" AND ALL SUPPLEMENTS THERETO. SIMILARLY PERTINENT CONSTRUCTION DETAILS THAT ARE NOT INCLUDED WITH THESE DRAWINGS SHALL CONFORM TO THE STATE OF CONNECTICUT, D.O.T. STANDARD ROADWAY DRAWINGS.
- 10. CONTRACTOR SHALL NOTIFY THE TOWN ENGINEER OF CONSTRUCTION SCHEDULE SO THAT INSPECTION MAY BE PROVIDED.
- 11. UNDERGROUND UTILITY, STRUCTURE AND FACILITY LOCATIONS DEPICTED ON PLANS HAVE BEEN COMPILED, IN PART, FROM RECORD MAPPING SUPPLIED BY THE RESPECTIVE UTILITY COMPANIES OR GOVERNMENTAL AGENCIES, FROM PAROL TESTIMONY, FIELD MEASUREMENTS AND FROM OTHER SOURCES, THESE LOCATIONS MUST BE CONSIDERED APPROXIMATE IN NATURE. ADDITIONALLY, OTHER SUCH FEATURES MAY EXIST ON THE SITE, THE EXISTENCE OF WHICH ARE UNKNOWN TO CHA THE SIZE, LOCATION AND EXISTENCE OF ALL SUCH FEATURES MUST BE FIELD DETERMINED AND VERIFIED BY THE APPROPRIATE AUTHORITIES PRIOR TO CONSTRUCTION.
- 12. CONTACT "CALL BEFORE YOU DIG" AT 1-800-922-4455 TWO (2) WORKING DAYS PRIOR TO THE START OF ANY CONSTRUCTION ACTIVITY.

SEEDING SPECIFICATIONS

- A. IF GROUND HAS BEEN PREVIOUSLY MULCHED, MULCH MUST BE REMOVED OR ADDITIONAL NITROGEN MUST BE ADDED.
- B. REMOVE ALL SURFACE STONES 2" OR LARGER AS WELL AS ALL DEBRIS SUCH AS WIRE, CABLE, TREE ROOTS, PIECES OF CONCRETE, CLODS, CLUMPS, OR OTHER
- C. APPLY FERTILIZER AT 7.5 POUNDS PER 1,000 SQUARE FEET AND LIME AT 200 POUNDS PER 1,000 SQUARE FEET UNLESS SOIL TESTING FOR REQUIREMENTS IS
- D. NO MOWING IS TO BE UNDERTAKEN UNTIL THE MAJORITY OF THE VEGETATION IS AT LEAST 6" HIGH. MOWING SHOULD CUT THE TOP 1/3 OF VEGETATION. DO NOT UNDER ANY CIRCUMSTANCES CUT VEGETATION BELOW 3".
- E. DO NOT APPLY ANY FORM OF WEED CONTROL UNTIL GRASS HAS BEEN MOWED AT LEAST 4 TIMES.
- F. THESE SEEDING MEASURES ARE NOT TO BE USED ON SLOPES IN EXCESS OF 2:1
- G. PERMANENT SEEDING MEASURES ARE TO BE USED INSTEAD OF TEMPORARY SEEDING MEASURES WHERE WORK IS TO BE SUSPENDED FOR A PERIOD OF TIME LONGER THAN 1 YEAR.
- H. IF THERE IS NO EROSION, BUT SEED SURVIVAL IS LESS THAN 100 PLANTS PER SQUARE FOOT AFTER 4 WEEKS OF GROWTH, RE-SEED AS PLANTING SEASON
- I. ALL DISTURBED AREAS OUTSIDE THE PAVEMENT AREA, WITHIN AND OUTSIDE THE ROAD RIGHT OF WAY, SHALL BE RESTORED IN ACCORDANCE WITH THE TOWN SUBDIVISION REGULATIONS.

CONSTRUCTION SEQUENCE

- A. STAKEOUT LIMIT OF DISTURBANCE.
- B. HOLD A PRECONSTRUCTION MEETING.
- C. CONTACT "CALL BEFORE YOU DIG" AT 1-800-922-4455 TWO (2) WORKING DAYS PRIOR TO THE START OF ANY CONSTRUCTION ACTIVITY.
- D. INSTALL THE CONSTRUCTION ENTRANCE.
- E. INSTALL PERIMETER FILTER (SILT FENCE OR WATTLES)
- F. PERFORM ALL NECESSARY CLEARING AND GRUBBING OPERATIONS.
- G. EXCAVATE & DISPOSE OF ALL STUMPS OFF SITE.
- H. STRIP ALL TOPSOIL WITHIN THE FOOTPRINT OF THE CONSTRUCTION SITE. STOCKPILE ALL TOPSOIL IN AN APPROVED AREA AND SECURE WITH EROSION AND
- ROUGH GRADE SITE.
- J. DIG FOUNDATIONS AND STOCKPILE MATERIAL AS REQUIRED.
- PRIOR TO INSTALLATION OF SURFACE WATER CONTROLS SUCH AS TEMPORARY DIVERSIONS AND STONE DIKES, INSPECT EXISTING CONDITIONS TO ENSURE DISCHARGE LOCATIONS ARE STABLE. IF NOT STABLE, REVIEW DISCHARGE CONDITIONS WITH THE DESIGN ENGINEER AND IMPLEMENT ADDITIONAL STABILIZATION MEASURES PRIOR TO INSTALLING WATER SURFACE CONTROLS.
- L. STABILIZE CUT AND FILL SLOPES.
- M. CONSTRUCT FOUNDATION AND ERECT STRUCTURES.
- N. INSTALL SERVICE UTILITIES.
- O. CONSTRUCT CONCRETE SIDEWALKS.
- P. FINISH GRADE ACCESS DRIVEWAYS & PARKING AREAS.
- Q. PLACE TOPSOIL WHERE REQUIRED. INSTALL PERIMETER LANDSCAPE
- R. FINISH GRADE SIDE SLOPES, SEED AND MULCH.
- S. UPON SUBSTANTIAL COMPLETION OF THE BUILDING, COMPLETE THE BALANCE OF SITE WORK AND STABILIZATION OF ALL OTHER DISTURBED AREAS.
- T. INSTALL BINDER COURSE OF PAVING.
- U. WHEN ALL OTHER WORK HAS BEEN COMPLETED, REPAIR AND SWEEP ALL PAVED AREAS FOR THE TOP COURSE OF PAVING.
- V. INSTALL TOP COURSE OF PAVEMENT.

SILT FENCE SPECIFICATIONS

1. FILTERING EFFICIENCY

2. GRAB TENSILE STRENGTH

3. ELONGATION AT FAILURE

4. MULLEN BURST STRENGTH

6. APPARENT OPENING SIZE

WEIGHT OF 0.5 POUNDS PER LINEAR FOOT.

TORN OR PUNCTURED GEOTEXTILES SHALL NOT BE USED.

5. PUNCTURE STRENGTH

REQUIREMENTS:

FLOW RATE

8. PERMITTIVITY

INTERVALS.

- W. ALL REMAINING EXPOSED AREAS SHALL BE LOAMED, SEEDED AND MULCHED OR SODDED WITHIN 14 DAYS OF FINAL GRADING.
- X. REMOVE TEMPORARY EROSION AND SEDIMENT CONTROLS.
- Y. CONTRACTOR TO REMOVE ANY ACCUMULATED SEDIMENT FROM DRAINAGE STRUCTURES OR BASINS.
- NOTE: SEVERAL OF THE ABOVE ACTIVITIES MAY BE DONE SIMULTANEOUSLY.

A. SYNTHETIC FILTER FABRIC SHALL BE A PERVIOUS SHEET OF PROPYLENE, NYLON,

MANUFACTURER OR SUPPLIER AS CONFORMING TO THE FOLLOWING MINIMUM

POLYESTER, ETHYLENE, OR SIMILAR FILAMENTS AND SHALL BE CERTIFIED BY THE

75 PERCENT (MIN)

250 POUNDS PER SQUARE INCH

0.2 GALLONS PER SQUARE FOOT PER

100 POUNDS

15 PERCENT

50 POUNDS

MINUTE

9. ULTRAVIOLET RADIATION STABILITY 70 PERCENT AFTER 500 HOURS OF

SECTIONAL AREA OF 1.5 SQUARE INCHES OR STEEL POSTS WITH A MINIMUM

STAKES ARE TO BE MADE OUT OF HARDWOOD WITH A MINIMUM CROSS

ON SLOPES WHERE SURFACE FLOW FOLLOWS THE SILT FENCE LINE,

E. LINES OF SILT FENCE SHOULD FOLLOW CONTOUR LINES 5-10 FEET DOWN

PERPENDICULAR WINGS SHOULD BE PLACED AT 50 FOOT INTERVALS.

PERPENDICULAR SILT FENCE CHECKS SHALL BE INSTALLED AT 50 FOOT

GRADIENT FROM THE SLOPE. WHERE CONTOUR LINES CAN NOT BE FOLLOWED

0.60mm< X <0.90mm

0.05 PER SECOND (MIN)

EXPOSURE (MIN)

EROSION & SEDIMENT CONTROL OPERATIONS AND MAINTENANCE

- A. EROSION AND SEDIMENTATION CONTROL AND RESTORATION MEASURES SHALL CONFORM TO THE "2002 CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENTATION CONTROL". PUBLISHED BY THE CONNECTICUT COUNCIL OF SOIL AND WATER CONSERVATION AND THE CONNECTICUT DEPARTMENT OF ENVIRONMENTAL PROTECTION; AND TO TOWN REGULATIONS.
- INSTALLATION OF SEDIMENT AND EROSION CONTROLS SUCH AS WATTLES AND SILT FENCES SHALL BE ESTABLISHED PRIOR TO COMMENCING ANY LAND DISTURBANCE ACTIVITIES.
- ALL STOCKPILED MATERIAL SHALL BE RINGED WITH WATTLES OR SILT FENCES. ANY MATERIAL TO BE STOCKPILED LONGER THAN 14 DAYS SHALL BE STABILIZED WITH TEMPORARY SEEDING OR JUTE NETTING.
- D. PAVEMENT AND CURBING SHOULD BE INSTALLED AS SOON AS POSSIBLE AFTER STORM DRAINAGE IS INSTALLED.
- CATCH BASINS SHALL BE PROTECTED FROM SEDIMENTATION UNTIL ALL AREAS ARE PERMANENTLY VEGETATED OR STABILIZED.
- F. CATCH BASIN SUMPS SHALL BE CLEANED OF SILT PERIODICALLY DURING
- G. WATTLES OR SILT FENCE SHALL BE PLACED 5-10 FEET FROM THE TOE OF ALL CRITICAL SLOPES AS SHOWN ON THE PLAN. THESE SHALL BE CHECKED BY THE CONTRACTOR REGULARLY AND REPAIRED WHENEVER THEY FAIL TO ENSURE CLEAN RUN-OFF FROM THE SITE.
- H. ADDITIONAL CONTROL MEASURES IF REQUESTED BY THE TOWN SHALL BE

INSTALLED IMMEDIATELY UPON REQUEST.

AS SHOWN IN ACCOMPANYING CHART.

- ALL DISTURBED AREAS SHALL BE PROTECTED WITH A MINIMUM VEGETATION COVER
- THE CONTRACTOR SHALL PLAN ALL LAND DISTURBING ACTIVITIES IN A MANNER AS TO MINIMIZE THE EXTENT OF THE DISTURBED AREAS.
- THE CONTRACTOR SHALL MAKE DAILY INSPECTIONS OF THE SITE TO INSURE EFFECTIVENESS OF EROSION AND SEDIMENTATION CONTROL MEASURES AND WILL IMMEDIATELY MAKE NECESSARY REPAIRS IF REQUIRED BY THE TOWN.
- ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE INSPECTED AT A MINIMUM OF ONCE A WEEK AND WITHIN 24 HOURS OF THE END OF A STORM
- WITH A RAINFALL AMOUNT OF 0.1 INCHES OR GREATER TO DETERMINE MAINTENANCE NEEDS.
- M. ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE REPLACED WITHIN 24 HOURS OF AN OBSERVED FAILURE.
- N. ALL CONSTRUCTION TRAFFIC SHALL ENTER AND LEAVE BY THE DESIGNATED ENTRANCE. THIS ENTRANCE SHALL BE CONSTRUCTED OF CRUSHED STONE TO HELP FREE TIRES OF SOIL WHEN LEAVING THE SITE. THE CONTRACTOR SHALL INSTRUCT ALL VEHICLE DRIVERS TO CLEAN SOIL MATERIAL FROM TIRES IN FRONT OF THE SITE. ALL SOIL, MISCELLANEOUS DEBRIS, OR OTHER MATERIAL SPILLED, DUMPED OR OTHERWISE DEPOSITED ON PUBLIC STREETS, HIGHWAYS, SIDEWALKS OR OTHER PUBLIC THOROUGHFARES DURING TRANSIT TO OR FROM THE SITE SHALL BE REMOVED PROMPTLY.
- THE CONTRACTOR HEREBY ACKNOWLEDGES HIS RESPONSIBILITY TO INSTALL SOIL EROSION AND SEDIMENTATION CONTROL MEASURES ON THIS SITE AND THAT HIS FAILURE TO INSTALL AND MAINTAIN THESE DEVICES COULD RESULT IN FINES OR SUSPENSION OF WORK BY THE CITY/TOWN.
- P. MINIMIZE OR ELIMINATE ANY UNNECESSARY LAND DISTURBANCE OR CLEARING.

PERSON RESPONSIBLE FOR MAINTAINING

CONTROL MEASURES DURING CONSTRUCTION. STEVE TOWNSEND NAME 169 BARRETT HILL ROAD BROOKLYN, CT ADDRESS

(860)-774-5359

MAINTENANCE LOG

FINAL STABILIZATION

TELEPHONE #

LOCATION	DESCRIPTION	DATE	INITIALS
PROJECT DATES		DATE	INITIALS

STORMWATER OPERATION AND MAINTENANCE

STORMWATER FACILITY OPERATION AND MAINTENANCE PLAN:

CONSTRUCTION PHASE

GENERAL PROVISIONS:

- CONTRACTOR TO INSTALL AND MAINTAIN DRAINAGE FACILITIES AS SHOWN ON THE PLAN SET TITLED: (SPECIAL PERMIT, SITE DEVELOPMENT PLAN, PREPARED FOR, TOWNSEND DEVELOPMENT ASSOCIATES, LLC, BY CHA, DATED MAY 5, 2023, REVISED JULY
- 2. PRIOR TO CONSTRUCTION, ALL EROSION/SILTATION CONTROL DEVICES SHOWN ON ABOVE PLAN SHALL BE INSTALLED. TO PREVENT SILT INTRUSION INTO THE DRAINAGE SYSTEM DURING CONSTRUCTION, THE CONTRACTOR IS TO INSTALL INLET PROTECTION AT ALL CATCH BASINS AND SET SILT FENCE AT ALL SLOPES WHICH MAY ERODE IN THE DIRECTION OF ANY OPEN DRAINAGE FACILITIES. SUCH PREVENTIVE MEASURES ARE TO BE MAINTAINED THROUGHOUT THE CONSTRUCTION PROCESS.
- 3. EROSION CONTROLS ARE TO BE INSPECTED ON A DAILY BASIS. UPON DISCOVERY, THE CONTRACTOR SHALL REMOVE ANY SEDIMENT FROM AN EROSION CONTROL STRUCTURE.
- 4. ALL EXPOSED SOILS SHALL BE IMMEDIATELY STABILIZED TO PREVENT EROSION.
- 5. UPON INSTALLATION OF CATCH BASINS, INLET PROTECTION SHALL BE INSTALLED AND MAINTAINED UNTIL READY FOR PAVING.
- 6. PRIOR TO CONSTRUCTION OF IMPERVIOUS AREAS, ALL DRAINAGE STRUCTURES AND PIPES SHALL BE INSTALLED AND INSPECTED FOR PROPER FUNCTION. DURING CONSTRUCTION OF OTHER SITE FEATURES, DRAINAGE FACILITIES SHALL BE INSPECTED ON A DAILY BASIS AND CLEANED/REPAIRED IMMEDIATELY UPON DISCOVERY OF SEDIMENT BUILD-UP OR DAMAGE.
- 7. AFTER PAVING IS INSTALLED, IT SHALL BE SWEPT CLEAN ON A MONTHLY BASIS.

GRASSED SWALES & DRAINAGE CHANNELS:

- 1. CONTRACTOR TO INSPECT SEVERAL TIMES DURING THE FIRST FEW MONTHS TO ENSURE THAT GRASS COVER IS ESTABLISHED. AFTER ESTABLISHMENT, INSPECTION TO OCCUR SEMI-ANNUALLY AND AFTER EVERY 0.5 INCH RAIN EVENT.
- 2. CONTRACTOR SHALL CLEAN SWALE AFTER SITE IS COMPLETELY STABILIZED AND PRIOR TO TRANSFER OF OWNERSHIP TO OWNER. CATCH BASIN SUMPS:
- 1. CONTRACTOR TO INSPECT WEEKLY OR AFTER EACH 0.5 INCH RAIN EVENT AND CLEAN AS NEEDED
- 2. CONTRACTOR SHALL CLEAN SUMPS AFTER SITE IS COMPLETELY STABILIZED AND PRIOR TO TRANSFER TO OWNER.

STONE CHECK DAMS:

- 1. CONTRACTOR TO INSPECT WEEKLY OR AFTER EACH 0.5 INCH RAIN EVENT.
- 2. CONTRACTOR SHALL REMOVE SEDIMENT FROM CHECK DAMS AFTER SITE IS COMPLETELY STABILIZED AND PRIOR TO TRANSFER TO

HYDRODYNAMIC OIL & PARTICLE SEPARATOR:

1. PRIOR TO TURNOVER TO OWNER THE OIL WATER SEPARATOR WILL BE CLEANED USING A VACUUM TRUCK OR OTHER ORDINARY CATCH BASIN CLEANING EQUIPMENT. THE DEBRIS WILL BE REMOVED FROM THE SITE AND DISPOSED OF ACCORDING TO ALL LOCAL, STATE, AND FEDERAL REGULATIONS. THIS WORK WILL BE DONE BY A LICENSED HAULER OF CONTAMINATED MATERIALS.

POST-DEVELOPMENT PHASE

GENERAL PROVISIONS:

SNOW STOCKPILING:

SNOW ACCUMULATIONS REMOVED FROM STREETS AND PARKING LOTS SHALL BE PLACED IN UPLAND AREAS, WHERE SAND AND DEBRIS WILL REMAIN AFTER SNOW MELT FOR LATER REMOVAL. CARE SHOULD BE TAKEN NOT TO DEPOSIT SNOW IN THE IMMEDIATE VICINITY OF CATCH BASINS, DRAINAGE SWALES, OR SLOPES LEADING TO BODIES OF WATER, AND DRINKING WATER WELL SUPPLIES.

STREETS AND PARKING LOTS SHOULD BE SWEPT CLEAN AT LEAST ONCE ANNUALLY, PREFERABLY IMMEDIATELY AFTER WINTER SNOW MELT AND BEFORE SPRING RAINS. SWEEPING DURING THIS PERIOD CAPTURES PEAK SEDIMENT LOADS AND EXTENDS THE SERVICE LIFE OF THE STORM WATER MANAGEMENT SYSTEM.

GRASSED SWALES & DRAINAGE CHANNELS:

- GRASSED SWALES AND DRAINAGE CHANNELS SHALL BE INSPECTED AT LEAST ANNUALLY TO ENSURE THAT THEY ARE OPERATING AS
- INTENDED. POTENTIAL PROBLEMS THAT SHOULD BE CHECKED INCLUDE: 1. SLOPE INTEGRITY
- FROSION
- 3. VEGETATIVE HEALTH 4. SOIL STABILITY

SEDIMENTATION

ANY NECESSARY REPAIRS SHALL BE MADE IMMEDIATELY. TRASH SHALL BE REMOVED AND THE BANKS MOWED AS REQUIRED, BUT AT LEAST ONCE PER YEAR. GRASS SHALL BE KEPT BETWEEN FOUR AND SIX INCHES IN LENGTH. (MOWING SHOULD BE PERFORMED WHEN GROUND IS DRY TO AVOID RUTS AND COMPACTION.)

CATCH BASIN SUMPS:

CATCH BASINS SHALL BE INSPECTED BI-ANNUALLY AND CLEANED AT LEAST ANNUALLY, AFTER THE SNOW AND ICE SEASON, AND AS SOON AS POSSIBLE BEFORE SPRING RAINS. IN GENERAL, A CATCH BASIN SHOULD BE CLEANED IF THE DEPTH OF DEPOSITS IS GREATER THAN ONE HALF THE SUMP DEPTH. IF A CATCH BASIN SIGNIFICANTLY EXCEEDS THIS STANDARD THEN MORE FREQUENT CLEANINGS SHALL BE SCHEDULED. IN AREAS WITH HIGHER POLLUTANT LOADINGS OR DISCHARGES INTO SENSITIVE BODIES OF WATER, MORE FREQUENT CLEANINGS WILL BE NECESSARY.

STONE CHECK DAMS:

CHECK DAMS SHALL BE INSPECTED FOR SEDIMENTATION ON A QUARTERLY BASIS AND CLEANED AS REQUIRED.

HYDRODYNAMIC OIL & PARTICLE SEPARATOR:

THE OIL WATER SEPARATOR WILL BE INSPECTED QUARTERLY FOR THE PRESENCE OF ACCUMULATED OIL AND GREASE, FLOATABLES AND SEDIMENT, IF FOUND, THE STRUCTURE WILL BE CLEANED USING A VACUUM TRUCK OR OTHER ORDINARY CATCH BASIN CLEANING EQUIPMENT. THE DEBRIS WILL BE REMOVED FROM THE SITE AND DISPOSED OF ACCORDING TO ALL LOCAL, STATE, AND FEDERAL REGULATIONS. THIS WORK WILL BE DONE BY A LICENSED HAULER OF CONTAMINATED MATERIALS. THE SCHEDULE OF INSPECTIONS WILL BE ADJUSTED TO AN ANNUAL INSPECTION IF NO OIL OR GREASE IS FOUND ON A REGULAR BASIS. OWNER WILL BE RESPONSIBLE FOR THE INSPECTIONS AND CLEANING.

> **E&S CONTROL AND** STORMWATER MAINTENANCE PLAN

Designed By: Drawn By: Checked By

Drawing No.

PMP

AS NOTE

No. | Submittal / Revision | App'd. | By | Date

PMP 07/21/202

REVIEW COMMENTS

Drawing Copyright © 2015

400 Capital Boulevard, Suite 301

Rocky Hill, CT 06067

860-257-4557 | www.chacompanies.com

SITE DEVELOPMENT PLAN

PREPARED FOR:

TOWNSEND

DEVELOPMENT

ASSOCIATES

PROVIDENCE ROAD (RT 6)

BROOKLYN, CT

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY AR ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, ARCHITECT, LANDSCAPE ARCHITECT OR LAND SURVEYOR TO ALTER AN ITEM IN ANY WAY. IF AN ITEM BEARING STAMP OF A LICENSED PROFESSIONAL IS ALTERED, THE ALTERIS ENGINEER, ARCHITECT, TO LAND SURVEYOR SHALL STAMP THE DOCUMENT AND INCLUDE THE NOTATION "ALTERED BY" FOLLOWED BY THEIR SIGNATURE, THE DATE OF SUCH ALTERATION, AND A SPECIFIC DESCRIPTION OF THE ALTERATION.

Issue Date: Project No: 05/05/2023 080849

PMP

DATE

REVIEWED BY THE TOWN ENGINEER


FIRST SELECTMAN


ENDORSED BY THE BROOKLYN INLAND WETLANDS COMMISSION


CHAIRMAN OR SECRETARY DATE CHAIRMAN OR SECRETARY DATE

APPROVED BY THE BROOKLYN

PLANNING & ZONING COMMISSION







- 1. This survey has been prepared pursuant to the Regulations of Connecticut State Agencies Sections 20—300b—1 through 20—300b—20 and the "Standards for Surveys and Maps in the State of Connecticut" as adopted by the Connecticut Association of Land Surveyors, Inc. on September 26, 1996, Amended October 26, 2018;
 - This survey conforms to a Class "C" horizontal accuracy.
- Field surveyed topographic features conform to a Class "T-2", "V-2" vertical accuracy.
- LIDAR topographic features conform to a Class "T-D" vertical accuracy.
- Survey Type: General Location Survey.

This map was prepared from record research, other maps, limited field measurements and other sources, it is not to be construed as a Property/Boundary or Limited Property/ Boundary Survey and is subject to such facts as said surveys may disclose.

- 2. Zone = RA.
- 3. Parcel is shown as Lot #22 on Assessors Map #18.
- 4. Owner of record: Ryan & Leah Kelleher & Judith & William Raitt 155 Lafantasie Road Danielson, CT 06239 See Volume 704, Page 126
- 5. Elevations shown are based on North American Vertical Datum of 1988 (NAVD 88). Contours shown are taken from Connecticut statewide LIDAR and supplemented with actual field survey. Contour interval = 2.
- 6. Wetlands shown were delineated in the field by Joseph Theroux, Certified Soil Scientist, in 5/2/2023.
- 7. North orientation, bearings and coordinate values shown are based on North American Datum of 1983 (NAD 83) and are taker from GPS obeservations using the "Superior" statewide GPS network and RTK correction system.
- 8. 100 year flood zone shown was taken from the preliminary FIRM Winhdham County flood maps dated 7/17/2020, panel 090164 0236F.

MAP REFERENCES:

- 1. "Survey Plan Prepared for State of Connecticut Dept. of Agriculture Farmland Preservation Program — Map of Property of — Hillandale Family Limited Partnership & Estate of Georgy L. Booth - Wolfden & Bush Hill Road - Brooklyn, Connecticut Scale: 1" = 100' - Date: October, 1992 - Sheet 1 of 2 - Prepared by: Scott L. Neff". On file in the Brooklyn Land Records as Map #35.
- 2. Subdivision Map prepared for Meehan Builders, LLC Wolf Den Road — Brooklyn, Connecticut — Date: 11/01/2004 — Revised to: 3/01/2005 - Scale: 1" = 80' - Sheet 2 of 17 - Prepared by Provost & Rovero, Inc." Not on file.

07/31/2023	ADDED BOX CULVERTS
DATE	DESCRIPTION
	REVISIONS

GENERAL LOCATION SURVEY DRIVEWAY CROSSING DESIGN PLAN

PREPARED FOR


RYAN KELLEHER


404 WOLF DEN ROAD BROOKLYN, CONNECTICUT

Killingly Engineering Associates Civil Engineering & Surveying

114 Westcott Road P.O. Box 421 Killingly, Connecticut 06241 www.killinglyengineering.com

	DRAWN: NET
	DESIGN: NET
	CHK BY: GG
ILE	JOB No: 23057






- of Connecticut State Agencies Sections 20-300b-1 through 20-300b-20 and the "Standards for Surveys and Maps in the State of Connecticut" as adopted by the Connecticut Association of Land Surveyors, Inc. on September 26, 1996,
- This survey conforms to a Class "C" horizontal accuracy.
- Field surveyed topographic features conform to a Class "T-2", "V-2" vertical accuracy.

limited field measurements and other sources, it is not to be construed as a Property/Boundary or Limited Property/ Boundary Survey and is subject to such facts as said

- 3. Parcel is shown as Lot #22 on Assessors Map #18.
- 4. Owner of record: Ryan & Leah Kelleher &
- of 1988 (NAVD 88). Contours shown are taken from Connecticut statewide LIDAR and supplemented with actual field survey.
- 6. Wetlands shown were delineated in the field by Joseph Theroux,
- 7. North orientation, bearings and coordinate values shown are based on North American Datum of 1983 (NAD 83) and are taken from GPS obeservations using the "Superior" statewide GPS
- 1. "Survey Plan Prepared for State of Connecticut Dept. of Agriculture Farmland Preservation Program — Map of Property of — Hillandale Family Limited Partnership & Estate of Georgy L. Booth — Wolfden & Bush Hill Road — Brooklyn, Connecticut Scale: 1" = 100' - Date: October, 1992 - Sheet 1 of 2 - Prepared by: Scott L. Neff". On file in the Brooklyn Land Records as Map #35.
- Road Brooklyn, Connecticut Date: 11/01/2004 Revised to: 3/01/2005 Scale: 1" = 80' Sheet 2 of 17 Prepared by



GENERAL LOCATION SURVEY

RYAN KELLEHER

BROOKLYN, CONNECTICUT

114 Westcott Road Killingly, Connecticut 06241

DRAWN: RGS DESIGN: NET CHK BY: GG JOB No: 23057

EROSION AND SEDIMENT CONTROL NARRATIVE:

PRINCIPLES OF EROSION AND SEDIMENT CONTROL

The primary function of erosion and sediment controls is to absorb erosional energies and reduce runoff velocities that force the detachment and transport of soil and/or encourage the deposition of eroded soil particles before they reach any sensitive area.

KEEP LAND DISTURBANCE TO A MINIMUM

The more land that is in vegetative cover, the more surface water will infiltrate into the soil, thus minimizing stormwater runoff and potential erosion. Keeping land disturbance to a minimum not only involves minimizing the extent of exposure at any one time, but also the duration of exposure. Phasing, sequencing and construction scheduling are interrelated. Phasing divides a large project into distinct sections where construction work over a specific area occurs over distinct periods of time and each phase is not dependent upon a subsequent phase in order to be functional. A sequence is the order in which construction activities are to occur during any particular phase. A sequence should be developed on the premise of "first things first" and "last things last" with proper attention given to the inclusion of adequate erosion and sediment control measures. A construction schedule is a sequence with time lines applied to it and should address the potential overlap of actions in a sequence which may be in conflict with each other.

- Limit areas of clearing and grading. Protect natural vegetation from construction equipment with fencing, tree armoring, and retaining walls or tree
- Route traffic patterns within the site to avoid existing or newly planted vegetation.
- Phase construction so that areas which are actively being developed at any one time are minimized and only that area under construction is exposed. Clear only those areas essential for construction.
- Sequence the construction of storm drainage systems so that they are operational as soon as possible during construction. Ensure all outlets are stable before outletting storm drainage flow into them.
- Schedule construction so that final grading and stabilization is completed as soon as possible.

SLOW THE FLOW

Detachment and transport of eroded soil must be kept to a minimum by absorbing and reducing the erosive energy of water. The erosive energy of water increases as the volume and velocity of runoff increases. The volume and velocity of runoff increases during development as a result of reduced infiltration rates caused by the removal of existing vegetation, removal of topsoil, compaction of soil and the construction of impervious surfaces.

- Use diversions, stone dikes, silt fences and similar measures to break flow lines and dissipate storm water energy.
- Avoid diverting one drainage system into another without calculating the potential for downstream flooding or erosion.

KEEP CLEAN RUNOFF SEPARATED

Clean runoff should be kept separated from sediment laden water and should not be directed over disturbed areas without additional controls. Additionally, prevent the mixing of clean off—site generated runoff with sediment laden runoff generated on—site until after adequate filtration of on-site waters has occurred.

- Segregate construction waters from clean water.
- Divert site runoff to keep it isolated from wetlands, watercourses and drainage ways that flow through or near the development until the sediment in that runoff is trapped or detained.

REDUCE ON SITE POTENTIAL INTERNALLY AND INSTALL PERIMETER CONTROLS

While it may seem less complicated to collect all waters to one point of discharge for treatment and just install a perimeter control, it can be more effective to apply internal controls to many small sub-drainage basins within the site. By reducing sediment loading from within the site, the chance of perimeter control failure and the potential off—site damage that it can cause is reduced. It is generally more expensive to correct off—site damage than it is to install proper internal controls.

- Control erosion and sedimentation in the smallest drainage area possible. It is easier to control erosion than to contend with sediment after it has been carried downstream and deposited in unwanted areas.
- Direct runoff from small disturbed areas to adjoining undisturbed vegetated areas to reduce the potential for concentrated flows and increase settlement and filtering of sediments.
- Concentrated runoff from development should be safely conveyed to stable outlets using rip rapped channels, waterways, diversions, storm drains or similar measures.
- Determine the need for sediment basins. Sediment basins are required on larger developments where major grading is planned and where it is impossible or impractical to control erosion at the source. Sediment basins are needed on large and small sites when sensitive areas such as wetlands, watercourses, and streets would be impacted by off-site sediment deposition. Do not locate sediment basins in wetlands or permanent or intermittent watercourses. Sediment basins should be located to intercept runoff prior to its entry into the wetland or watercourse.

SEPTIC SYSTEM CONSTRUCTION NOTES

- 1. The building, septic system and well shall be accurately staked in the field by a licensed Land Surveyor in the State of Connecticut,
- 2. Topsoil shall be removed and in the area of the primary leaching field scarified, prior to placement of septic fill. Septic fill specifications are as follows:
 - Max. percent of gravel (material between No. 4 & 3 inch sieves) = 45% GRADATION OF FILL (MINUS GRAVEL)


SIEVE	PERCENT PASSING (WET SIEVE)	PERCENT PASSING (DRY SIEVE)
<u>SIZE</u>		
No. 4	100%	100%
No. 10	70% — 100%	70% — 100%
No. 40	10% – 50%	10% – 75%
No. 100	0% – 20%	0% – 5%
No. 200	0% - 5%	0% - 2.5%

Fill material shall be approved by the sanitarian prior to placement. It shall be compacted in 6" lifts and shall extend a minimum of five feet (5') around the perimeter of the system. Common fill shall extend an additional five feet (5') down gradient of the system (10' total) before tapering off at a maximum slope of 2H:1V.

- 3. Septic tank shall be two compartment precast 1500 gallon tank with gas deflector and outlet filter as manufactured by Jolley Precast,
- 4. Distribution boxes shall be 4 hole precast concrete as manufactured by Jolley Precast, Inc. or equal.
- 5. All precast structures such as septic tanks, distribution boxes, etc. shall be set level on six inches (6") of compacted gravel base at the elevations specified on the plans.
- 6. Solid distribution pipe shall be 4" diameter PVC meeting ASTM D-3034 SDR 35 with compression gasket joints. It shall be laid true to the lines and grades shown on the plans and in no case have a slope less than 0.125 inches per foot.
- 7. Perforated distribution pipe shall be 4" diameter PVC meeting ASTM D-3034 or ASTM F1760 for SDR 35, or ASTM F810 for SDR 38.
- 8. Sewer pipe from the foundation wall to the septic tank shall be schedule 40 PVC meeting ASTM D 1785. It shall be laid true to the grades shown on the plans and in no case shall have a slope less
- 9. Solid footing drain outlet pipe shall be 4" Diameter PVC meeting ASTM D 3034, SDR 35 with compression gasketed joints. Footing drain outlet pipe shall <u>not</u> be backfilled with free draining material, such as gravel, broken stone, rock fragments, etc.

10. Septic sand shall meet the requirements of ASTM C-33 with less than 10% passing a 100 sieve and less than 5% passing a 200 sieve


SIEVE SIZE	% PASSING
0.375	100
#4	95-100
#8	80-100
#16	60-85
#30	25-60
#50	10-30
#100	<10
#200	<5




NOTE: CONTRACTOR SHALL PROVIDE SILT/CLAY DAMS AT 100' INTERVALS ALONG PROPOSED JTILITY TRENCH TO AVOID TRANSPORTING INTERCEPTED WATER.

UNDERGROUND UTILITY TRENCH

NOT TO SCALE



SILT FENCE @ TOE OF SLOPE APPLICATION





~8" PROCESSED GRAVEL

-PREPARED SUBGRADE

CROSS SLOPE DRIVE TO SWALE

NOT TO SCALE





10'-6"

CAST CONCRETE COVERS -

PLAN

IF MORE THAN 12" OF COVER — IS REQUIRED IN THE FIELD, PROVIDE ACCESS COVERS TO GRADE.

— SOLID BLOCK—

CROSS SECTION

1500 GALLON

COMPARTMEN

SEPTIC TANK

NOT TO SCALE

1 *3" VENT —* []

À WITH FILTER →

60° GAS DEFLECTOR

PROVIDE POSITIVE GRADE AWAY FROM

GROUNDWATER FROM ENTERING CHAMBER

FINISHED GRADE

ELJEN MANTIS SPECIFIED SAND -(C-33)

MANHOLE COVER TO PREVENT

KNOCKOUT INLET AND


RIBS INSIDE

_____,

LIQUID LEVEL —

7**'**-0**"**

CONTINUOUS HOT ASPHALT SEAL



DETAIL

CLEAN BACKFILL

VENTING REQUIRED WHEN MORE THAN 18" OF COVER AS MEASURED FROM THE TOP OF THE UNIT TO FINISHED

PROVIDE 5' OF SELECT FILL OR ASTM C-33 SAND 5'


ELJEN 536-8 WASTEWATER

LEACHING SYSTEM

2. FOR SYSTEMS INSTALLED IN FILL, CONTRACTOR SHALL


AROUND PERIMETER OF SYSTEM.

WITH HOLES AT 5, 7 & 12 O'CLOCK






FREE DRAINING MATERIAL SHALL CONFORM TO ARTICLE M.02.07 OF CTDOT FORM 818



STANDARD D-BOX

NORMAND THIBEAULT, JR., P.E. No. 22834 DATE



4" PIPE WITH

5, 7 & 12 O'CLOCK

PRE-DRILLED -1" HOLES AT

18" MINIMUM FROM

6" MIN (SEE NOTE #2)

SEASONAL HIGH WATER TABLE


DETAIL SHEET

PREPARED FOR

RYAN KELLEHER

WOLF DEN ROAD BROOKLYN, CONNECTICUT

Killingly Engineering Associates Civil Engineering & Surveying



DRAWN: RGS DESIGN: NET CHK BY: GG

DATE: 5/24/2023 SCALE: NOT TO SCALE SHEET: 3 OF 3 DWG. No: CLIENT FILE JOB No: 23057



Brooklyn Land Use Department

69 South Main Street Brooklyn CT 06234 (860) 779-3411 x 31

Inland Wetlands	Zoning Enforcement	Blight Enforcement
SITE INSPECTION	ON NUMBER	1 2 3 4 5
404 Wolf 1	Den Rd.	7(25)23
, addie	55	Date
I met fanet	Booth, Norm	Thibeault and
Raiff Sant	erre, inspected o	Thibeault and and took photos.
Norm did a c	votershed analy	sis. He expects to
install a box	culvert, with	an open bottom, or
	so box culver	
We have me	structived Syl	Pauley's comments
yet.		
Norm recei	ved Demian's	comments,
Commission Represent	ative M. Was	inburn
Owner or Authorized S	Signature	









DRAINAGE REPORT

Prepared for

RYAN KELLEHER BROOKLYN, CT

June 2023

Prepared for

Proposed single-family Site Development 404 Wolf Den Road Brooklyn, CT

Prepared by

Killingly Engineering Associates

Civil Engineering & Surveying

Normand Thibeault Jr., P.E. CT License #22

Drainage Design Executive Summary

This proposal involves a single-family home on approximately 41 acres of land. The project site is located on the east side of Wolf Den Road, across from the intersection of Wolf Den Road and Woodward Road. Included with this proposal is the improvement of an existing gravel driveway and construction of a paved driveway to access the proposed residence. The residence will be served by private well and an on-site subsurface sewage disposal system.

Existing Conditions Hydrology

An existing conditions hydrologic model was created for areas of the site to be affected by this proposal. Hydrologic conditions were modeled with TR-55 methodology as utilized by HydroCAD software from Applied Microcomputer Systems. Runoff curve numbers for use in the model are based on accepted values published by the U.S. Department of Agriculture (USDA).


Since Bush Hill Brook flows through the property and constitutes the most important hydrologic resource on the site, the hydrologic model represents the entire upstream watershed of Bush Hill Brook, substantially areas off the project site; approximately 76 acres. The analysis point is the existing gravel driveway where there are currently two 15ö reinforced concrete pipes that convey flows from Bush Hill Brook which currently flows through the eastern end of a stone wall, runs parallel to the existing driveway and flows through the concrete pipes. Based on a visual inspection of the site, the existing gravel drive routinely overtops. The wetlands to the north are dammed to some extent by the stonewall which forms the northern boundary of the project property in that area and provide some limited storage capacity. The computations demonstrate that the driveway is overtopped for all storms except for the 2-year for existing conditions.


Proposed Conditions Hydrology


The proposed conditions are identical to the existing conditions with regard to the watershed area and composition. The existing driveway will be widened to a width of 12\alpha raised to elevation 350, and the existing 15\alpha concrete pipes will be replaced with 4\alpha 2\alpha open bottom box culverts. With the replacement of the 15\alpha concrete pipes with box culverts and slightly raising the driveway, up to a 100-year storm is conveyed without overtopping the driveway.

Table 1. Watershed Peak Flow Analysis

Design Storm	Depth (in)	Runoff peak	Existing Flow over Driveway	Proposed Flow over Driveway
2-Year	3.33	24.61 CFS	0.00 CFS	0.00 CFS
5-Year	4.27	47.30 CFS	3.75 CFS	+0.14 CFS
10-Year	5.02	68.97 CFS	12.10 CFS	+0.19 CFS
25-Year	6.05	101.44 CFS	61.41 CFS	+0.25 CFS
50-Year	6.81	157.66 CFS	134.54 CFS	+0.24 CFS
100-Year	7.64	222.75 CFS	197.68 CFS	+0.16 CFS







Wetlands









Prepared by Killingly Engineering Associates, LLC HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC Printed 7/31/2023 Page 2

Area Listing (all nodes)

Area	CN	Description
 (acres)		(subcatchment-numbers)
12.000	55	Woods, Good, HSG B (1S)
61.000	70	Woods, Good, HSG C (1S)
3.000	32	Woods/grass comb., Good, HSG A (1S)
76.000	66	TOTAL AREA

404 Wolf Den Type II 24-hr 2-year Rainfall=3.36" Printed 7/31/2023

Prepared by Killingly Engineering Associates, LLC HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC

Page 3

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Drainage Area

Runoff Area=76.000 ac 0.00% Impervious Runoff Depth>0.62"

Flow Length=3,325' Slope=0.0480 '/' Tc=56.3 min CN=66 Runoff=24.61 cfs 3.939 af

Pond 1P: Wetlands

Peak Elev=349.17' Storage=0.584 af Inflow=24.61 cfs 3.939 af

Primary=13.51 cfs 3.934 af Secondary=0.00 cfs 0.000 af Outflow=13.51 cfs 3.934 af

Total Runoff Area = 76.000 ac Runoff Volume = 3.939 af Average Runoff Depth = 0.62" 100.00% Pervious = 76.000 ac 0.00% Impervious = 0.000 ac

Page 4

Existing

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC

Summary for Subcatchment 1S: Drainage Area

Runoff = 24.61 cfs @ 12.68 hrs, Volume= 3.939 af, Depth> 0.62"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 2-year Rainfall=3.36"

_	Area ((ac) (ON D)esc	ription					
	12.0	000	55 V	Woods, Good, HSG B						
	3.0	000	32 V	Voo	ds/grass d	comb., Goo	d, HSG A			
_	61.0	000	70 V	Voo	ds, Good,	HSG C				
	76.0	000	66 V	Veig	hted Aver	age				
	76.0	000	1	00.0	00% Pervi	ous Area				
	Tc	Length	ı Slo	pe	Velocity	Capacity	Description			
_	(min)	(feet)	(ft	/ft)	(ft/sec)	(cfs)				
	56.3	3.325	0.04	80	0.98		Lag/CN Method, Tc-Watershed			

Summary for Pond 1P: Wetlands

Inflow Area =	76.000 ac,	0.00% Impervious, In	nflow Depth > 0.62" for 2-year event
Inflow =	24.61 cfs @	12.68 hrs, Volume=	3.939 af
Outflow =	13.51 cfs @	13.27 hrs, Volume=	3.934 af, Atten= 45%, Lag= 35.4 min
Primary =	13.51 cfs @	13.27 hrs, Volume=	3.934 af
Secondary =	0.00 cfs @	5.00 hrs, Volume=	0.000 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Peak Elev= 349.17' @ 13.27 hrs Surf.Area= 3.684 ac Storage= 0.584 af

Plug-Flow detention time= 13.3 min calculated for 3.934 af (100% of inflow) Center-of-Mass det. time= 12.8 min (874.9 - 862.1)

Volume	Invert A	vail.Stora	ge Stora	age Description	
#1	349.00'	4.300	af Cust	om Stage Data ((Prismatic) Listed below (Recalc)
Elevation	on Surf.Area	ı In	c.Store	Cum.Store	
(fee	et) (acres)	(acı	e-feet)	(acre-feet)	
349.0	00 3.380)	0.000	0.000	
350.0	00 5.220		4.300	4.300	
<u>Device</u>	Routing	Invert	Outlet De	evices	
#1	Primary	347.08'			= 20.0' RCP, sq.cut end projecting, Ke= 0.500 08' / 347.03' S= 0.0025 '/' Cc= 0.900
			n= 0.013	, Flow Area= 1.2	23 sf
#2	Primary	347.15'		•	= 20.0' RCP, sq.cut end projecting, Ke= 0.500
	·		Inlet / Ou	itlet Invert= 347.	15' / 346.95' S= 0.0100 '/' Cc= 0.900
				, Flow Area= 1.2	
#3	Secondary	349.30'	Head (fe	et) 0.20 0.40 0	h Broad-Crested Rectangular Weir .60 0.80 1.00 1.20 1.40 1.60 0 2.70 2.64 2.63 2.64 2.64 2.63

404 Wolf Den Type II 24-hr 2-year Rainfall=3.36" Printed 7/31/2023

Page 5

Prepared by Killingly Engineering Associates, LLC HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC

Primary OutFlow Max=13.51 cfs @ 13.27 hrs HW=349.17' (Free Discharge) **1=Culvert** (Barrel Controls 6.61 cfs @ 5.38 fps)

2=Culvert (Barrel Controls 6.90 cfs @ 5.62 fps)

Secondary OutFlow Max=0.00 cfs @ 5.00 hrs HW=349.00' (Free Discharge)
—3=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

404 Wolf Den Type II 24-hr 5-year Rainfall=4.27" Printed 7/31/2023

Prepared by Killingly Engineering Associates, LLC HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC

Page 6

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Drainage Area

Runoff Area=76.000 ac 0.00% Impervious Runoff Depth>1.09"

Flow Length=3,325' Slope=0.0480 '/' Tc=56.3 min CN=66 Runoff=47.30 cfs 6.929 af

Pond 1P: Wetlands

Peak Elev=349.51' Storage=1.945 af Inflow=47.30 cfs 6.929 af

Primary=15.55 cfs 6.523 af Secondary=3.75 cfs 0.397 af Outflow=19.30 cfs 6.920 af

Total Runoff Area = 76.000 ac Runoff Volume = 6.929 af Average Runoff Depth = 1.09" 100.00% Pervious = 76.000 ac 0.00% Impervious = 0.000 ac

Page 7

Existing

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC

Summary for Subcatchment 1S: Drainage Area

Runoff = 47.30 cfs @ 12.63 hrs, Volume= 6.929 af, Depth> 1.09"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 5-year Rainfall=4.27"

_	Area	(ac)	CN	Desc	Description						
	12.	000	55 Woods, Good, HSG B								
3.000 32 Woods/grass comb., Good, HSG A											
_	61.	000	70	Woo	ds, Good,	HSG C					
	76.	000	66	Weig	hted Aver	age					
	76.000 100.00% Pervious Area										
	Tc	Lengt	h	Slope	Velocity	Capacity	Description				
_	(min)	(fee	t)	(ft/ft)	(ft/sec)	(cfs)					
	56.3	3,32	5 (0.0480	0.98		Lag/CN Method, Tc-Watershed				

Summary for Pond 1P: Wetlands

Inflow Area =	76.000 ac, 0.00% Impervious, Inflow	Depth > 1.09" for 5-year event
Inflow =	47.30 cfs @ 12.63 hrs, Volume=	6.929 af
Outflow =	19.30 cfs @ 13.44 hrs, Volume=	6.920 af, Atten= 59%, Lag= 48.5 min
Primary =	15.55 cfs @ 13.44 hrs, Volume=	6.523 af
Secondary =	3.75 cfs @ 13.44 hrs, Volume=	0.397 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Peak Elev= 349.51' @ 13.44 hrs Surf.Area= 4.310 ac Storage= 1.945 af

Plug-Flow detention time= 43.8 min calculated for 6.897 af (100% of inflow) Center-of-Mass det. time= 43.2 min (893.1 - 849.9)

Volume	Invert A	vail.Stora	ge Stora	age Description	
#1	349.00'	4.300	af Cust	tom Stage Data (Prismatic) Listed below (Recalc)	
Elevatio (fee 349.0 350.0	et) (acres) 00 3.380	(acr	c.Store e-feet) 0.000 4.300	Cum.Store (acre-feet) 0.000 4.300	
Device	Routing	Invert	Outlet De	Pevices	
#1	Primary	347.08'	Inlet / Ou	ound Culvert L= 20.0' RCP, sq.cut end projecting, Ke= 0.500 utlet Invert= 347.08' / 347.03' S= 0.0025 '/' Cc= 0.900 3, Flow Area= 1.23 sf)
#2	Primary	347.15'	15.0" Ro Inlet / Ou	ound Culvert L= 20.0' RCP, sq.cut end projecting, Ke= 0.500 utlet Invert= 347.15' / 346.95' S= 0.0100 '/' Cc= 0.900)
#3	Secondary	349.30'	15.0' Ion Head (fe	3, Flow Area= 1.23 sf ng x 90.0' breadth Broad-Crested Rectangular Weir eet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 inglish) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63	

Existing
Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC

404 Wolf Den Type II 24-hr 5-year Rainfall=4.27" Printed 7/31/2023 Page 8

Primary OutFlow Max=15.55 cfs @ 13.44 hrs HW=349.51' (Free Discharge)
—1=Culvert (Barrel Controls 7.77 cfs @ 6.34 fps)
—2=Culvert (Inlet Controls 7.77 cfs @ 6.33 fps)

Secondary OutFlow Max=3.75 cfs @ 13.44 hrs HW=349.51' (Free Discharge) 3=Broad-Crested Rectangular Weir (Weir Controls 3.75 cfs @ 1.22 fps)

404 Wolf Den Type II 24-hr 10-year Rainfall=5.02" Printed 7/31/2023

Prepared by Killingly Engineering Associates, LLC HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC

Page 9

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Drainage Area Runoff Area=76.000 ac 0.00% Impervious Runoff Depth>1.54" Flow Length=3,325' Slope=0.0480 '/' Tc=56.3 min CN=66 Runoff=68.97 cfs 9.745 af

Pond 1P: Wetlands

Peak Elev=349.75' Storage=3.037 af Inflow=68.97 cfs 9.745 af

Primary=16.74 cfs 8.027 af Secondary=12.10 cfs 1.707 af Outflow=28.84 cfs 9.735 af

Total Runoff Area = 76.000 ac Runoff Volume = 9.745 af Average Runoff Depth = 1.54" 100.00% Pervious = 76.000 ac 0.00% Impervious = 0.000 ac

Page 10

Summary for Subcatchment 1S: Drainage Area

Runoff = 68.97 cfs @ 12.61 hrs, Volume= 9.745 af, Depth> 1.54"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 10-year Rainfall=5.02"

_	Area	(ac)	CN	Desc	Description						
	12.	000	55 Woods, Good, HSG B								
3.000 32 Woods/grass comb., Good, HSG A											
_	61.	000	70	Woo	ds, Good,	HSG C					
	76.	000	66	Weig	hted Aver	age					
	76.000 100.00% Pervious Area										
	Tc	Lengt	h	Slope	Velocity	Capacity	Description				
_	(min)	(fee	t)	(ft/ft)	(ft/sec)	(cfs)					
	56.3	3,32	5 (0.0480	0.98		Lag/CN Method, Tc-Watershed				

Summary for Pond 1P: Wetlands

Inflow Area =	76.000 ac,	0.00% Impervious, Infl	ow Depth > 1.54" for 10-year event
Inflow =	68.97 cfs @	12.61 hrs, Volume=	9.745 af
Outflow =	28.84 cfs @	13.37 hrs, Volume=	9.735 af, Atten= 58%, Lag= 45.4 min
Primary =	16.74 cfs @	13.37 hrs, Volume=	8.027 af
Secondary =	12 10 cfs @	13 37 hrs Volume=	1 707 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Peak Elev= 349.75' @ 13.37 hrs Surf.Area= 4.754 ac Storage= 3.037 af

Plug-Flow detention time= 54.8 min calculated for 9.735 af (100% of inflow) Center-of-Mass det. time= 54.4 min (897.6 - 843.2)

<u>Volume</u>	Invert A	vail.Stora	ge Sto	rage Description	1
#1	349.00'	4.300	af Cus	stom Stage Data	a (Prismatic) Listed below (Recalc)
Elevatio	n Surf.Area	In	c.Store	Cum.Store	
(fee	t) (acres)	(acı	re-feet)	(acre-feet)	
349.0	0 3.380		0.000	0.000	
350.0	0 5.220		4.300	4.300	
Device	Routing	Invert	Outlet [Devices	
#1	Primary	347.08'	15.0" F	Round Culvert L	L= 20.0' RCP, sq.cut end projecting, Ke= 0.500
			Inlet / C	Outlet Invert= 347	7.08' / 347.03' S= 0.0025 '/' Cc= 0.900
			n = 0.01	3, Flow Area= 1	1.23 sf
#2	Primary	347.15'	15.0" F	Round Culvert L	L= 20.0' RCP, sq.cut end projecting, Ke= 0.500
			Inlet / C	Outlet Invert= 347	7.15' / 346.95' S= 0.0100 '/' Cc= 0.900
				3, Flow Area= 1	
#3	Secondary	349.30'		•	dth Broad-Crested Rectangular Weir
			`	,	0.60 0.80 1.00 1.20 1.40 1.60
			Coef. (I	English) 2.68 2.	.70 2.70 2.64 2.63 2.64 2.64 2.63

404 Wolf Den Type II 24-hr 10-year Rainfall=5.02" Printed 7/31/2023

Prepared by Killingly Engineering Associates, LLC HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC

Page 11

Primary OutFlow Max=16.74 cfs @ 13.37 hrs HW=349.75' (Free Discharge)
—1=Culvert (Inlet Controls 8.44 cfs @ 6.88 fps)
—2=Culvert (Inlet Controls 8.30 cfs @ 6.76 fps)

Secondary OutFlow Max=12.09 cfs @ 13.37 hrs HW=349.75' (Free Discharge) 3=Broad-Crested Rectangular Weir (Weir Controls 12.09 cfs @ 1.80 fps)

Existing

404 Wolf Den Type II 24-hr 25-year Rainfall=6.05"

Prepared by Killingly Engineering Associates, LLC HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC

Printed 7/31/2023 Page 12

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Drainage Area Runoff Area=76.000 ac 0.00% Impervious Runoff Depth>2.21" Flow Length=3,325' Slope=0.0480 '/' Tc=56.3 min CN=66 Runoff=101.44 cfs 14.000 af

Pond 1P: Wetlands

Peak Elev=350.64' Storage=4.300 af Inflow=101.44 cfs 14.000 af Primary=20.12 cfs 9.649 af Secondary=61.41 cfs 4.336 af Outflow=81.54 cfs 13.986 af

Total Runoff Area = 76.000 ac Runoff Volume = 14.000 af Average Runoff Depth = 2.21" 100.00% Pervious = 76.000 ac 0.00% Impervious = 0.000 ac

Existing

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC

Page 13

Summary for Subcatchment 1S: Drainage Area

Runoff = 101.44 cfs @ 12.60 hrs, Volume= 14.000 af, Depth> 2.21"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 25-year Rainfall=6.05"

_	Area	(ac)	CN	Desc	ription					
	12.	000	55	Woo	ds, Good,	HSG B				
	3.	000	32	Woo	Woods/grass comb., Good, HSG A					
_	61.000 70 Woods, Good, HSG C									
	76.000 66 Weighted Average									
	76.	000		100.0	00% Pervi	ous Area				
	Tc	Lengt	h	Slope	Velocity	Capacity	Description			
_	(min)	(fee	t)	(ft/ft)	(ft/sec)	(cfs)				
	56.3	3,32	5 (0.0480	0.98		Lag/CN Method, Tc-Watershed			

Summary for Pond 1P: Wetlands

Inflow Area =	76.000 ac,	0.00% Impervious, Inflow	Depth > 2.21" for 25-year event
Inflow =	101.44 cfs @	12.60 hrs, Volume=	14.000 af
Outflow =	81.54 cfs @	13.05 hrs, Volume=	13.986 af, Atten= 20%, Lag= 27.1 min
Primary =	20.12 cfs @	13.05 hrs, Volume=	9.649 af
Secondary =	61 41 cfs @	13.05 hrs Volume=	4 336 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Peak Elev= 350.64' @ 13.05 hrs Surf.Area= 5.220 ac Storage= 4.300 af

Plug-Flow detention time= 59.7 min calculated for 13.986 af (100% of inflow) Center-of-Mass det. time= 59.4 min (895.5 - 836.2)

Volume	Invert A	vail.Stora	ge Stoi	rage Description	1	
#1	349.00'	4.300	af Cus	tom Stage Data	(Prismatic) Listed below (Recalc)	
Elevatio	n Surf.Area	In	c.Store Cum.Store			
(fee	t) (acres)	(acı	re-feet)	(acre-feet)		
349.0	0 3.380		0.000	0.000		
350.0	0 5.220		4.300	4.300		
Device	Routing	Invert	Outlet D)evices		
#1	Primary	347.08'	15.0" R	Cound Culvert L	L= 20.0' RCP, sq.cut end projecting, Ke= 0.500	
			Inlet / O	utlet Invert= 347	7.08' / 347.03' S= 0.0025 '/' Cc= 0.900	
				3, Flow Area= 1		
#2	Primary	347.15'			L= 20.0' RCP, sq.cut end projecting, Ke= 0.500	
			Inlet / Outlet Invert= 347.15' / 346.95' S= 0.0100 '/' Cc= 0.900			
				3, Flow Area= 1		
#3	Secondary	349.30'		•	oth Broad-Crested Rectangular Weir	
			`	,	0.60 0.80 1.00 1.20 1.40 1.60	
			Coet. (E	nglish) 2.68 2.	70 2.70 2.64 2.63 2.64 2.64 2.63	

404 Wolf Den Type II 24-hr 25-year Rainfall=6.05"

Existing

Prepared by Killingly Engineering Associates, LLC HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC

-2=Culvert (Inlet Controls 10.00 cfs @ 8.15 fps)

Printed 7/31/2023 Page 14

Primary OutFlow Max=20.12 cfs @ 13.05 hrs HW=350.64' (Free Discharge) **1=Culvert** (Inlet Controls 10.12 cfs @ 8.25 fps)

Secondary OutFlow Max=61.38 cfs @ 13.05 hrs HW=350.64' (Free Discharge) **3=Broad-Crested Rectangular Weir** (Weir Controls 61.38 cfs @ 3.06 fps)

Existing

404 Wolf Den Type II 24-hr 50-year Rainfall=6.81" Printed 7/31/2023

Prepared by Killingly Engineering Associates, LLC HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC

Page 15

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Drainage Area Runoff Area=76.000 ac 0.00% Impervious Runoff Depth>2.74" Flow Length=3,325' Slope=0.0480 '/' Tc=56.3 min CN=66 Runoff=126.90 cfs 17.360 af

Pond 1P: Wetlands

Peak Elev=351.57' Storage=4.300 af Inflow=126.90 cfs 17.360 af Primary=23.12 cfs 10.569 af Secondary=134.54 cfs 6.758 af Outflow=157.66 cfs 17.327 af

Total Runoff Area = 76.000 ac Runoff Volume = 17.360 af Average Runoff Depth = 2.74" 100.00% Pervious = 76.000 ac 0.00% Impervious = 0.000 ac

Page 16

Existing

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC

Summary for Subcatchment 1S: Drainage Area

Runoff = 126.90 cfs @ 12.59 hrs, Volume= 17.360 af, Depth> 2.74"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 50-year Rainfall=6.81"

_	Area	(ac)	CN	Desc	ription					
	12.	000	55	Woo	ds, Good,	HSG B				
	3.	000	32	Woo	Woods/grass comb., Good, HSG A					
_	61.000 70 Woods, Good, HSG C									
	76.000 66 Weighted Average									
	76.	000		100.0	00% Pervi	ous Area				
	Tc	Lengt	h	Slope	Velocity	Capacity	Description			
_	(min)	(fee	t)	(ft/ft)	(ft/sec)	(cfs)				
	56.3	3,32	5 (0.0480	0.98		Lag/CN Method, Tc-Watershed			

Summary for Pond 1P: Wetlands

Inflow Area =	76.000 ac,	0.00% Impervious, Inflo	ow Depth > 2.74"	for 50-year event
Inflow =	126.90 cfs @	12.59 hrs, Volume=	17.360 af	-
Outflow =	157.66 cfs @	12.80 hrs, Volume=	17.327 af, Atte	en= 0%, Lag= 12.4 min
Primary =	23.12 cfs @	12.80 hrs, Volume=	10.569 af	
Secondary -	134 54 cfs @	12.80 hrs Volume-	6 758 af	

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Peak Elev= 351.57' @ 12.80 hrs Surf.Area= 5.220 ac Storage= 4.300 af

Plug-Flow detention time= 55.6 min calculated for 17.270 af (99% of inflow) Center-of-Mass det. time= 54.7 min (886.7 - 832.0)

Volume	Invert A	vail.Stora	ge Stor	rage Description
#1	349.00'	4.300	af Cus	stom Stage Data (Prismatic) Listed below (Recalc)
Elevatio			c.Store	Cum.Store
(fee	t) (acres)	(ac	re-feet)	(acre-feet)
349.0	0 3.380		0.000	0.000
350.0	0 5.220		4.300	4.300
Device	Routing	Invert	Outlet D	Devices
#1	Primary	347.08'	15.0" R	Round Culvert L= 20.0' RCP, sq.cut end projecting, Ke= 0.500
	,			outlet Invert= 347.08' / 347.03' S= 0.0025 '/' Cc= 0.900
			n = 0.013	3, Flow Area= 1.23 sf
#2	Primary	347.15'		Round Culvert L= 20.0' RCP, sq.cut end projecting, Ke= 0.500
	,			outlet Invert= 347.15' / 346.95' S= 0.0100 '/' Cc= 0.900
			n = 0.013	3. Flow Area= 1.23 sf
#3	Secondary	349.30'		ng x 90.0' breadth Broad-Crested Rectangular Weir
	,			eet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60
			`	English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63

Existing

404 Wolf Den Type II 24-hr 50-year Rainfall=6.81" Printed 7/31/2023

Prepared by Killingly Engineering Associates, LLC HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC

Page 17

Primary OutFlow Max=22.97 cfs @ 12.80 hrs HW=351.52' (Free Discharge)
—1=Culvert (Inlet Controls 11.54 cfs @ 9.40 fps)
—2=Culvert (Inlet Controls 11.43 cfs @ 9.32 fps)

Secondary OutFlow Max=131.33 cfs @ 12.80 hrs HW=351.53' (Free Discharge) 3=Broad-Crested Rectangular Weir (Weir Controls 131.33 cfs @ 3.93 fps)

404 Wolf Den Type II 24-hr 100-year Rainfall=7.64"

Existing

Prepared by Killingly Engineering Associates, LLC HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC

Printed 7/31/2023

Page 18

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Drainage Area Runoff Area=76.000 ac 0.00% Impervious Runoff Depth>3.35" Flow Length=3,325' Slope=0.0480 '/' Tc=56.3 min CN=66 Runoff=155.78 cfs 21.199 af

Pond 1P: Wetlands

Peak Elev=352.22' Storage=4.300 af Inflow=155.78 cfs 21.199 af Primary=25.02 cfs 11.372 af Secondary=197.68 cfs 9.609 af Outflow=222.75 cfs 20.980 af

Total Runoff Area = 76.000 ac Runoff Volume = 21.199 af Average Runoff Depth = 3.35" 100.00% Pervious = 76.000 ac 0.00% Impervious = 0.000 ac

Printed 7/31/2023 Page 19

Summary for Subcatchment 1S: Drainage Area

Runoff = 155.78 cfs @ 12.59 hrs, Volume= 21.199 af, Depth> 3.35"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 100-year Rainfall=7.64"

Area	a (ac)	CI	N Desc	cription			
12	2.000	5	5 Woo	ds, Good,	HSG B		
(3.000	3	2 Woo	ds/grass d	omb., Goo	d, HSG A	
6	1.000	7	0 Woo	ds, Good,	HSG C		
76	76.000 66 Weighted Average						
76	6.000		100.	00% Pervi	ous Area		
To		,	Slope	Velocity	Capacity	Description	
(min)	(fe	et)	(ft/ft)	(ft/sec)	(cfs)		
56.3	3,3	25	0.0480	0.98		Lag/CN Method, Tc-Watershed	

Summary for Pond 1P: Wetlands

Inflow Area =	76.000 ac,	0.00% Impervious, Inflow	Depth > 3.35"	for 100-year event
Inflow =	155.78 cfs @	12.59 hrs, Volume=	21.199 af	-
Outflow =	222.75 cfs @	12.65 hrs, Volume=	20.980 af, Atte	en= 0%, Lag= 4.0 min
Primary =	25.02 cfs @	12.65 hrs, Volume=	11.372 af	
Secondary -	197 68 cfs @	12.65 hrs Volume-	9 609 af	

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Peak Elev= 352.22' @ 12.65 hrs Surf.Area= 5.220 ac Storage= 4.300 af

Plug-Flow detention time= 51.5 min calculated for 20.980 af (99% of inflow) Center-of-Mass det. time= 47.7 min (875.8 - 828.1)

Volume	Invert A	vail.Stora	ge Stora	ge Description			
#1	349.00'	4.300	af Cust	om Stage Data (Prismatic) Listed below (Red	calc)		
Elevatio	• • • • • • • • • • • • • • • • • •		c.Store e-feet)	Cum.Store (acre-feet)			
349.0	0 3.380		0.000	0.000			
350.0	0 5.220		4.300	4.300			
Device	Routing	Invert	Outlet De	vices			
#1	Primary	347.08'		und Culvert L= 20.0' RCP, sq.cut end project Invert= 347.08' / 347.03' S= 0.0025 '/' C	,		
# 0	Deign	0.47.45	n = 0.013	Flow Area= 1.23 sf			
#2	Primary	347.15'		und Culvert L= 20.0' RCP, sq.cut end pro let Invert= 347.15' / 346.95' S= 0.0100 '/' C			
			n = 0.013	n= 0.013, Flow Area= 1.23 sf			
#3	Secondary	349.30'	15.0' long x 90.0' breadth Broad-Crested Rectangular Weir				
			•	et) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.40 1.40 1.40 1.40 1.40 1.40 1.4			
			Coel. (El	glish) 2.68 2.70 2.70 2.64 2.63 2.64 2.64	1 2.03		

404 Wolf Den Type II 24-hr 100-year Rainfall=7.64"

Existing

Prepared by Killingly Engineering Associates, LLC HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC

Printed 7/31/2023

Page 20


Primary OutFlow Max=25.02 cfs @ 12.65 hrs HW=352.22' (Free Discharge)
—1=Culvert (Inlet Controls 12.56 cfs @ 10.23 fps)
—2=Culvert (Inlet Controls 12.46 cfs @ 10.15 fps)

Secondary OutFlow Max=187.12 cfs @ 12.65 hrs HW=352.12' (Free Discharge)
—3=Broad-Crested Rectangular Weir (Weir Controls 187.12 cfs @ 4.42 fps)



SUPPORTING DOCUMENTATION

NOAA Point Precipitation Estimates



Wetlands









Proposed
Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC

Printed 7/31/2023 Page 2

Area Listing (all nodes)

Area	CN	Description
(acres)		(subcatchment-numbers)
12.000	55	Woods, Good, HSG B (1S)
61.000	70	Woods, Good, HSG C (1S)
3.000	32	Woods/grass comb., Good, HSG A (1S)
76.000	66	TOTAL AREA

Proposed

404 Wolf Den Type II 24-hr 2-year Rainfall=3.36" Printed 7/31/2023

Prepared by Killingly Engineering Associates, LLC HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC

Page 3

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Drainage Area

Runoff Area=76.000 ac 0.00% Impervious Runoff Depth>0.62"

Flow Length=3,325' Slope=0.0480 '/' Tc=56.3 min CN=66 Runoff=24.61 cfs 3.939 af

Pond 1P: Wetlands

Peak Elev=348.11' Storage=0.362 af Inflow=24.61 cfs 3.939 af

Primary=17.61 cfs 3.931 af Secondary=0.00 cfs 0.000 af Outflow=17.61 cfs 3.931 af

Total Runoff Area = 76.000 ac Runoff Volume = 3.939 af Average Runoff Depth = 0.62" 100.00% Pervious = 76.000 ac 0.00% Impervious = 0.000 ac

Page 4

Proposed

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC

Summary for Subcatchment 1S: Drainage Area

Runoff = 24.61 cfs @ 12.68 hrs, Volume= 3.939 af, Depth> 0.62"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 2-year Rainfall=3.36"

_	Area	(ac)	CN	Desc	ription					
	12.	000	55	Woo	ds, Good,	HSG B				
	3.	000	32	Woo	Woods/grass comb., Good, HSG A					
_	61.000 70 Woods, Good, HSG C									
	76.000 66 Weighted Average									
	76.	000		100.0	00% Pervi	ous Area				
	Tc	Lengt	h	Slope	Velocity	Capacity	Description			
_	(min)	(fee	t)	(ft/ft)	(ft/sec)	(cfs)				
	56.3	3,32	5 (0.0480	0.98		Lag/CN Method, Tc-Watershed			

Summary for Pond 1P: Wetlands

Inflow Area =	76.000 ac,	0.00% Impervious, Inflow De	epth > 0.62" for 2-year event
Inflow =	24.61 cfs @	12.68 hrs, Volume=	3.939 af
Outflow =	17.61 cfs @	13.05 hrs, Volume=	3.931 af, Atten= 28%, Lag= 22.2 min
Primary =	17.61 cfs @	13.05 hrs, Volume=	3.931 af
Secondary =	0.00 cfs @	5 00 hrs Volume=	0.000 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Peak Elev= 348.11' @ 13.05 hrs Surf.Area= 3.477 ac Storage= 0.362 af

Plug-Flow detention time= 6.8 min calculated for 3.931 af (100% of inflow) Center-of-Mass det. time= 6.1 min (868.1 - 862.1)

<u>Volume</u>	Invert A	vail.Stora	age Storage Description
#1	348.00'	8.600	af Custom Stage Data (Prismatic) Listed below (Recalc)
Elevatio	n Surf.Area	ln	nc.Store Cum.Store
(fee	t) (acres)	(acı	ere-feet) (acre-feet)
348.0	0 3.380		0.000 0.000
350.0	0 5.220		8.600 8.600
Device	Routing	Invert	Outlet Devices
#1	Primary	347.08'	48.0" W x 24.0" H Box Culvert
			L= 20.0' RCP, sq.cut end projecting, Ke= 0.500
			Inlet / Outlet Invert= 347.08' / 347.03' S= 0.0025 '/' Cc= 0.900
			n= 0.030 Earth, grassed & winding, Flow Area= 8.00 sf
#2	Primary	347.15'	48.0" W x 24.0" H Box Culvert
	-		L= 20.0' RCP, sq.cut end projecting, Ke= 0.500
			Inlet / Outlet Invert= 347.15' / 346.95' S= 0.0100 '/' Cc= 0.900
			n= 0.030 Earth, grassed & winding, Flow Area= 8.00 sf
#3	Secondary	350.00'	15.0' long x 90.0' breadth Broad-Crested Rectangular Weir
	•		

404 Wolf Den Type II 24-hr 2-year Rainfall=3.36" Printed 7/31/2023

Page 5

Prepared by Killingly Engineering Associates, LLC HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC

> Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63

Primary OutFlow Max=17.61 cfs @ 13.05 hrs HW=348.11' (Free Discharge) -1=Culvert (Barrel Controls 8.39 cfs @ 2.73 fps)

-2=Culvert (Barrel Controls 9.22 cfs @ 3.21 fps)

Secondary OutFlow Max=0.00 cfs @ 5.00 hrs HW=348.00' (Free Discharge)
—3=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Proposed

404 Wolf Den Type II 24-hr 5-year Rainfall=4.27" Printed 7/31/2023

Prepared by Killingly Engineering Associates, LLC HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC

Page 6

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Drainage Area

Runoff Area=76.000 ac 0.00% Impervious Runoff Depth>1.09"

Flow Length=3,325' Slope=0.0480 '/' Tc=56.3 min CN=66 Runoff=47.30 cfs 6.929 af

Pond 1P: Wetlands

Peak Elev=348.39' Storage=1.381 af Inflow=47.30 cfs 6.929 af Primary=25.97 cfs 6.915 af Secondary=0.00 cfs 0.000 af Outflow=25.97 cfs 6.915 af

Total Runoff Area = 76.000 ac Runoff Volume = 6.929 af Average Runoff Depth = 1.09" 100.00% Pervious = 76.000 ac 0.00% Impervious = 0.000 ac

Page 7

Proposed

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC

Summary for Subcatchment 1S: Drainage Area

Runoff = 47.30 cfs @ 12.63 hrs, Volume= 6.929 af, Depth> 1.09"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 5-year Rainfall=4.27"

_	Area	(ac)	CN	Desc	ription		
	12.	000	55	Woo	ds, Good,	HSG B	
	3.	000	32	Woo	ds/grass d	omb., Goo	d, HSG A
_	61.	000	70	Woo	ds, Good,	HSG C	
	76.	000	66	Weig	hted Aver	age	
	76.000 100.00% Pervious Area				00% Pervi	ous Area	
	Tc	Lengt	h	Slope	Velocity	Capacity	Description
_	(min)	(fee	t)	(ft/ft)	(ft/sec)	(cfs)	
	56.3	3,32	5 (0.0480	0.98		Lag/CN Method, Tc-Watershed

Summary for Pond 1P: Wetlands

Inflow Area =	76.000 ac,	0.00% Impervious, Inflow	v Depth > 1.09" for 5-year event
Inflow =	47.30 cfs @	12.63 hrs, Volume=	6.929 af
Outflow =	25.97 cfs @	13.19 hrs, Volume=	6.915 af, Atten= 45%, Lag= 33.7 min
Primary =	25.97 cfs @	13.19 hrs, Volume=	6.915 af
Secondary =	0.00 cfs @	5.00 hrs Volume=	0.000 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Peak Elev= 348.39' @ 13.19 hrs Surf.Area= 3.737 ac Storage= 1.381 af

Plug-Flow detention time= 20.4 min calculated for 6.892 af (99% of inflow) Center-of-Mass det. time= 19.7 min (869.6 - 849.9)

Volume	Invert A	vail.Stora	age Storage Description
#1	348.00'	8.600	af Custom Stage Data (Prismatic) Listed below (Recalc)
Elevatio	•••••		nc.Store Cum.Store ere-feet) (acre-feet)
348.0	0 3.380)	0.000 0.000
350.0	0 5.220)	8.600 8.600
Device	Routing	Invert	Outlet Devices
#1	Primary	347.08'	48.0" W x 24.0" H Box Culvert
#2	Primary	347.15'	L= 20.0' RCP, sq.cut end projecting, Ke= 0.500 Inlet / Outlet Invert= 347.08' / 347.03' S= 0.0025 '/' Cc= 0.900 n= 0.030 Earth, grassed & winding, Flow Area= 8.00 sf 48.0" W x 24.0" H Box Culvert L= 20.0' RCP, sq.cut end projecting, Ke= 0.500 Inlet / Outlet Invert= 347.15' / 346.95' S= 0.0100 '/' Cc= 0.900
#3	Secondary	350.00'	n= 0.030 Earth, grassed & winding, Flow Area= 8.00 sf 15.0' long x 90.0' breadth Broad-Crested Rectangular Weir

404 Wolf Den Type II 24-hr 5-year Rainfall=4.27" Printed 7/31/2023

Page 8

Prepared by Killingly Engineering Associates, LLC HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC

> Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63

Primary OutFlow Max=25.97 cfs @ 13.19 hrs HW=348.39' (Free Discharge) -1=Culvert (Barrel Controls 12.43 cfs @ 3.17 fps)

-2=Culvert (Barrel Controls 13.54 cfs @ 3.65 fps)

Secondary OutFlow Max=0.00 cfs @ 5.00 hrs HW=348.00' (Free Discharge)
—3=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Proposed

404 Wolf Den Type II 24-hr 10-year Rainfall=5.02" Printed 7/31/2023

Prepared by Killingly Engineering Associates, LLC HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC

Page 9

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Drainage Area Runoff Area=76.000 ac 0.00% Impervious Runoff Depth>1.54" Flow Length=3,325' Slope=0.0480 '/' Tc=56.3 min CN=66 Runoff=68.97 cfs 9.745 af

Pond 1P: Wetlands

Peak Elev=348.65' Storage=2.399 af Inflow=68.97 cfs 9.745 af

Primary=34.69 cfs 9.728 af Secondary=0.00 cfs 0.000 af Outflow=34.69 cfs 9.728 af

Total Runoff Area = 76.000 ac Runoff Volume = 9.745 af Average Runoff Depth = 1.54" 100.00% Pervious = 76.000 ac 0.00% Impervious = 0.000 ac

Page 10

Proposed

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC

Summary for Subcatchment 1S: Drainage Area

Runoff = 68.97 cfs @ 12.61 hrs, Volume= 9.745 af, Depth> 1.54"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 10-year Rainfall=5.02"

_	Area	(ac)	CN	Desc	ription		
	12.	000	55	Woo	ds, Good,	HSG B	
	3.	000	32	Woo	ds/grass d	omb., Goo	d, HSG A
_	61.	000	70	Woo	ds, Good,	HSG C	
	76.	000	66	Weig	hted Aver	age	
	76.000 100.00% Pervious Area				00% Pervi	ous Area	
	Tc	Lengt	h	Slope	Velocity	Capacity	Description
_	(min)	(fee	t)	(ft/ft)	(ft/sec)	(cfs)	
	56.3	3,32	5 (0.0480	0.98		Lag/CN Method, Tc-Watershed

Summary for Pond 1P: Wetlands

Inflow Area =	76.000 ac,	0.00% Impervious, Inflow I	Depth > 1.54" for 10-year event
Inflow =	68.97 cfs @	12.61 hrs, Volume=	9.745 af
Outflow =	34.69 cfs @	13.22 hrs, Volume=	9.728 af, Atten= 50%, Lag= 36.7 min
Primary =	34.69 cfs @	13.22 hrs, Volume=	9.728 af
Secondary =	0.00 cfs @	5.00 hrs, Volume=	0.000 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Peak Elev= 348.65' @ 13.22 hrs Surf.Area= 3.980 ac Storage= 2.399 af

Plug-Flow detention time= 29.8 min calculated for 9.696 af (99% of inflow) Center-of-Mass det. time= 29.0 min (872.2 - 843.2)

Volume	Invert A	vail.Stora	age Storage Description
#1	348.00'	8.600	af Custom Stage Data (Prismatic) Listed below (Recalc)
Elevatio	•••••		nc.Store Cum.Store ere-feet) (acre-feet)
348.0	0 3.380)	0.000 0.000
350.0	0 5.220)	8.600 8.600
Device	Routing	Invert	Outlet Devices
#1	Primary	347.08'	48.0" W x 24.0" H Box Culvert
#2	Primary	347.15'	L= 20.0' RCP, sq.cut end projecting, Ke= 0.500 Inlet / Outlet Invert= 347.08' / 347.03' S= 0.0025 '/' Cc= 0.900 n= 0.030 Earth, grassed & winding, Flow Area= 8.00 sf 48.0" W x 24.0" H Box Culvert L= 20.0' RCP, sq.cut end projecting, Ke= 0.500 Inlet / Outlet Invert= 347.15' / 346.95' S= 0.0100 '/' Cc= 0.900
#3	Secondary	350.00'	n= 0.030 Earth, grassed & winding, Flow Area= 8.00 sf 15.0' long x 90.0' breadth Broad-Crested Rectangular Weir

404 Wolf Den Type II 24-hr 10-year Rainfall=5.02" Printed 7/31/2023

Prepared by Killingly Engineering Associates, LLC HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC

Page 11

Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.63

Primary OutFlow Max=34.68 cfs @ 13.22 hrs HW=348.65' (Free Discharge)

-1=Culvert (Barrel Controls 16.66 cfs @ 3.53 fps)
-2=Culvert (Barrel Controls 18.02 cfs @ 4.00 fps)

Secondary OutFlow Max=0.00 cfs @ 5.00 hrs HW=348.00' (Free Discharge)
—3=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Proposed

404 Wolf Den Type II 24-hr 25-year Rainfall=6.05" Printed 7/31/2023

Prepared by Killingly Engineering Associates, LLC HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC

Page 12

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Drainage Area Runoff Area=76.000 ac 0.00% Impervious Runoff Depth>2.21" Flow Length=3,325' Slope=0.0480 '/' Tc=56.3 min CN=66 Runoff=101.44 cfs 14.000 af

Pond 1P: Wetlands

Peak Elev=349.02' Storage=3.943 af Inflow=101.44 cfs 14.000 af Primary=48.28 cfs 13.977 af Secondary=0.00 cfs 0.000 af Outflow=48.28 cfs 13.977 af

Total Runoff Area = 76.000 ac Runoff Volume = 14.000 af Average Runoff Depth = 2.21" 100.00% Pervious = 76.000 ac 0.00% Impervious = 0.000 ac

Printed 7/31/2023 Page 13

Summary for Subcatchment 1S: Drainage Area

Runoff = 101.44 cfs @ 12.60 hrs, Volume= 14.000 af, Depth> 2.21"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 25-year Rainfall=6.05"

_	Area	(ac)	CN	Desc	ription		
	12.	000	55	Woo	ds, Good,	HSG B	
	3.	000	32	Woo	ds/grass d	omb., Goo	d, HSG A
_	61.	000	70	Woo	ds, Good,	HSG C	
	76.	000	66	Weig	hted Aver	age	
	76.	000		100.0	00% Pervi	ous Area	
	Tc	Lengtl	า	Slope	Velocity	Capacity	Description
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
	56.3	3,32	5 0	0.0480	0.98		Lag/CN Method, Tc-Watershed

Summary for Pond 1P: Wetlands

Inflow Area =	76.000 ac,	0.00% Impervious, Inflo	w Depth > 2.21" for 25-year event
Inflow =	101.44 cfs @	12.60 hrs, Volume=	14.000 af
Outflow =	48.28 cfs @	13.24 hrs, Volume=	13.977 af, Atten= 52%, Lag= 38.2 min
Primary =	48.28 cfs @	13.24 hrs, Volume=	13.977 af
Secondary =	0.00 cfs @	5.00 hrs, Volume=	0.000 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Peak Elev= 349.02' @ 13.24 hrs Surf.Area= 4.322 ac Storage= 3.943 af

Plug-Flow detention time= 38.7 min calculated for 13.977 af (100% of inflow) Center-of-Mass det. time= 38.2 min (874.3 - 836.2)

<u>Volume</u>	Invert A	vert Avail.Storage Storage Description		orage Description
#1	348.00'	.00' 8.600		stom Stage Data (Prismatic) Listed below (Recalc)
Elevatio	n Surf.Area	ln	c.Store	Cum.Store
(fee	t) (acres)	(acı	re-feet)	(acre-feet)
348.0	0 3.380		0.000	0.000
350.0	0 5.220		8.600	8.600
Device	Routing	Invert	Outlet D	Devices
#1	Primary	347.08'	48.0" W	V x 24.0" H Box Culvert
			L=20.0'	D' RCP, sq.cut end projecting, Ke= 0.500
			Inlet / O	Outlet Invert= 347.08' / 347.03' S= 0.0025 '/' Cc= 0.900
			n = 0.030	30 Earth, grassed & winding, Flow Area= 8.00 sf
#2	Primary	347.15'	48.0" W	V x 24.0" H Box Culvert
			L=20.0'	D' RCP, sq.cut end projecting, Ke= 0.500
			Inlet / O	Outlet Invert= 347.15' / 346.95' S= 0.0100 '/' Cc= 0.900
			n = 0.030	30 Earth, grassed & winding, Flow Area= 8.00 sf
#3	Secondary	350.00'	15.0' lor	ong x 90.0' breadth Broad-Crested Rectangular Weir

Proposed

Prepared by Killingly Engineering Associates, LLC HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC

Printed 7/31/2023 Page 14

Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.63

Primary OutFlow Max=48.27 cfs @ 13.24 hrs HW=349.02' (Free Discharge) **1=Culvert** (Barrel Controls 23.30 cfs @ 4.00 fps)

2=Culvert (Barrel Controls 24.97 cfs @ 4.44 fps)

Secondary OutFlow Max=0.00 cfs @ 5.00 hrs HW=348.00' (Free Discharge)
—3=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Proposed

404 Wolf Den Type II 24-hr 50-year Rainfall=6.81" Printed 7/31/2023

Prepared by Killingly Engineering Associates, LLC HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC

Page 15

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Drainage Area Runoff Area=76.000 ac 0.00% Impervious Runoff Depth>2.74" Flow Length=3,325' Slope=0.0480 '/' Tc=56.3 min CN=66 Runoff=126.90 cfs 17.360 af

Pond 1P: Wetlands

Peak Elev=349.30' Storage=5.157 af Inflow=126.90 cfs 17.360 af

Primary=59.15 cfs 17.334 af Secondary=0.00 cfs 0.000 af Outflow=59.15 cfs 17.334 af

Total Runoff Area = 76.000 ac Runoff Volume = 17.360 af Average Runoff Depth = 2.74" 100.00% Pervious = 76.000 ac 0.00% Impervious = 0.000 ac

Page 16

Proposed

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC

Summary for Subcatchment 1S: Drainage Area

Runoff = 126.90 cfs @ 12.59 hrs, Volume= 17.360 af, Depth> 2.74"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 50-year Rainfall=6.81"

_	Area	(ac)	CN	Desc	ription		
	12.	000	55	Woo	ds, Good,	HSG B	
	3.	000	32	Woo	ds/grass d	omb., Goo	d, HSG A
_	61.	000	70	Woo	ds, Good,	HSG C	
	76.	000	66	Weig	hted Aver	age	
	76.000 100.00% Pervious Area				00% Pervi	ous Area	
	Tc	Lengt	h	Slope	Velocity	Capacity	Description
_	(min)	(fee	t)	(ft/ft)	(ft/sec)	(cfs)	
	56.3	3,32	5 (0.0480	0.98		Lag/CN Method, Tc-Watershed

Summary for Pond 1P: Wetlands

Inflow Area =	76.000 ac,	0.00% Impervious,	Inflow Depth > 2.74" for 50-year event
Inflow =	126.90 cfs @	12.59 hrs, Volume=	= 17.360 af
Outflow =	59.15 cfs @	13.24 hrs, Volume=	= 17.334 af, Atten= 53%, Lag= 38.6 min
Primary =	59.15 cfs @	13.24 hrs, Volume=	= 17.334 af
Secondary =	0.00 cfs @	5.00 hrs, Volume=	= 0.000 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Peak Elev= 349.30' @ 13.24 hrs Surf.Area= 4.573 ac Storage= 5.157 af

Plug-Flow detention time= 43.5 min calculated for 17.334 af (100% of inflow) Center-of-Mass det. time= 42.9 min (874.9 - 832.0)

Volume	Invert A	vail.Stora	age Storage Description
#1	348.00'	8.600	0 af Custom Stage Data (Prismatic) Listed below (Recalc)
Elevatio			nc.Store Cum.Store cre-feet) (acre-feet)
348.0	0 3.380		0.000 0.000
350.0	0 5.220		8.600 8.600
Device	Routing	Invert	Outlet Devices
#1	Primary	347.08'	48.0" W x 24.0" H Box Culvert
#2	Primary	347.15'	L= 20.0' RCP, sq.cut end projecting, Ke= 0.500 Inlet / Outlet Invert= 347.08' / 347.03' S= 0.0025 '/' Cc= 0.900 n= 0.030 Earth, grassed & winding, Flow Area= 8.00 sf 48.0" W x 24.0" H Box Culvert L= 20.0' RCP, sq.cut end projecting, Ke= 0.500
#3 Secondary		350.00'	Inlet / Outlet Invert= 347.15' / 346.95' S= 0.0100 '/' Cc= 0.900 n= 0.030 Earth, grassed & winding, Flow Area= 8.00 sf 15.0' long x 90.0' breadth Broad-Crested Rectangular Weir

404 Wolf Den Type II 24-hr 50-year Rainfall=6.81" Printed 7/31/2023

Prepared by Killingly Engineering Associates, LLC HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC

Page 17

Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63

Primary OutFlow Max=59.13 cfs @ 13.24 hrs HW=349.30' (Free Discharge)

-1=Culvert (Barrel Controls 28.63 cfs @ 4.30 fps)

-2=Culvert (Barrel Controls 30.51 cfs @ 4.74 fps)

Secondary OutFlow Max=0.00 cfs @ 5.00 hrs HW=348.00' (Free Discharge)
—3=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

404 Wolf Den

Type II 24-hr 100-year Rainfall=7.64"

Proposed

Prepared by Killingly Engineering Associates, LLC HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC

Printed 7/31/2023 Page 18

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Drainage Area Runoff Area=76.000 ac 0.00% Impervious Runoff Depth>3.35" Flow Length=3,325' Slope=0.0480 '/' Tc=56.3 min CN=66 Runoff=155.78 cfs 21.199 af

Pond 1P: Wetlands

Peak Elev=349.59' Storage=6.539 af Inflow=155.78 cfs 21.199 af Primary=71.60 cfs 21.167 af Secondary=0.00 cfs 0.000 af Outflow=71.60 cfs 21.167 af

Total Runoff Area = 76.000 ac Runoff Volume = 21.199 af Average Runoff Depth = 3.35" 100.00% Pervious = 76.000 ac 0.00% Impervious = 0.000 ac

Printed 7/31/2023

Page 19

Summary for Subcatchment 1S: Drainage Area

Runoff = 155.78 cfs @ 12.59 hrs, Volume= 21.199 af, Depth> 3.35"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 100-year Rainfall=7.64"

_	Area (a	ac) C	N Desc	escription						
	12.0	00 5	55 Woo	ds, Good,	HSG B					
	3.0	00 3	32 Woo	ds/grass o	comb., Goo	d, HSG A				
_	61.0	00 7	'0 Woo	ds, Good,	HSG C					
	76.0	00 6	66 Weig	ghted Avei	age					
	76.0	00	100.	00% Pervi	ous Area					
		Length	Slope	Velocity	Capacity	Description				
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)					
	56.3	3.325	0.0480	0.98		Lag/CN Method, Tc-Watershed				

Summary for Pond 1P: Wetlands

Inflow Area =	76.000 ac,	0.00% Impervious, Inflow	v Depth > 3.35" for 100-year event	
Inflow =	155.78 cfs @	12.59 hrs, Volume=	21.199 af	
Outflow =	71.60 cfs @	13.23 hrs, Volume=	21.167 af, Atten= 54%, Lag= 38.7 mir	n
Primary =	71.60 cfs @	13.23 hrs, Volume=	21.167 af	
Secondary -	0 00 cfs @	5.00 hrs. Volume-	0.000 af	

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Peak Elev= 349.59' @ 13.23 hrs Surf.Area= 4.843 ac Storage= 6.539 af

Plug-Flow detention time= 47.6 min calculated for 21.097 af (100% of inflow) Center-of-Mass det. time= 46.9 min (875.0 - 828.1)

Volume	Invert A	vail.Stora	nge Storage Description	
#1	348.00'	8.600	af Custom Stage Data (Prismatic) Listed below (Recalc)	
Elevatio (fee 348.0	t) (acres)	(acr	c.Store Cum.Store re-feet) (acre-feet) 0.000 0.000	
350.0	0 5.220		8.600 8.600	
Device	Routing	Invert	Outlet Devices	
#1	Primary	347.08'	48.0" W x 24.0" H Box Culvert	
#2	#2 Primary		L= 20.0' RCP, sq.cut end projecting, Ke= 0.500 Inlet / Outlet Invert= 347.08' / 347.03' S= 0.0025 '/' Cc= 0.900 n= 0.030 Earth, grassed & winding, Flow Area= 8.00 sf 48.0" W x 24.0" H Box Culvert L= 20.0' RCP, sq.cut end projecting, Ke= 0.500 Inlet / Outlet Invert= 347.15' / 346.95' S= 0.0100 '/' Cc= 0.900	
#3	Secondary	350.00'	n= 0.030 Earth, grassed & winding, Flow Area= 8.00 sf 15.0' long x 90.0' breadth Broad-Crested Rectangular Weir	

Type II 24-hr 100-year Rainfall=7.64"

Proposed

Prepared by Killingly Engineering Associates, LLC HydroCAD® 10.00-26 s/n 07240 © 2020 HydroCAD Software Solutions LLC Printed 7/31/2023 Page 20

Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63

Primary OutFlow Max=71.58 cfs @ 13.23 hrs HW=349.59' (Free Discharge)

-1=Culvert (Barrel Controls 34.74 cfs @ 4.61 fps) -2=Culvert (Barrel Controls 36.83 cfs @ 5.03 fps)

Secondary OutFlow Max=0.00 cfs @ 5.00 hrs HW=348.00' (Free Discharge)
—3=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

SUPPORTING DOCUMENTATION

NOAA Point Precipitation Estimates



NOAA Atlas 14, Volume 10, Version 3 Location name: Brooklyn, Connecticut, USA* Latitude: 41.8039°, Longitude: -71.9768° Elevation: 354 ft**

8039°, Longitude: -71.9768°
levation: 354 ft**
*source: ESRI Maps
**source: USGS

POINT PRECIPITATION FREQUENCY ESTIMATES

Sanja Perica, Sandra Pavlovic, Michael St. Laurent, Carl Trypaluk, Dale Unruh, Orlan Wilhite NOAA, National Weather Service, Silver Spring, Maryland

PF_tabular | PF_graphical | Maps_&_aerials

PF tabular

PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches) ¹										
Duration	Average recurrence interval (years)									
Duration	1	2	5	10	25	50	100	200	500	1000
5-min	0.338 (0.257-0.445)	0.401 (0.304-0.528)	0.503 (0.380-0.664)	0.587 (0.442-0.779)	0.703 (0.515-0.967)	0.792 (0.568-1.11)	0.883 (0.616-1.27)	0.980 (0.657-1.45)	1.11 (0.720-1.70)	1.22 (0.772-1.89)
10-min	0.479 (0.364-0.631)	0.568 (0.431-0.747)	0.712 (0.539-0.941)	0.832 (0.626-1.10)	0.996 (0.729-1.37)	1.12 (0.805-1.57)	1.25 (0.873-1.80)	1.39 (0.929-2.05)	1.58 (1.02-2.40)	1.73 (1.09-2.68)
15-min	0.564 (0.429-0.742)	0.668 (0.507 <u>-</u> 0.879)	0.838 (0.634-1.11)	0.978 (0.737 ₋ 1.30)	1.17 (0.858-1.61)	1.32 (0.947 <u>-</u> 1.85)	1.47 (1.03-2.12)	1.63 (1.09-2.41)	1.86 (1.20-2.83)	2.03 (1.29-3.16)
30-min	0.776 (0.590-1.02)	0.919 (0.697-1.21)	1.15 (0.872-1.52)	1.35 (1.01-1.78)	1.61 (1.18-2.22)	1.82 (1.30-2.54)	2.02 (1.41-2.92)	2.25 (1.50-3.32)	2.55 (1.65-3.89)	2.80 (1.77-4.34)
60-min	0.988 (0.751-1.30)	1.17 (0.888-1.54)	1.47 (1.11-1.94)	1.71 (1.29-2.27)	2.05 (1.50-2.82)	2.31 (1.66-3.23)	2.58 (1.80-3.71)	2.86 (1.91-4.22)	3.25 (2.10-4.95)	3.56 (2.25-5.52)
2-hr	1.26 (0.965-1.66)	1.50 (1.14-1.96)	1.88 (1.42-2.46)	2.19 (1.66-2.89)	2.63 (1.93-3.60)	2.95 (2.14-4.13)	3.30 (2.33-4.77)	3.69 (2.48-5.42)	4.27 (2.77-6.46)	4.74 (3.01-7.31)
3-hr	1.46 (1.12-1.90)	1.73 (1.32-2.26)	2.17 (1.65-2.84)	2.53 (1.92-3.33)	3.03 (2.24-4.16)	3.41 (2.47-4.76)	3.81 (2.70-5.51)	4.28 (2.87-6.26)	4.98 (3.24-7.52)	5.58 (3.55-8.56)
6-hr	1.86 (1.43-2.42)	2.21 (1.70-2.88)	2.78 (2.12-3.62)	3.24 (2.47-4.25)	3.89 (2.88-5.31)	4.37 (3.19-6.08)	4.88 (3.49-7.04)	5.50 (3.71-8.01)	6.43 (4.19-9.65)	7.23 (4.61-11.0)
12-hr	2.36 (1.82-3.05)	2.80 (2.16-3.62)	3.52 (2.70-4.57)	4.12 (3.15-5.37)	4.95 (3.68-6.71)	5.56 (4.07-7.70)	6.22 (4.45-8.91)	7.00 (4.74-10.1)	8.17 (5.34-12.2)	9.16 (5.86-13.9)
24-hr	2.81 (2.18-3.62)	3.36 (2.60-4.33)	4.27 (3.29-5.51)	5.02 (3.85-6.51)	6.05 (4.52-8.16)	6.81 (5.00-9.37)	7.64 (5.48-10.9)	8.60 (5.84-12.4)	10.0 (6.58-14.8)	11.2 (7.21-16.9)
2-day	3.17 (2.46-4.06)	3.83 (2.98-4.92)	4.92 (3.81-6.32)	5.82 (4.48-7.52)	7.06 (5.30-9.49)	7.98 (5.89-10.9)	8.97 (6.47-12.7)	10.1 (6.90-14.5)	11.9 (7.82-17.5)	13.4 (8.61-20.0)
3-day	3.43 (2.68-4.39)	4.16 (3.24-5.32)	5.34 (4.15-6.86)	6.33 (4.89-8.15)	7.68 (5.78-10.3)	8.69 (6.43-11.9)	9.78 (7.07-13.8)	11.1 (7.55-15.8)	13.0 (8.58-19.1)	14.7 (9.47-21.9)
4-day	3.67 (2.86-4.68)	4.44 (3.46-5.67)	5.70 (4.44-7.30)	6.75 (5.22-8.69)	8.20 (6.18-11.0)	9.26 (6.87-12.6)	10.4 (7.56-14.7)	11.8 (8.07-16.8)	13.9 (9.18-20.3)	15.7 (10.2-23.3)
7-day	4.33 (3.39-5.51)	5.20 (4.07-6.62)	6.63 (5.18-8.46)	7.82 (6.07-10.0)	9.44 (7.15-12.6)	10.7 (7.92-14.5)	12.0 (8.71-16.8)	13.5 (9.27-19.1)	16.0 (10.5-23.2)	18.0 (11.7-26.6)
10-day	5.00 (3.93-6.34)	5.93 (4.66-7.53)	7.45 (5.83-9.48)	8.71 (6.78-11.1)	10.4 (7.92-13.9)	11.7 (8.74-15.9)	13.1 (9.55-18.4)	14.8 (10.1-20.8)	17.3 (11.4-25.0)	19.4 (12.6-28.5)
20-day	7.15 (5.64-9.02)	8.14 (6.41-10.3)	9.77 (7.67-12.4)	11.1 (8.68-14.1)	13.0 (9.84-17.0)	14.4 (10.7-19.2)	15.8 (11.4-21.7)	17.4 (12.0-24.4)	19.7 (13.1-28.2)	21.4 (13.9-31.3)
30-day	8.96 (7.08-11.3)	9.98 (7.88-12.6)	11.6 (9.17-14.7)	13.0 (10.2-16.5)	14.9 (11.3-19.4)	16.4 (12.2-21.7)	17.9 (12.8-24.2)	19.3 (13.4-26.9)	21.2 (14.2-30.4)	22.7 (14.8-33.0)
45-day	11.2 (8.89-14.1)	12.3 (9.70-15.4)	14.0 (11.0-17.6)	15.4 (12.1-19.4)	17.3 (13.2-22.4)	18.9 (14.0-24.7)	20.3 (14.6-27.2)	21.7 (15.0-30.0)	23.3 (15.6-33.1)	24.4 (15.9-35.3)
60-day	13.1 (10.4-16.4)	14.2 (11.2-17.7)	15.9 (12.6-20.0)	17.3 (13.6-21.9)	19.3 (14.7-24.9)	20.9 (15.6-27.3)	22.4 (16.0-29.8)	23.7 (16.5-32.6)	25.1 (16.8-35.6)	26.0 (17.0-37.5)

¹ Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS).


Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values.

Please refer to NOAA Atlas 14 document for more information.

Back to Top

PF graphical

PDS-based depth-duration-frequency (DDF) curves Latitude: 41.8039°, Longitude: -71.9768°




NOAA Atlas 14, Volume 10, Version 3


Created (GMT): Mon Jul 31 16:42:43 2023


Back to Top

Maps & aerials


Small scale terrain







Large scale aerial



Back to Top

US Department of Commerce

National Oceanic and Atmospheric Administration

National Weather Service

National Water Center

1325 East West Highway
Silver Spring, MD 20910

Questions?: HDSC.Questions@noaa.gov

<u>Disclaimer</u>



Killingly Engineering Associates
Civil Engineering & Surveying

114 Westont Roord

114 Westont Roord

114 Westont Roord

115 Westont Roord

115 Westont Roord

115 Westont Roord

116 Westont Roord

117 Westont Roord


117 Westont Roord


118 We

WOLF DEN ROAD BROOKLYN, CONNECTICUT

RYAN KELLEHER

DRAINAGE AREA PLAN PREPARED FOR





HYDROLOGIC SOILS MAPPING/WATERSHED AREA

SCALE: 1'' = 200'






Brooklyn Land Use Department

69 South Main Street Brooklyn CT 06234 (860) 779-3411 x 31

Inland Wetlands	Zoning Enforcement	Blight Enforcement
SITE INSPECTI	ON NUMBER	1 2 3 4 5
Addr	Rd. MI4 L10-1	7 (25) 23 Date
_ & inspec	ted with Da	net Booth,
Norm	Thi beault a	net Booth, nd Raiff Sonterre.
Photos w	vere taken,	
The wetle	ands flags a	re all missing.
The wet	lands were f	lagged in NOV. 2003.
We look	ed at the u	retlands near
		work, near the
proposed	footing drain	outlet.
	ked at the I	
proposed	house and	driveway.
	e no wellan	
	end approv	
	ntative <u>M, Was</u>	
Owner or Authorized	Signature	











P.O. Box 421 Killingly, CT 06241 Phone: 860-779-7299 www.killinglengineering.com

June 26, 2023

Proposed Single Family Home

Tripp Hollow Investments, LLC Tripp Hollow Road Brooklyn, CT

APPLICATION PACKAGE CONTENTS – Inland Wetlands

- 1. Application fee: \$210.00
- 2. 5- full sized sets of plans dated: 6/15/2023
- 3. Inland Wetlands Application
- 4. List of adjacent landowners including across the street
- 5. CT DEEP Reporting Form
- 6. Web Soil Survey Map
- 7. Town GIS map
- 8. Applicant's Certification



INLAND WETLANDS & WATERCOURSES COMMISSION TOWN OF BROOKLYN, CONECTICUT

Date	Application #
------	---------------

APPLICATION -- INLAND WETLANDS & WATERCOURSES

APPLICANT TRIPP HOUSE INVESTMENTS WE MAILING ADDRESS 89 WAVRECAN RO, BROWNING CT. OGE APPLICANT'S INTEREST IN PROPERTY OWNER. PHONE: CELL 401-374-6543 HOME: E-MAIL BMEEHAN 4 @ YANGE, COM
PROPERTY OWNER IF DIFFERENT PHONE: CELL: HOME: MAILING ADDRESS EMAIL
ENGINEER/SURVEYOR (IF ANY) **LILING LY ENGINEERING ASSOCIATES* ATTORNEY (IF ANY)
PROPERTY LOCATION/ADDRESS) TRIPP HOLLOW RD.
MAP #_14 LOT #_10-1 ZONE <u>PA</u> TOTAL ACRES <u>4.26</u> ACRES OF WETLANDS ON PROPERTY <u>1.4</u>
PURPOSE AND DESCRIPTION OF THE ACTIVITY EXISTING SUBDINISION LOT FROM 2004, PROPOSED HOUSE, WELL, SEPTIC SYSTEM AND SITE GRADING IN THE UPLAND REVIEW AREA.
WETLANDS EXCAVATION AND FILL: FILL PROPOSED CUBIC YDS SQ FT
EXCAVATION PROPOSED _O CUBIC YDS SQ FT
LOCATION WHERE MATERIAL WILL BE PLACED: ON SITE OFF SITE
TOTAL REGULATED AREA ALTERED: SQ FT ACRES
EXPLAIN ALTERNATIVES CONSIDERED (REQUIRED):
MITIGATION MEASURES (IF REQUIRED): WETLANDS/WATERCOURSES CREATED: CY SQ FT ACRES
Is parcel located within 500ft of an adjoining Town? If yes, which Town(s)
Is the activity located within the watershed of a water company as defined in CT General Statutes 25-32A? \mathcal{Wo}

THE OWNER AND APPLICANT HEREBY GRANT THE BROOKLYN IWWC, THE BOARD OF SELECTMAN AND THEIR AUTHORIZED AGENTS PERMISSION TO ENTER THE SUBJECT PROPERTY FOR THE PURPOSE OF INSPECTION AND ENFORCEMENT OF THE IWWC REGULATIONS OF THE TOWN OF BROOKLYN. IF THE COMMISSION DETERMINES THAT OUTSIDE REVIEW IS REQUIRED, APPLICANT WILL PAY CONSULTING FEE. NOTE: DETERMINATION THAT THE INFORMATION PROVIDED IS INACCURATE MAY INVALIDATE THE IWWC DECISION AND RESULT IN ENFORCEMENT ACTION. APPLICANT: REQUIREMENTS STANDARD APPLICATION FEE \$ (\$150) ____ STATE FEE (\$60) ___ CHECK #____ NOTICE OF ACTION PUBLICATION FEE \$ CHECK # PUBLIC HEARING PUBLICATION FEE (\$100) \$_____ (SUBJECT TO CHANGE DEPENDING ON PAPER) CHECK#____ SIGNIFICANT ACTIVITY FEE (PUBLIC HEARING) (\$250) \$ CHECK # COMPLETION OF CT DEEP REPORTING FORM ORIGINAL PLUS COPIES OF ALL MATERIALS REQUIRED - NUMBER TO BE DETERMINED BY STAFF PRE-APPLICATION MEETING WITH THE WETLANDS AGENT IS RECOMMENDED TO EXAMINE THE SCOPE OF THE **ACTIVITY** SITE PLAN SHOWING LOCATION OF THE WETLANDS WITH EXISTING AND PROPOSED CONDITIONS. APPLICANT MAY BE REQUIRED TO HAVE A CERTIFIED SOIL SCIENTIST IDENTIFY THE WETLANDS. COMPLIANCE WITH THE CONNECTICUT EROSION & SEDIMENTATION CONTROL MANUAL IF THE PROPOSED ACTIVITY IS DEEMED TO BE A "SIGNIFICANT IMPACT ACTIVITY" A PUBLIC HEARING IS REQUIRED ALONG WITH THE FOLLOWING INFORMATION: O NAMES AND ADDRESSES OF ABUTTING PROPERTY OWNERS O ADDITIONAL INFORMATION AS CONTAINED IN IWWC REGULATIONS ARTICLE 7.6 ADDITIONAL INFORMATION/ACTION NEEDED:

OTHER APPLICATIONS MAY BE REQUIRED. CONTACT THESE AGENCIES FOR FURTHER INFORMATION: APPLICATION TO STATE OF CONNECTICUT DEEP

INLAND WATER RESOURCES DIVISION 79 ELM ST. HARTFORD, CT. 06106 1-860-424-3019

DEPARTMENT OF THE ARMY CORPS OF ENGINEERS 696 VIRGINIA ROAD CONCORD, MA. 01742 1-860-343-4789

STAFF USE ONLY:		
DECLARATORY RULING: AS OF RIGHT & NOT	N-REGULATED USES (SEE IWWC REGULA	TIONS SECTION 4
PERMIT REQUIRED:		
AUTHORIZED BY STAFF/CHAIR (NO AC	TIVITY IN WETLANDS/WATERCOURSE AND	MINIMAL IMPACT
CHAIR, BROOKLYN IWWC	WETLANDS OFFICER	
AUTHORIZED BY IWWC		
Significant Activity/Pubi	IC HEARING	
No permit required		
OUTSIDE OF UPLAND REVIEW AREA		
NO IMPACT		
CHAIR, BROOKLYN IWWC	WETLANDS OFFICER	
Timber Harvest		

LIST OF AJACENT LAND OWNERS as of 6/26/2023 GIS

Meehan Builders, LLC Tripp Hollow Road Brooklyn, CT

Job No. 16069

MAP/BLOCK/LOT
BROOKLYN

NAME

Map 14, Lot 10-2

ADAM TUCKER & BETHANY S. TUCKER

184 TRIPP HOLLOW RD BROOKLYN, CT 06234

Map 14, Lot 10-3

MICHAEL J. CAPUANO 192 TRIPP HOLLOW RD BROOKLYN, CT 06234

Map 14, Lot 10-4

DEANE RETTIG & ELIZABETH A. RETTIG

208 TRIPP HOLLOW RD BROOKLYN, CT 06234

Map 14, Lot 10

MEEHAN BUILDERS, LLC

89 WAUREGAN RD BROOKLYN, CT 06234

Map 14, Lot 10-59

TATNIC HILL INVESTMENTS, LLC

89 WAUREGAN RD BROOKLYN, CT 06234

Map 15, Lot 19-18

KEVIN FERRA

176 TRIPP HOLLOW RD BROOKLYN, CT 06234



79 Elm Street • Hartford, CT 06106-5127

www.ct.gov/deep

Affirmative Action/Equal Opportunity Employer


Statewide Inland Wetlands & Watercourses Activity Reporting Form

Please complete this form in accordance with the instructions on pages 2 and 3 and mail to:

DEEP Land & Water Resources Division, Inland Wetlands Management Program, 79 Elm Street, 3rd Floor, Hartford, CT 06106


Incomplete or incomprehensible forms will be mailed back to the inland wetlands agency.

_	
	PART I: Must Be Completed By The Inland Wetlands Agency
1.	DATE ACTION WAS TAKEN: year: month:
2.	ACTION TAKEN (see instructions - one code only):
3.	WAS A PUBLIC HEARING HELD (check one)? yes ☐ no ☐
4.	NAME OF AGENCY OFFICIAL VERIFYING AND COMPLETING THIS FORM:
	(print name) (signature)
	PART II: To Be Completed By The Inland Wetlands Agency Or The Applicant
5.	TOWN IN WHICH THE ACTIVITY IS OCCURRING (print name):
	does this project cross municipal boundaries (check one)? yes no
	if yes, list the other town(s) in which the activity is occurring (print name(s)):
6.	LOCATION (see instructions for information): USGS quad name:
	subregional drainage basin number:
7.	NAME OF APPLICANT, VIOLATOR OR PETITIONER (print name):
8.	NAME & ADDRESS OF ACTIVITY / PROJECT SITE (print information):
	briefly describe the action/project/activity (check and print information): temporary permanent description:
	Construction of a single tarrily home
9.	ACTIVITY PURPOSE CODE (see instructions - one code only):
10.	ACTIVITY TYPE CODE(S) (see instructions for codes):,,,,,
11.	WETLAND / WATERCOURSE AREA ALTERED (see instructions for explanation, must provide acres or linear feet):
	wetlands: acres open water body: acres stream: linear feet
12.	UPLAND AREA ALTERED (must provide acres): acres
13.	AREA OF WETLANDS / WATERCOURSES RESTORED, ENHANCED OR CREATED (must provide acres): acres
DA	TE RECEIVED: PART III: To Be Completed By The DEEP DATE RETURNED TO DEEP:
FO	PM COMPLETED: VES NO



Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
3	Ridgebury, Leicester, and Whitman soils, 0 to 8 percent slopes, extremely stony	0.2	1.0%
17	Timakwa and Natchaug soils, 0 to 2 percent slopes	2.4	14.3%
51B	Sutton fine sandy loam, 0 to 8 percent slopes, very stony		3.1%
52C	Sutton fine sandy loam, 2 to 15 percent slopes, extremely stony	7.6	44.8%
59D	Gloucester gravelly sandy loam, 15 to 35 percent slopes, extremely stony	3.8	22.1%
73C	Charlton-Chatfield complex, 0 to 15 percent slopes, very rocky	2.5	14.8%
Totals for Area of Interest		17.0	100.0%





Killingly Engineering Associates

P.O. Box 421 Killingly, CT 06241 Phone: 860-779-7299 www.killinglyengineering.com

June 26, 2023

Meehan Builders, LLC Tripp Hollow Road Brooklyn, CT


Per Section 7.7 of the Inland Wetland and Watercourses regulations


The applicant certifies that:

- a. The property on which the regulated activity is proposed is not located within 500 feet of the boundary of an adjoining municipality);
- b. Traffic attributable to the completed project on the site will not use streets within the adjoining municipality to enter or exit the site;
- c. Sewer or water drainage from the project site will not flow through and impact the sewage or drainage system within the adjoining municipality;
- d. Water run-off from the improved site will not impact streets of other municipal or private property within the adjoining municipality.

Applicant-

Date





EROSION AND SEDIMENT CONTROL PLANS

REFERENCE IS MADE TO:

- 1. Connecticut Guidelines for Soil Erosion and Sediment Control 2002 (2002 Guidelines)
- 2. Soil Survey of Windham County Connecticut, U.S.D.A. Soil Conservation Service 1983.

The proposed development area is comprised mainly of three soil types; Timakwa and Natchaug (17), Sutton (52C) and Gloucester (59D)

- 17 Timakwa and Natchaug soils, 0-2% slopes
- Included with these soils in mapping are areas of very poorly drained Catden soils where the muck is more than 51 inches thick over mineral substratum. Also included are areas of very poorly drained Whitman, Menlo, Scarboro, Maybid, and Saco soils. Whitman and Menlo soils formed in loamy glacial till. Scarboro soils are sandy and Maybid soils are silty and clayey. Saco soils are on flood plains and are silty. Minor components make up about 15 percent of the map unit Slope: nearly level
- Landscape: depressions Size of map unit: Areas commonly range from 3 to 150 acres.

52C Sutton fine sandy loam, 2 to 15 percent slopes, extremely stony

Included with this soil in mapping are greas of well drained Canton. Charlton, and Paxton soils that are higher on the landscape. Canton soils are loamy over sandy Charlton soils are sandy loam throughout, and Paxton soils have a dense substratum. Also included are small areas of poorly drained Leicester soils in depressions and drainageways. Small areas of moderately well drained Woodbridge soils are included in areas with a dense substratum. Some areas have a silt loam surface laver and subsoil. A few greas in New London County include well drained Narragansett soils and moderately well drained Rainbow soils. Minor components make up about 20 percent of this map unit. Slope: nearly level to strongly sloping

Landscape: drainageways on uplands, depressions on uplands Surface cover: 3 to 15 percent stones Size of map unit: Areas commonly range from 3 to 50 acres.

59D-Gloucester gravelly sandy loam, 15 to 35 percent slopes, extremely stony

Included with these soils in mapping are areas of moderately well drained Sutton soils in slight depressions on the landscape, and poorly drained Leicester soils in depressions and drainageways. Also included are areas of moderately deep, somewhat excessively drained and well drained Chatfield soils where bedrock is 20 to 40 inches below the surface. Shallow, somewhat excessively drained and well drained Hollis soils are in small areas where bedrock is 10 to 20 inches below the surface. Minor components make up about 20 percent of the map unit.

DEVELOPMENT SCHEDULE:

- 1. Construction will begin with clearing, grubbing and rough grading of the proposed site. The work will be confined to areas adjacent to the proposed buildings, septic systems and driveways. Topsoil will be stockpiled on site and utilized during final
- 2. The site will be graded so that all possible trees on site will be saved to provide buffers to adjoining lots. **DEVELOPMENT CONTROL PLAN:**
- 1. Development of the site will be performed by the individual lot owner, who will be responsible for the installation and maintenance of erosion and sediment control measures required throughout construction.
- 2. The sedimentation control mechanisms shall remain in place from start of construction until permanent vegetation has been established. The representative for the Town of Brooklyn will be notified when sediment and erosion control structures are initially in place. Any additional soil & erosion control measures requested by the Town or its agent, shall be installed immediately. Once the proposed development, seeding and planting have been completed, the representative shall again be notified to inspect the site. The control measures will not be removed until this inspection is complete.
- 3. All stripping is to be confined to the immediate construction area. Topsoil shall be stockpiled so that slopes do not exceed 2 to 1. A hay bale sediment barrier is to surround each stockpile and a temporary vegetative cover shall be provided.
- 4. Dust control will be accomplished by spraying with water and if necessary, the application of calcium chloride.
- 5. The proposed planting schedule is to be adhered to during the planting of disturbed areas throughout the proposed
- 6. Final stabilization of the site is to follow the procedures outlined in "Permanent Vegetative Cover". If necessary a temporary vegetative cover is to be provided until a permanent cover can be applied.

FILTER BARRIER INSTALLATION AND MAINTENANCE:

- 1. Dig a 6" deep trench on the uphill side of the barrier location.
- 2. Position the posts on the downhill side of the barrier and drive the posts 1.5 feet into the ground.
- 3. Lay the bottom 6" of the fabric in the trench to prevent undermining and backfill.
- 5. Inspections will be made at least once per week and within 24 hours of the end of a storm with a rainfall amount of 0.5 Route traffic patterns within the site to avoid existing or newly planted
- 6. Sediment deposits are to be removed when they reach a height of 1 foot behind the barrier or half the height of the barrier and are to be deposited in an area which is not regulated by the inland wetlands commission.
- 7. Replace or repair the fence within 24 hours of observed failure. Failure of the fence has occurred when sediment fails to
- be retained by the fence because: - the fence has been overtopped, undercut or bypassed by runoff water, - the fence has been moved out of position (knocked over), or
- the geotextile has decomposed or been damaged.

HAY BALE INSTALLATION AND MAINTENANCE:

- 1. Bales shall be placed as shown on the plans with the ends of the bales tightly abutting each other.
- 2. Each bale shall be securely anchored with at least 2 stakes and gaps between bales shall be wedged with straw to prevent water from passing between the bales.
- 3. Inspect bales at least once per week and within 24 hours of the end of a storm with a rainfall amount of 0.5 inches or greater to determine maintenance needs.
- 4. Remove sediment behind the bales when it reaches half the height of the bale and deposit in an area which is not regulated by the Inland Wetlands Commission.
- 5. Replace or repair the barrier within 24 hours of observed failure. Failure of the barrier has occurred when sediment fails to be retained by the barrier because:
- the barrier has been overtopped, undercut or bypassed by runoff water,
- the barrier has been moved out of position, or - the hay bales have deteriorated or been damaged

TEMPORARY VEGETATIVE COVER:

Grass species shall be appropriate for the season and site conditions. Appropriate species are outlined in Figure TS-2 in the 2002 Guidelines.

TIMING CONSIDERATIONS

Seed with a temporary seed mixture within 7 days after the suspension of grading work in disturbed areas where the suspension of work is expected to be more than 30 days but less than 1 year.

Install needed erosion control measures such as diversions, grade stabilization structures, sediment basins and grassed

Grade according to plans and allow for the use of appropriate equipment for seedbed preparation, seeding, mulch application, and mulch anchoring.

ENDORSED BY THE BROOKLYN INLAND

WETLANDS COMMISSION

CHAIRMAN

ANY CHANGES TO THESE PLANS WITHIN 200' OF WETLANDS OR WATERCOURSES MUST BE RESUBMITTED TO THE BROOKLYN INLAND WETLANDS COMMISSION.

THE APPLICANT WILL CONTACT THE BROOKLYN INLAND WETLANDS COMMISSION OR ITS AGENT AFTER ALL FROSION AND SEDIMENT CONTROL MEASURES ARE INSTALLED, PRIOR TO ANY CONSTRUCTION OR EXCAVATION ON THE PROPERTY.

SEEDBED PREPARATION

Loosen the soil to a depth of 3-4 inches with a slightly roughened surface. If the area has been recently loosened or disturbed, no further roughening is required. Soil preparation can be accomplished by tracking with a bulldozer, discing, harrowing, raking or dragging with a section of chain link fence. Avoid excessive compaction of the surface by equipment traveling back and forth over the surface. If the slope is tracked, the cleat marks shall be perpendicular to the anticipated direction of the flow of surface water.

If soil testing is not practical or feasible on small or variable sites, or where timing is critical, fertilizer may be applied at the rate of 300 pounds per acre or may be applied using rates given in Figure TS-1 in the 2002 Guidelines.

Apply seed uniformly by hand cyclone seeder, drill, cultipacker type seeder or hydroseeder at a minimum rate for the selected species. Increase seeding rates by 10% when hydroseeding.

Temporary seedings made during optimum seeding dates shall be mulched according to the recommendations in the 2002 Guidelines. When seeding outside of the recommended dates, increase the application of mulch to provide 95%-100% coverage.

Inspect seeded area at least once a week and within 24 hours of the end of a storm with a rainfall amount of 0.5 inch or greater for seed and mulch movement

Where seed has moved or where soil erosion has occurred, determine the cause of the failure. Repair eroded areas and install additional controls if required to prevent reoccurrence of erosion.

Continue inspections until the grasses are firmly established. Grasses shall not be considered established until a ground cover is achieved which is mature enough to control soil erosion and to survive severe weather conditions (approximately 80% vegetative cover).

PERMANENT VEGETATIVE COVER:

MAINTENANCE

Refer to Permanent Seeding Measure in the 2002 Guidelines for specific applications and details related to the installation and maintenance of a permanent vegetative cover. In general, the following sequence of operations shall apply:

- Topsoil will be replaced once the excavation and grading has been completed. Topsoil will be spread at a minimum compacted depth of 4".
- 2. Once the topsoil has been spread, all stones 2" or larger in any dimension
- 3. Apply agricultural ground limestone at a rate of 2 tons per acre or 100 lbs. per 1000 s.f. Apply 10-10-10 fertilizer or equivalent at a rate of 300 lbs. per acre or 7.5 lbs. per 1000 s.f. Work lime and fertilizer into the soil to a depth of
- 4. Inspect seedbed before seeding. If traffic has compacted the soil, retill
- 5. Apply the chosen grass seed mix. The recommended seeding dates are: April 1 to June 15 & August 15 October 1.

6. Following seeding, firm seedbed with a roller. Mulch immediately following seeding. If a permanent vegetative stand cannot be established by September 30, apply a temporary cover on the topsoil such as netting, mat or organic mulch.

EROSION AND SEDIMENT CONTROL NARRATIVE: PRINCIPLES OF EROSION AND SEDIMENT CONTROL

The primary function of erosion and sediment controls is to absorb erosional energies and reduce runoff velocities that force the detachment and transport of soil and/or encourage the deposition of eroded soil particles before they reach any

KEEP LAND DISTURBANCE TO A MINIMUM

The more land that is in vegetative cover, the more surface water will infiltrate into the soil, thus minimizing stormwater runoff and potential erosion. Keeping land disturbance to a minimum not only involves minimizing the extent of exposure at any one time, but also the duration of exposure. Phasing, sequencing and construction scheduling are interrelated. Phasing divides a large project into distinct sections where construction work over a specific area occurs over distinct periods of time and each phase is not dependent upon a subsequent phase in order to be functional. A sequence is the order in which construction activities are to occur during any particular phase. A sequence should be developed on the premise of "first things first" and "last things last" with proper attention given to the inclusion of adequate erosion and sediment control measures. A construction schedule is a sequence with time lines applied to it and should address the potential overlap of actions in a sequence which may be in conflict with each

- Limit areas of clearing and grading. Protect natural vegetation from
- Phase construction so that areas which are actively being developed at any one time are minimized and only that area under construction is exposed. Clear only those areas essential for construction.
- Sequence the construction of storm drainage systems so that they are operational as soon as possible during construction. Ensure all outlets are stable before outletting storm drainage flow into them.
- Schedule construction so that final grading and stabilization is completed as soon as possible.

SLOW THE FLOW

Detachment and transport of eroded soil must be kept to a minimum by absorbing and reducing the erosive energy of water. The erosive energy of water increases as the volume and velocity of runoff increases. The volume and velocity of runoff increases during development as a result of reduced infiltration rates caused by the removal of existing vegetation, removal of topsoil, compaction of soil and the construction of impervious surfaces.

- Use diversions, stone dikes, silt fences and similar measures to break flow
- Avoid diverting one drainage system into another without calculating the potential for downstream flooding or erosion.

KEEP CLEAN RUNOFF SEPARATED

Clean runoff should be kept separated from sediment laden water and should not be directed over disturbed areas without additional controls. Additionally, prevent the mixing of clean off-site generated runoff with sediment laden runoff generated

Segregate construction waters from clean water.

Divert site runoff to keep it isolated from wetlands, watercourses and drainage ways that flow through or near the development until the sediment in that runoff is trapped or detained.

REDUCE ON SITE POTENTIAL INTERNALLY AND INSTALL PERIMETER CONTROLS

While it may seem less complicated to collect all waters to one point of discharge for treatment and just install a perimeter control, it can be more effective to apply internal controls to many small sub-drainage basins within the site. By reducing sediment loading from within the site, the chance of perimeter control failure and the potential off-site damage that it can cause is reduced. It is generally more expensive to correct off-site damage than it is to install proper

- Control erosion and sedimentation in the smallest drainage area possible. It is easier to control erosion than to contend with sediment after it has been carried downstream and deposited in unwanted areas.
- Direct runoff from small disturbed areas to adjoining undisturbed vegetated areas to reduce the potential for concentrated flows and increase settlement and filtering of sediments.
- Concentrated runoff from development should be safely conveyed to stable outlets using rip rapped channels, waterways, diversions, storm drains
- Determine the need for sediment basins. Sediment basins are required on larger developments where major grading is planned and where it is impossible or impractical to control erosion at the source. Sediment basins are needed on large and small sites when sensitive areas such as wetlands, watercourses, and streets would be impacted by off-site sediment deposition. Do not locate sediment basins in wetlands or permanent or intermittent watercourses. Sediment basins should be located to intercept runoff prior to its entry into the wetland or
- Grade and landscape around buildings and septic systems to divert water away from them.

SEPTIC SYSTEM CONSTRUCTION NOTES

- 1. The building, septic system and well shall be accurately staked in the field by a licensed Land Surveyor in the State of Connecticut, prior to construction.
- 2. Topsoil shall be removed and in the area of the primary leaching field scarified, prior to placement of septic fill. Septic fill specifications are as follows:

- Max. percent of gravel (material between No. 4 & 3 inch sieves) = 45% GRADATION OF FILL (MINUS GRAVEL)

SIEVE	PERCENT PASSING	PERCENT PASSING
<u>SIZE</u>	(WET SIEVE)	(DRY SIEVE)
No. 4	100%	100%
No. 10	70% - 100%	70% - 100%
No. 40	10% - 50%	10% - 75%
No. 100	0% - 20%	0% - 5%
No. 100	0% — 20%	0% - 5%
No. 200	0% — 5%	0% - 2.5%

- Fill material shall be approved by the sanitarian prior to placement. It shall be compacted in 6" lifts and shall extend a minimum of ten feet (10') beyond the last leaching trench before tapering off.
- 3. Septic tank shall be two compartment precast 1000 gallon tank with gas deflector and outlet filter as manufactured by Jolley Precast,
- 4. Distribution boxes shall be 4 hole precast concrete as manufactured by Jolley Precast, Inc. or equal.
- 5. All precast structures such as septic tanks, distribution boxes, etc. shall be set level on six inches (6") of compacted gravel base at the elevations specified on the plans.
- 6. Solid distribution pipe shall be 4" diameter PVC meeting ASTM D-3034 SDR 35 with compression gasket joints. It shall be laid true to the lines and grades shown on the plans and in no case have a slope less than 0.125 inches per foot.
- 7. Perforated distribution pipe shall be 4" diameter PVC meeting ASTM D-2729 or ASTM D-3350, 1500 lb. minimum crush.
- 8. Sewer pipe from the foundation wall to the septic tank shall be schedule 40 PVC meeting ASTM D 1785. It shall be laid true to the grades shown on the plans and in no case shall have a slope less than 0.25 inches per foot.
- 9. Force main pressure pipe from pump chamber to the leaching field shall be 2" diameter pvc meeting ASTM D 2241 SDR 21.
- 10. Solid footing drain outlet pipe shall be 4" Diameter PVC meeting ASTM D 3034, SDR 35 with compression gasketed joints. Footing drain outlet pipe shall <u>not</u> be backfilled with free draining material, such as gravel, broken stone, rock fragments, etc.


ANGLE 10° UP SLOPE

FOR STABILITY AND SELF CLEANING

COMPACTED /

SILT FENCE

NOT TO SCALE



4" CONCRETE ACCESS—

COVER (TYP.)

FINISHED GRADE

KNOCKOUT INLET AND

CAST CONCRETE COVERS—

✓ IF MORE THAN 12" OF COVER —

^{/2}→ X → SOLID BLOCK—

· 3" VENT -

LIQUID LEVEL

5'-8"

CROSS SECTION

NOT TO SCALE

HAYBALE BARRIER

IS REQUIRED IN THE FIELD, PROVIDE

ACCESS COVERS TO GRADE.

3" VENT —

f" OUTLET

| WITH FILTER_

PROVIDE POSITIVE GRADE AWAY FROM


GROUNDWATER FROM ENTERING CHAMBER

--- FINISHED GRADE

OUTLET


MANHOLE COVER TO PREVENT


RIBS INSIDE -



- BEDROCK

TYPICAL LEACHING TRENCH SECTION NOT TO SCALE





DETAIL SHEET - LOT 1 PREPARED FOR

TRIPP HOLLOW INVESTMENTS, LLC

> TRIPP HOLLOW ROAD BROOKLYN, CONNECTICUT



Killingly Engineering Associates Civil Engineering & Surveying

> 114 Westcott Road P.O. Box 421 Killingly, Connecticut 06241 (860) 779-7299 www.killinglyengineering.com

DATE: 6/15/2023 DRAWN: AMR SCALE: NOT TO SCALE DESIGN: NET SHEET: 2 OF 2 CHK BY: ---DWG. No: CLIENT FILE JOB No: 16069

NORMAND THIBEAULT, JR., P.E. No. 22834 DATE

INLAND WETLANDS & WATERCOURSES COMMISSION TOWN OF BROOKLYN, CONECTICUT

Date 06/21/2023

Application	#

APPLICATION -- INLAND WETLANDS & WATERCOURSES

Wal-N	Mart Real Estate Business Trus	t MAILING ADDRESS	01 SE 10th Street	, Bentonville, AR	72716
APPLICANT'S INTER	Mart Real Estate Business Trus	PHONE _ (479)270-702	4	mail_mike.ru	therford@walmart
PROPERTY OWNER MAILING ADDRESS_	IF DIFFERENT Wal-Mart Real Esta _ PO Box 8050 Bentonville, AR,	te Business Trust 72712	PHONEEMAIL		
Engineer/Surveye Attorney (if any)	UR (IF ANY)	(c/o Jeff Bord - 65 LaSa	lle Road, West Ha	artford, CT	
PROPERTY LOCATIO MAP # 41 LO	N/ADDRESS 450 Providence Roa DT # 10 ZONE PC TOTAL A	ad, Brooklyn, CT Acres 25.48 Acres of	WETLANDS ON PROI	PERTY 1.37 +/	
Online grocer	скиртиом об тне Астіліту_ y pick up addition with park	king modifications -			
EXCAVATION PROPORTION WHERE A TOTAL REGULATED EXPLAIN ALTERNATION	CUBIC YDS 0 SQ FT 0 CUBIC YDS 0 SQ FT 0 MATERIAL WILL BE PLACED: ON SITE AREA ALTERED: SQ FT 4,637 A VES CONSIDERED (REQUIRED): native. No additional benefi	OFF SITE CRES_ 0.11			
MITIGATION MEASE	ures (if required): Wetlands/wat	ERCOURSES CREATED: CY_	N/A SQFT N/	A ACRES N/A	
IS PARCEL LOCATED IS THE ACTIVITY LOC	WITHIN 500FT OF AN ADJOINING TOV ATED WITHIN THE WATERSHED OF A V	VN? NO IF YES, WHICH VATER COMPANY AS DEFINE	Town(s) D IN CT GENERAL STA	ATUTES 25-32A?	No
SUBJECT PROPERTY FO	ICANT HEREBY GRANT THE BROOKLYN IW R THE PURPOSE OF INSPECTION AND ENFOR TSIDE REVIEW IS REQUIRED, APPLICANT WIR	CEMENT OF THE IWWC REGU			
NOTE: DETERMINATIO	N THAT THE INFORMATION PROVIDED IS IN	ACCURATE MAY INVALIDATE TE	E IWWC DECISION AND	RESULT IN ENFORCEME	NT ACTION.
APPLICANT:	Mike Rutherford	D	ATEJune_21,20	023 13:02 CDT	
OWNER:	Mike Rutherford Mike Rutherford	D	June 21, 202 ATE	3 13:02 CDT	

REQUIREMENTS
APPLICATION FEE \$ 200.00 STATE FEE (\$60.00) 60.00
COMPLETION OF CT DEEP REPORTING FORM
ORIGINAL PLUS COPIES OF ALL MATERIALS REQUIRED - NUMBER TO BE DETERMINED BY STAFF
PRE-APPLICATION MEETING WITH THE WETLANDS AGENT IS RECOMMENDED TO EXAMINE THE SCOPE OF THE ACTIVITY
SITE PLAN SHOWING LOCATION OF THE WETLANDS WITH EXISTING AND PROPOSED CONDITIONS. APPLICANT MAY BE REQUIRED TO HAVE A CERTIFIED SOIL SCIENTIST IDENTIFY THE WETLANDS.
Compliance with the Connecticut Erosion & Sedimentation Control Manual
IF THE PROPOSED ACTIVITY IS DEEMED TO BE A "SIGNIFICANT IMPACT ACTIVITY" A PUBLIC HEARING IS REQUIRED ALONG WITH THE FOLLOWING INFORMATION: O NAMES AND ADDRESSES OF ABUTTING PROPERTY OWNERS ADDITIONAL INFORMATION AS CONTAINED IN IWWC REGULATIONS ARTICLE 7.6
ADDITIONAL INFORMATION/ACTION NEEDED:
APPLICATION TO STATE OF CONNECTICUT DEEP INLAND WATER RESOURCES DIVISION 79 ELM ST. HARTFORD, CT. 06106 1-860-424-3019 DEPARTMENT OF THE ARMY CORPS OF ENGINEERS 696 VIRGINIA ROAD CONCORD, MA. 01742 1-860-343-4789
STAFF USE ONLY:
DECLARATORY RULING: As OF RIGHT & NON-REGULATED USES (SEE IWWC REGULATIONS SECTION 4)
PERMIT REQUIRED:AUTHORIZED BY STAFF/CHAIR (NO ACTIVITY IN WETLANDS/WATERCOURSE AND MINIMAL IMPACT)
CHAIR, BROOKLYN IWWC WETLANDS OFFICER AUTHORIZED BY IWWC
SIGNIFICANT ACTIVITY/PUBLIC HEARING
NO PERMIT REQUIRED
OUTSIDE OF UPLAND REVIEW AREA NO IMPACT
CHAIR, BROOKLYN IWWC WETLANDS OFFICER
TIMBER HARVEST



79 Elm Street • Hartford, CT 06106-5127

www.ct.gov/deep

Affirmative Action/Equal Opportunity Employer

STATEWIDE INLAND WETLANDS & WATERCOURSES ACTIVITY REPORTING FORM

Pursuant to section 22a-39(m) of the General Statutes of Connecticut and section 22a-39-14 of the Regulations of Connecticut State Agencies, inland wetlands agencies must complete the Statewide Inland Wetlands & Watercourses Activity Reporting Form for <u>each</u> action taken by such agency.

This form may be made part of a municipality's inland wetlands application package. If the municipality chooses to do this, it is recommended that a copy of the Town and Quadrangle Index of Connecticut and a copy of the municipality's subregional drainage basin map be included in the package as well.

Please remember, the inland wetlands agency is responsible for ensuring that the information provided is accurate and that it reflects the <u>final</u> action of the agency. Incomplete or incomprehensible forms will be mailed back to the agency. Instructions for completing the form are located on the following page.

The inland wetlands agency shall mail completed forms for actions taken during a calendar month no later than the 15th day of the following month to the Department of Energy and Environmental Protection (DEEP). <u>Do not</u> mail this cover page or the instruction page. **Please mail only the completed yellow reporting form to**:

Wetlands Management Section
Inland Water Resources Division
Department of Energy & Environmental Protection
79 Elm Street, 3rd Floor
Hartford, CT 06106

Questions may be directed to the DEEP's Wetlands Management Section at (860) 424-3019.

INSTRUCTIONS FOR COMPLETING

THE STATEWIDE INLAND WETLANDS & WATERCOURSES ACTIVITY REPORTING FORM

Use a separate form to report each action taken by the Agency. Complete the form as described below.

PLEASE PRINT CLEARLY

PART I: To Be Completed By the Inland Wetlands Agency Only

- 1. Enter the year and month the Inland Wetlands Agency took the action being reported. If multiple actions were taken regarding the same project or activity then multiple forms need to be completed. Enter ONE year and month per form.
- 2. Enter <u>ONE</u> code letter to describe the final action or decision taken by the inland Wetlands Agency. *Do not submit a reporting form for withdrawn applications*. Do not enter multiple code letters (for example; if an enforcement notice was given and subsequent permit issued two forms for the two separate actions are to be completed).
 - A = A Permit Granted by the Inland Wetlands Agency (not including map amendments, see code D below)
 - B = Any Permit Denied by the Inland Wetlands Agency
 - C = A Permit Renewed or Amended by the Inland Wetlands Agency
 - D = A Map Amendment to the Official Town Wetlands Map or -An Approved/Permitted Wetland or Watercourse Boundary Amendment to a Project Site Map
 - E = An Enforcement Notice of Violation, Order, Court Injunction, or Court Fines
 - F = A Jurisdictional Ruling by the Inland Wetlands Agency (i.e.; activities "permitted as of right" or activities considered non-regulated)
 - G = An Agent Approval pursuant to CGS 22a-42a(c)(2)
 - H = An Appeal of Agent Approval Pursuant to 22a-42a(c)(2)
- 3. Check "Yes" if a public hearing was held in regards to the action taken; otherwise check "No".
- 4. Enter the name of the Inland Wetlands Agency official verifying that the information provided on this form is accurate and that it reflects the <u>FINAL</u> action of the agency.

PART II: To Be Completed by the Inland Wetlands Agency or the Applicant - If Part II is completed by the applicant, the applicant must return the form to the Inland Wetlands Agency. The Inland Wetlands Agency must ensure that the information provided is accurate and that it reflects the FINAL action of the Agency.

- 5. Enter the name of the municipality for which the Inland Wetlands Agency has jurisdiction and in which the action/project/activity is occurring.
 - Check "Yes" if the action/project/activity crosses municipal boundaries and enter the name(s) of the other municipality(ies) where indicated. Check "No" if it does not cross municipal boundaries.
- 6. Enter the USGS Quad Map name or number (1 through 115) as found on the Connecticut Town and Quadrangle Index Map (the directory to all USGS Quad Maps) that contains the location of the action/project/activity. See the following website for USGS Quad Map names and numbers: http://ct.gov/deep/gis/resources/Index_NamedQuadTown.pdf
 - ALSO enter the four-digit identification number of the corresponding Subregional Drainage Basin in which the action/project/activity is located. If the action/project/activity is located in more than one subregional drainage basin, enter the number of the basin in which the majority of the action/project/activity is located. Town subregional drainage basin maps can be found at UConn CLEAR's website: http://clear.uconn.edu/data/map_set/index.htm
- 7. Enter the name of the individual applying for, petitioning, or receiving the action.
- 8. Enter the name and address or location of the action/project/activity. Check if the the action/project/activity is TEMPORARY or PERMANENT in nature. Also provide a brief description of the action/project/activity.

- CAREFULLY REVIEW the list below and enter ONE code letter which best characterizes the action/project/activity. All state agency projects must code "N".
 - A = Residential improvement by Homeowner
 - B = New Residential Development for Single Family Units
 - C = New Residential Development for Multi-Family / Condos
 - D = Commercial / Industrial Uses
 - E = Municipal Project
 - F = Utility Company Project
 - **G** = Agriculture, Forestry or Conservation
 - H = Wetland Restoration, Enhancement, Creation

- I = Storm Water / Flood Control
- J = Erosion / Sedimentation Control
- K = Recreation / Boating / Navigation
- L = Routine Maintenance
- **M** = Map Amendment
- N = State Agency Project
- P = Other (this code includes the approval of concept plans with no-on-the-ground work)
- 10. Enter between one and four code numbers to best characterize the project or activity being reported. Enter "NA" if this form is being completed for the action of map amendment. You must provide code 12 if the activity is located in an established upland review area (buffer, setback). You must provide code 14 if the activity is located <u>BEYOND</u> the established upland review area (buffer, setback) or <u>NO</u> established upland review area (buffer, setback) exists.
 - 1 = Filling
 - 2 = Excavation
 - 3 = Land Clearing / Grubbing (no other activity)
 - 4 = Stream Channelization
 - 5 = Stream Stabilization (includes lakeshore stabilization)
 - 6 = Stream Clearance (removal of debris only)
 - 7 = Culverting (not for roadways)

- 8 = Underground Utilities (no other activities)
- 9 = Roadway / Driveway Construction
- 10 = Drainage Improvements
- 11 = Pond, Lake Dredging / Dam Construction
- 12 = Activity in an Established Upland Review
 - Area
- 14 = Activity in Upland

Examples: Jurisdictional ruling allowing construction of a parking lot in an upland where the municipality does not have an established upland review area must use code 14; other possible codes are 2 and 10. Permitted construction of a free standing garage (residential improvement by homeowner) partially in an established upland review area with the remainder in the upland must use code 12 and 14; other possible codes are 1 and 2. Permitted dredging of a pond must use code 11; other possible codes are 12 and 5.

- 11. Leave blank for <u>TEMPORARY</u> alterations but please indicate action/project/activity is temporary under question #8 on the form. For <u>PERMANENT</u> alterations, enter in acres the area of wetland soils or watercourses altered. Include areas that are permanently altered, or are proposed to be, for all agency permits, denials, amendments, and enforcement actions. For those activities that involve filling or dredging of lakes, ponds or similar open water bodies enter the acres filled or dredged under "open water body". For those activities that involve directly altering a linear reach of a brook, river, lakeshore or similar linear watercourse, enter the total linear feet altered under "stream". Remember that these figures represent only the acreage altered not the total acreage of wetlands or watercourses on the site. You <u>MUST</u> provide all information in <u>ACRES</u> (or linear feet as indicated) including those areas less than one acre. To convert from square feet to acres, divide square feet by the number 43,560. Enter zero if there is no alteration.
- 12. Enter in acres the area of upland altered as a result of an <u>ACTIVITY REGULATED BY</u> the inland wetlands agency, or as a result of an <u>AGENT APPROVAL</u> pursuant to 22a-42a(c)(2). Leave blank for <u>TEMPORARY</u> alterations but please indicate action/project/activity is temporary under question #8 on the form. Include areas that are permanently altered, or proposed to be permanently altered, for all agency permits, denials, amendments, and enforcement actions. Inland wetlands agencies may have established an upland review area (also known as a buffer or setback) in which activities are regulated. Agencies may also regulate activities beyond these established areas. You <u>MUST</u> provide all information in <u>ACRES</u> including those areas less than one acre. To convert from square feet to acres, divide square feet by the number 43,560. Enter zero if there is no alteration. Remember that these figures represent only the upland acreage altered as a result of an activity regulated by the inland wetlands agency, or as a result of an agent approval.
- 13. Enter the acres that are, or are proposed to be, restored, enhanced or created for all agency permits, denials, amendments, and enforcement actions. NOTE restored or enhanced applies to previously existing wetlands or watercourses. Created applies to a non-wetland or non-watercourse area which is converted into wetlands or watercourses (question #10 must provide 12 and/or 14 as an answer, and question #12 must also be answered). You MUST provide all information in ACRES including those areas less than one acre. To convert from square feet to acres, divide square feet by the number 43,560. Enter zero if there is no restoration, enhancement or creation.

PART III: To Be Completed By The DEEP - Please leave this area blank. Incomplete or incomprehensible forms will be mailed back to the inland wetlands agency.



For CEEP Use Only	GIS CODE #:							-	89 9	
-------------------	-------------	--	--	--	--	--	--	---	------	--

79 Elm Street • Hartford, CT 06106-5127

www.ct.gov/deep

Affirmative Action/Equal Opportunity Employer

Statewide Inland Wetlands & Watercourses Activity Reporting Form

Please complete - <u>print clearly</u> - and mail this form in accordance with the Instructions on pages 2 and 3 to: Wetlands Management Section, Inland Water Resources Division, CT DEEP, 79 Elm Street – 3rd Floor, Hartford, CT 05106

	PART I: To Be Completed By the Municipal Inland Wetlands Agency Only
1.	DATE ACTION WAS TAKEN (enter one year and month): Year Month
2.	
3.	
4.	NAME OF AGENCY OFFICIAL VERIFYING AND COMPLETING THIS FORM:
7.	
	(type name) (signature)
	PART II: To Be Completed By the Municipal Inland Wetlands Agency or the Applicant
5.	TOWN IN WHICH THE ACTION IS OCCURRING (type name):
	Does this project cross municipal boundaries (check one)? Yes No X
	If Yes, list the other town(s) in which the action is occurring (type name(s)):,
6.	LOCATION (see directions for website information): USGS Quad Map Name: or Quad Number:
	Subregional Drainage Basin Number:
7.	NAME OF APPLICANT, VIOLATOR OR PETITIONER (type name): Bohler Engineering
8.	NAME & ADDRESS/LOCATION OF PROJECT SITE (type information):
	Briefly describe the action/project/activity (check and type information): Temporary Permanent X Online grocery pick up addition with parking modification
9.	ACTIVITY PURPOSE CODE (enter one code letter):D
10.	ACTIVITY TYPE CODE(S) (enter up to four code numbers): 8, 14,
11.	WETLAND / WATERCOURSE AREA ALTERED (type in acres or linear feet as indicated):
	Wetlands: 1.37 acres Open Water Body: acres Stream: linear feet
12.	UPLAND AREA ALTERED (type in acres as indicated): 0.11 acres
13.	AREA OF WETLANDS / WATERCOURSES RESTORED, ENHANCED OR CREATED (type in acres as Indicated): 0 acres
DA	TE RECEIVED: PART III: To Be Completed By the DEEP DATE RETURNED TO DEEP:
FO	ORM COMPLETED: YES NO FORM CORRECTED / COMPLETED: YES NO

—— FOR ———

Walmart


STORE #5777-228

PROPOSED


PICKUP AND SIGNAGE / STRIPING
IMPROVEMENTS AND BUILDING EXPANSION

WINDHAM COUNTY, CONNECTICUT

LOCATION OF SITE:
450 PROVIDENCE ROAD, TOWN OF BROOKLYN



SCALE: 1" = 1,000'
SOURCE: DANIELSON CONNECTICUT USGS
QUADRANGLE



SITE MAP

SCALE: 1" = 200'
SOURCE: 2023 MICROSOFT


DRAWING SHEET INDEX


-	
SHEET TITLE	SHEET NUMBER
COVER SHEET	COV-1
GENERAL NOTES SHEET	NS-1
EXISTING CONDITIONS PLAN	EC-1
OVERALL SITE PLAN - STOP SIGNS AND MARKINGS PLAN	SSM-1
DEMOLITION AND SITE CONSTRUCTION PLAN	SECP-1
DEMOLITION AND EROSION CONTROL PLAN	DM-1
SITE PLAN	SP-1
GRADING, DRAINAGE, & UTILITY PLAN	GD-1
SECP AND STOP SIGNS AND MARKINGS DETAIL SHEET	SECP/SSM DETAILS
DETAIL SHEET	DTL-1
DETAIL SHEET	DTL-2
DETAIL SHEET	DTL-3
SPECIFICATIONS SHEET	CSS-1
SPECIFICATIONS SHEET 2	CSS-2
ALTA/NSPS LAND TITLE SURVEY (BY OTHERS)	2 SHEETS

PREPARED BY



COVER SHEET








OPERCENTER #3777-220 50 PROVIDENCE ROAD, TOWN OF BROOM VAL-MART STORES, INC.





• "ALTA/NSPS LAND TITLE SURVEY" PREPARED BY CONTROL POINT ASSOCIATES, DATED: 05/30/2023 • "INITIAL REPORT OF GEOTECHNICAL INVESTIGATION", PREPARED BY WHITESTONE ASSOCIATES, INC., DATED: 05/31/2023

. THE FOLLOWING DOCUMENTS ARE INCORPORATED BY REFERENCE AS PART OF THIS SITE PLAN

PRIOR TO THE START OF CONSTRUCTION, THE CONTRACTOR MUST VERIFY THAT HE/SHE HAS THE LATEST EDITION OF THE DOCUMENTS REFERENCED ABOVE.

2. ALL ACCESSIBLE (A/K/A ADA) PARKING SPACES MUST BE CONSTRUCTED TO MEET, AT A MINIMUM. THE MORE STRINGENT OF THE REQUIREMENTS OF THE "AMERICANS WITH DISABILITIES ACT" (ADA) CODE (42 U.S.C. § 12101 et seg. AND 42 U.S.C. § 4151 et seg.) OR THE REQUIREMENTS OF THE JURISDICTION WHERE THE PROJECT IS TO BE CONSTRUCTED, AND ANY AND ALL AMENDMENTS TO BOTH WHICH ARE IN EFFECT WHEN THESE PLANS ARE COMPLETED.

3. PRIOR TO STARTING CONSTRUCTION, THE CONTRACTOR IS RESPONSIBLE TO ENSURE THAT ALL REQUIRED PERMITS AND APPROVALS HAVE BEEN OBTAINED. NO CONSTRUCTION OR FABRICATION SHALL BEGIN UNTIL THE CONTRACTOR HAS RECEIVED AND THOROUGHLY REVIEWED THE COMMENTS TO ALL PLANS AND OTHER DOCUMENTS REVIEWED AND APPROVED BY THE PERMITTING AUTHORITIES AND CONFIRMED THAT ALL NECESSARY OR REQUIRED PERMITS HAVE BEEN OBTAINED. CONTRACTOR MUST HAVE COPIES OF ALL PERMITS AND APPROVALS ON SITE AT ALL TIMES.

4. THE OWNER/CONTRACTOR MUST BE FAMILIAR WITH AND RESPONSIBLE FOR THE PROCUREMENT OF ANY AND ALL CERTIFICATIONS REQUIRED FOR THE ISSUANCE

5. ALL WORK MUST BE PERFORMED IN ACCORDANCE WITH THESE PLANS. SPECIFICATIONS AND CONDITIONS OF APPROVAL, AND ALL APPLICABLE REQUIREMENTS. RULES, REGULATIONS, STATUTORY REQUIREMENTS, CODES, LAWS AND STANDARDS OF ALL GOVERNMENTAL ENTITIES WITH JURISDICTION OVER THIS PROJECT 6. THE GEOTECHNICAL REPORT AND RECOMMENDATIONS SET FORTH HEREIN ARE A PART OF THE REQUIRED CONSTRUCTION DOCUMENTS AND, IN CASE OF CONFLICT, DISCREPANCY OR AMBIGUITY, THE MORE STRINGENT REQUIREMENTS AND/OR RECOMMENDATIONS CONTAINED IN THE PLANS AND THE GEOTECHNICAL REPORT AND RECOMMENDATIONS SHALL TAKE PRECEDENCE LINESS SPECIFICALLY NOTED OTHERWISE ON THE PLANS. THE CONTRACTOR MUST NOTIFY THE ENGINEER, IN WRITING, OF ANY SUCH CONFLICT, DISCREPANCY OR AMBIGUITY BETWEEN THE GEOTECHNICAL REPORTS AND PLANS AND SPECIFICATIONS PRIOR

7. THESE PLANS ARE BASED ON INFORMATION PROVIDED TO BOHLER ENGINEERING BY THE OWNER AND OTHERS PRIOR TO THE TIME OF PLAN PREPARATION. CONTRACTOR MUST FIELD VERIFY EXISTING CONDITIONS AND NOTIFY BOHLER ENGINEERING, IN WRITING, IMMEDIATELY IF ACTUAL SITE CONDITIONS DIFFER FROM THOSE SHOWN ON THE PLAN. OR IF THE PROPOSED WORK CONFLICTS WITH ANY OTHER SITE FEATURES.

8. ALL DIMENSIONS SHOWN ON THE PLANS MUST BE FIELD VERIFIED BY THE CONTRACTOR PRIOR TO THE START OF CONSTRUCTION. CONTRACTOR MUST NOTIFY NGINEER, IN WRITING, IF ANY CONFLICTS, DISCREPANCIES, OR AMBIGUITIES EXIST PRIOR TO PROCEEDING WITH CONSTRUCTION. NO EXTRA COMPENSATION VILL BE PAID TO THE CONTRACTOR FOR WORK WHICH HAS TO BE REDONE OR REPAIRED DUE TO DIMENSIONS OR GRADES SHOWN INCORRECTLY ON THESE PLANS PRIOR TO CONTRACTOR GIVING ENGINEER WRITTEN NOTIFICATION OF SAME AND ENGINEER, THEREAFTER, PROVIDING CONTRACTOR WITH WRITTEN AUTHORIZATION TO PROCEED WITH SUCH ADDITIONAL WORK.

9. CONTRACTOR MUST REFER TO THE ARCHITECTURAL/BUILDING PLANS "OF RECORD" FOR EXACT LOCATIONS AND DIMENSIONS OF ENTRY/EXIT POINTS, ELEVATIONS,

10 PRIOR TO THE START OF CONSTRUCTION THE CONTRACTOR MUST COORDINATE THE RUIL DING LAYOUT BY CAREFUL REVIEW OF THE ENTIRE SITE PLAN AND THE LATEST ARCHITECTURAL PLANS (INCLUDING BUT NOT LIMITED TO STRUCTURAL MECHANICAL ELECTRICAL PLUMBING AND FIRE SUPPRESSION PLAN WHERE APPLICABLE). CONTRACTOR MUST IMMEDIATELY NOTIFY OWNER, ARCHITECT AND SITE ENGINEER, IN WRITING, OF ANY CONFLICTS, DISCREPANCIES OR

11. DEBRIS MUST NOT BE BURIED ON THE SUBJECT SITE AND ALL UNSUITABLE EXCAVATED MATERIAL AND DEBRIS (SOLID WASTE) MUST BE DISPOSED OF IN ACCORDANCE WITH THE REQUIREMENTS OF ANY AND ALL GOVERNMENTAL AUTHORITIES WHICH HAVE JURISDICTION OVER THIS PROJECT OR OVER CONTRACTOR. 12. THE CONTRACTOR IS RESPONSIBLE FOR IDENTIFYING WHEN SHORING IS REQUIRED AND FOR INSTALLING ALL SHORING REQUIRED DURING EXCAVATION (TO BE PERFORMED IN ACCORDANCE WITH CURRENT OSHA STANDARDS) AND ANY ADDITIONAL PRECAUTIONS TO BE TAKEN TO ASSURE THE STABILITY OF ADJACENT, NEARBY AND CONTIGUOUS STRUCTURES AND PROPERTIES.

13. THE CONTRACTOR IS TO EXERCISE EXTREME CARE WHEN PERFORMING ANY WORK ACTIVITIES ADJACENT TO PAVEMENT, STRUCTURES, ETC. WHICH ARE TO REMAIN EITHER FOR AN INITIAL PHASE OF THE PROJECT OR AS PART OF THE FINAL CONDITION. CONTRACTOR IS RESPONSIBLE FOR TAKING ALL APPROPRIATE MEASURES REQUIRED TO ENSURE THE STRUCTURAL STABILITY OF SIDEWALKS AND PAVEMENT, UTILITIES, BUILDINGS, AND INFRASTRUCTURE WHICH ARE TO REMAIN, AND TO PROVIDE A SAFE WORK AREA FOR THIRD PARTIES, PEDESTRIANS AND ANYONE INVOLVED WITH THE PROJECT

14 THE CONTRACTOR IS RESPONSIBLE FOR REPAIRING ANY DAMAGE DONE TO ANY NEW OR EXISTING CONSTRUCTION OR PROPERTY DURING THE COURSE OF CONSTRUCTION, INCLUDING BUT NOT LIMITED TO DRAINAGE, UTILITIES, PAVEMENT, STRIPING, CURB, ETC, AND SHALL BEAR ALL COSTS ASSOCIATED WITH SAME TO INCLUDE, BUT NOT BE LIMITED TO, REDESIGN, RE-SURVEY, RE-PERMITTING AND CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE FOR AND MUST REPLACE ALL SIGNAL INTERCONNECTION CABLE, WIRING CONDUITS, AND ANY UNDERGROUND ACCESSORY EQUIPMENT DAMAGED DURING CONSTRUCTION AND MUST BEAR ALL COSTS ASSOCIATED WITH SAME. THE REPAIR OF ANY SUCH NEW OR EXISTING CONSTRUCTION OR PROPERTY MUST RESTORE SUCH CONSTRUCTION OR PROPERTY TO A CONDITION EQUIVALENT TO OR BETTER THAN THE CONDITIONS PRIOR TO COMMENCEMENT OF THE CONSTRUCTION, AND IN CONFORMANCE WITH APPLICABLE CODES, LAWS RULES, REGULATIONS, STATUTORY REQUIREMENTS AND STATUTES, CONTRACTOR MUST BEAR ALL COSTS ASSOCIATED WITH SAME CONTRACTOR IS RESPONSIBLE TO DOCUMENT ALL EXISTING DAMAGE AND TO NOTIFY THE OWNER AND THE CONSTRUCTION MANAGER PRIOR TO THE START OF

15. ALL CONCRETE MUST BE AIR ENTRAINED AND HAVE THE MINIMUM COMPRESSIVE STRENGTH OF 4,000 PSI AT 28 DAYS UNLESS OTHERWISE NOTED ON THE PLANS, DETAILS AND/OR GEOTECHNICAL REPORT

16. THE ENGINEER IS NOT RESPONSIBLE FOR CONSTRUCTION METHODS, MEANS, TECHNIQUES OR PROCEDURES, GENERALLY OR FOR THE CONSTRUCTION MEANS. METHODS, TECHNIQUES OR PROCEDURES FOR COMPLETION OF THE WORK DEPICTED BOTH ON THESE PLANS, AND FOR ANY CONFLICTS/SCOPE REVISIONS WHICH RESULT FROM SAME. CONTRACTOR IS RESPONSIBLE FOR DETERMINING THE METHODS/MEANS FOR COMPLETION OF THE WORK PRIOR TO THE COMMENCEMENT

17. THE ENGINEER OF RECORD IS NOT RESPONSIBLE FOR JOB SITE SAFETY. THE ENGINEER OF RECORD HAS NOT BEEN RETAINED TO PERFORM OR BE RESPONSIBLE FOR JOB SITE SAFETY, SAME BEING WHOLLY OUTSIDE OF ENGINEER'S SERVICES AS RELATED TO THE PROJECT. THE ENGINEER OF RECORD IS NOT RESPONSIBLE TO IDENTIFY OR REPORT ANY JOB SITE SAFETY ISSUES, AT ANY TIME.

18 ALL CONTRACTORS MUST CARRY THE SPECIFIED STATUTORY WORKER'S COMPENSATION INSURANCE EMPLOYER'S LIABILITY INSURANCE AND LIMITS OF PAST, PRESENT AND FUTURE OWNERS. OFFICERS. DIRECTORS. PARTNERS. SHAREHOLDERS. MEMBERS. PRINCIPALS. COMMISSIONERS. AGENTS. SERVANTS EMPLOYEES, AFFILIATES, SUBSIDIARIES, AND RELATED ENTITIES, AND ITS SUBCONTRACTORS AND SUBCONSULTANTS AS ADDITIONAL NAMED INSURED AND TO ROVIDE CONTRACTUAL LIABILITY COVERAGE SUFFICIENT TO INSURE THIS HOLD HARMLESS AND INDEMNITY OBLIGATIONS ASSUMED BY THE CONTRACTORS. ALL CONTRACTORS MUST FURNISH BOHLER ENGINEERING WITH CERTIFICATIONS OF INSURANCE AS EVIDENCE OF THE REQUIRED INSURANCE PRIOR TO COMMENCING WORK AND UPON RENEWAL OF EACH POLICY DURING THE ENTIRE PERIOD OF CONSTRUCTION AND FOR ONE YEAR AFTER THE COMPLETION OF CONSTRUCTION. IN ADDITION, ALL CONTRACTORS WILL. TO THE FULLEST EXTENT PERMITTED UNDER THE LAW, INDEMNIFY, DEFEND AND HOLD HARMLESS BOHLER ENGINEERING AND ITS PAST, PRESENT AND FUTURE OWNERS, OFFICERS, DIRECTORS, PARTNERS, SHAREHOLDERS, MEMBERS, PRINCIPALS, COMMISSIONERS, AGENTS, SERVANTS, EMPLOYEES, AFFILIATES, SUBSIDIARIES, AND RELATED ENTITIES, AND ITS SUBCONTRACTORS AND SUBCONSULTANTS FROM AND AGAINST ANY DAMAGES, VIURIES, CLAIMS, ACTIONS, PENALTIES, EXPENSES, PUNITIVE DAMAGES, TORT DAMAGES, STATUTORY CLAIMS, STATUTORY CAUSES OF ACTION, LOSSES, CAUSES OF ACTION, LIABILITIES OR COSTS, INCLUDING, BUT NOT LIMITED TO, REASONABLE ATTORNEYS' FEES AND DEFENSE COSTS, ARISING OUT OF OR IN ANY WAY CONNECTED WITH OR TO THE PROJECT, INCLUDING ALL CLAIMS BY EMPLOYEES OF THE CONTRACTORS. ALL CLAIMS BY THIRD PARTIES AND ALL CLAIMS RELATED TO THE PROJECT. CONTRACTOR MUST NOTIFY ENGINEER, IN WRITING, AT LEAST THIRTY (30) DAYS PRIOR TO ANY TERMINATION, SUSPENSION OR CHANGE OF ITS

19. BOHLER ENGINEERING WILL REVIEW OR TAKE OTHER APPROPRIATE ACTION ON THE CONTRACTOR SUBMITTALS, SUCH AS SHOP DRAWINGS, PRODUCT DATA, SAMPLES, AND OTHER DATA, WHICH THE CONTRACTOR IS REQUIRED TO SUBMIT, BUT ONLY FOR THE LIMITED PURPOSE OF CHECKING FOR CONFORMANCE WITH THE DESIGN INTENT AND THE INFORMATION SHOWN IN THE CONSTRUCTION CONTRACT DOCUMENTS. CONSTRUCTION MEANS AND/OR METHODS AND/OR ECHNIQUES OR PROCEDURES. COORDINATION OF THE WORK WITH OTHER TRADES. AND CONSTRUCTION SAFETY PRECAUTIONS ARE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND BOHLER HAS NO RESPONSIBILITY OR LIABILITY FOR SAME HEREUNDER. BOHLER ENGINEERING'S SHOP DRAWING REVIEW WILL BE CONDUCTED WITH REASONABLE PROMPTNESS WHILE ALLOWING SUFFICIENT TIME TO PERMIT ADEQUATE REVIEW. REVIEW OF A SPECIFIC ITEM MUST NOT INDICATE THAT BOHLER ENGINEERING HAS REVIEWED THE ENTIRE ASSEMBLY OF WHICH THE ITEM IS A COMPONENT. BOHLER ENGINEERING WILL NOT BE RESPONSIBLE FOR ANY DEVIATIONS FROM THE CONSTRUCTION DOCUMENTS NOT PROMPTLY AND IMMEDIATELY BROUGHT TO ITS ATTENTION, IN WRITING, BY THE CONTRACTOR. BOHLER ENGINEERING WILL NOT BE REQUIRED TO REVIEW PARTIAL SUBMISSIONS OR THOSE FOR WHICH SUBMISSIONS OF CORRELATED ITEMS

20. NEITHER THE PROFESSIONAL ACTIVITIES OF BOHLER ENGINEERING, NOR THE PRESENCE OF BOHLER ENGINEERING AND/OR ITS PAST, PRESENT AND FUTURE OWNERS, OFFICERS, DIRECTORS, PARTNERS, SHAREHOLDERS, MEMBERS, PRINCIPALS, COMMISSIONERS, AGENTS, SERVANTS, EMPLOYEES, AFFILIATES SUBSIDIARIES, AND RELATED ENTITIES, AND ITS SUBCONTRACTORS AND SUBCONSULTANTS AT A CONSTRUCTION/PROJECT SITE, SHALL RELIEVE THE GENERAL CONTRACTOR OF ITS ORLIGATIONS DUTIES AND RESPONSIBILITIES INCLUDING BUT NOT LIMITED TO CONSTRUCTION MEANS METHODS SECUENCE TECHNIQUES OR PROCEDURES NECESSARY FOR PERFORMING. OVERSEEING. SUPERINTENDING AND COORDINATING THE WORK IN ACCORDANCE WITH THE CONTRACT DOCUMENTS AND COMPLIANCE WITH ANY HEALTH OR SAFETY PRECAUTIONS REQUIRED BY ANY REGULATORY AGENCIES WITH JURISDICTION OVER THE PROJECT IND/OR PROPERTY. BOHLER ENGINEERING AND ITS PERSONNEL HAVE NO AUTHORITY TO EXERCISE ANY CONTROL OVER ANY CONSTRUCTION CONTRACTOR OF ITS EMPLOYEES IN CONNECTION WITH THEIR WORK OR ANY HEALTH OR SAFETY PROGRAMS OR PROCEDURES. THE GENERAL CONTRACTOR IS SOLELY RESPONSIBLE FOR JOB SITE SAFETY. BOHLER ENGINEERING SHALL BE INDEMNIFIED BY THE GENERAL CONTRACTOR AND MUST BE NAMED AN ADDITIONAL

INSURED UNDER THE GENERAL CONTRACTOR'S POLICIES OF GENERAL LIABILITY INSURANCE AS DESCRIBED ABOVE IN NOTE 19 FOR JOB SITE SAFETY 21. IF THE CONTRACTOR DEVIATES FROM THE PLANS AND SPECIFICATIONS. INCLUDING THE NOTES CONTAINED HEREIN, WITHOUT FIRST OBTAINING THE PRIOR WRITTEN AUTHORIZATION OF THE ENGINEER FOR SUCH DEVIATIONS, THE CONTRACTOR IS SOLELY RESPONSIBLE FOR THE PAYMENT OF ALL COSTS INCURRED IN CORRECTING ANY WORK DONE WHICH DEVIATES FROM THE PLANS, ALL FINES AND/OR PENALTIES ASSESSED WITH RESPECT THERETO AND ALL COMPENSATORY OR PUNITIVE DAMAGES RESULTING THEREFROM AND. FURTHER, SHALL DEFEND, INDEMNIFY AND HOLD HARMLESS THE ENGINEER. TO THE FULLEST EXTENT PERMITTED UNDER THE LAW, IN ACCORDANCE WITH PARAGRAPH 19 HEREIN, FOR AND FROM ALL FEES, ATTORNEYS' FEES, DAMAGES, COSTS, JUDGMENTS, PENALTIES AND THE LIKE RELATED TO SAME.

22. CONTRACTOR IS RESPONSIBLE FOR MAINTENANCE AND PROTECTION OF TRAFFIC PLAN FOR ALL WORK THAT AFFECTS PUBLIC TRAVEL EITHER IN THE R.O.W. OR ON SITE. THE COST FOR THIS ITEM MUST BE INCLUDED IN THE CONTRACTOR'S PRICE.

23. ALL SIGNING AND PAVEMENT STRIPING MUST CONFORM TO MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES OR LOCALLY APPROVED SUPPLEMENT.

24. ENGINEER IS NOT RESPONSIBLE FOR ANY INJURY OR DAMAGES RESULTING FROM CONTRACTOR'S FAILURE TO BUILD OR CONSTRUCT IN STRICT ACCORDANCE WITH THE APPROVED PLANS. IF CONTRACTOR AND/OR OWNER FAIL TO BUILD OR CONSTRUCT IN STRICT ACCORDANCE WITH APPROVED PLANS, THEY AGREE TO JOINTLY AND SEVERALLY INDEMNIFY AND HOLD ENGINEER HARMLESS FOR ALL INJURIES AND DAMAGES THAT ENGINEER SUFFERS AND COSTS THAT ENGINEER

25. OWNER MUST MAINTAIN AND PRESERVE ALL PHYSICAL SITE FEATURES AND DESIGN FEATURES DEPICTED ON THE PLANS AND RELATED DOCUMENTS, IN STRICT ACCORDANCE WITH THE APPROVED PLAN(S) AND DESIGN AND, FURTHER ENGINEER IS NOT RESPONSIBLE FOR ANY FAILURE TO SO MAINTAIN OR PRESERVE SITE AND/OR DESIGN FEATURES. IF OWNER FAILS TO MAINTAIN AND/OR PRESERVE ALL PHYSICAL SITE FEATURES AND/OR DESIGN FEATURES DEPICTED ON THE PLANS AND RELATED DOCUMENTS, OWNER AGREES TO INDEMNIFY AND HOLD ENGINEER HARMLESS FOR ALL INJURIES AND DAMAGES THAT ENGINEER SUFFERS AND COSTS THAT ENGINEER INCURS AS A RESULT OF SAID FAILURE.

26. ALL DIMENSIONS MUST BE TO FACE OF CURB, EDGE OF PAVEMENT, OR EDGE OF BUILDING, UNLESS NOTED OTHERWISE.

27. ALL CONSTRUCTION AND MATERIALS MUST COMPLY WITH AND CONFORM TO APPLICABLE FEDERAL, STATE AND LOCAL REGULATIONS, LAWS, ORDINANCES, RULES AND CODES, AND ALL APPLICABLE OSHA REQUIREMENTS.

28. CONTRACTOR AND OWNER MUST INSTALL ALL ELEMENTS AND COMPONENTS IN STRICT COMPLIANCE WITH AND ACCORDANCE WITH MANUFACTURER'S STANDARDS AND RECOMMENDED INSTALLATION CRITERIA AND SPECIFICATIONS. IF CONTRACTOR AND/OR OWNER FAIL TO DO SO, THEY AGREE TO JOINTLY AND SEVERALLY INDEMNIFY AND HOLD ENGINEER HARMLESS FOR ALL INJURIES AND DAMAGES THAT ENGINEER SUFFERS AND COSTS THAT ENGINEER INCURS AS A

29. CONTRACTOR IS RESPONSIBLE TO MAINTAIN ON-SITE STORMWATER POLLUTION PREVENTION PLAN (SWPPP) IN COMPLIANCE WITH EPA REQUIREMENTS FOR SITES WHERE ONE (1) ACRE OR MORE (UNLESS THE LOCAL JURISDICTION REQUIRES FEWER) IS DISTURBED BY CONSTRUCTION ACTIVITIES. CONTRACTOR IS RESPONSIBLE TO ENSURE THAT ALL ACTIVITIES, INCLUDING THOSE OF SUBCONTRACTORS, ARE IN COMPLIANCE WITH THE SWPPP, INCLUDING BUT NOT LIMITED TO LOGGING ACTIVITIES (MINIMUM ONCE PER WEEK AND AFTER RAINFALL EVENTS) AND CORRECTIVE MEASURES, AS APPROPRIATE.

30. AS CONTAINED IN THESE DRAWINGS AND ASSOCIATED APPLICATION DOCUMENTS PREPARED BY THE SIGNATORY PROFESSIONAL ENGINEER, THE USE OF THE WORDS CERTIFY OR CERTIFICATION CONSTITUTES AN EXPRESSION OF "PROFESSIONAL OPINION" REGARDING THE INFORMATION WHICH IS THE SUBJECT OF THE UNDERSIGNED PROFESSIONAL'S KNOWLEDGE OR BELIEF AND IN ACCORDANCE WITH COMMON ACCEPTED PROCEDURE CONSISTENT WITH THE APPLICABLE TANDARDS OF PRACTICE, AND DOES NOT CONSTITUTE A WARRANTY OR GUARANTEE, EITHER EXPRESSED OR IMPLIED.

GENERAL SITE NOTES

1. THE GENERAL NOTES MUST BE INCLUDED AS PART OF THIS ENTIRE DOCUMENT PACKAGE AND ARE PART OF THE CONTRACT DOCUMENTS. THE GENERAL NOTES ARE REFERENCED HEREIN, AND THE CONTRACTOR MUST REFER TO THEM AND FULLY COMPLY WITH THESE NOTES, IN THEIR ENTIRETY. THE CONTRACTOR MUST BE FAMILIAR WITH AND ACKNOWLEDGE FAMILIARITY WITH ALL OF THE GENERAL NOTES AND ALL OF THE PLANS' SPECIFIC NOTES

2. PRIOR TO THE COMMENCEMENT OF GENERAL CONSTRUCTION, THE CONTRACTOR MUST INSTALL SOIL EROSION CONTROL AND ANY STORMWATER POLLUTION PREVENTION PLAN (SWPPP) MEASURES NECESSARY. AS INDICATED ON THE APPROVED SOIL EROSION AND SEDIMENT CONTROL PLAN AND IN ACCORDANCE WITH APPLICABLE AND/OR APPRÓPRIATE AGENCIES' GUIDÈLINES TO PREVENT SEDIMENT AND/OR LOOSE DEBRIS FROM WASHING ONTO ADJACENT PROPERTIES OR

3. ALL DIRECTIONAL/TRAFFIC SIGNING AND PAVEMENT STRIPING MUST CONFORM TO THE LATEST STANDARDS OF THE MANUAL ON UNIFORM TRAFFIC CONTROL

4. THE LOCATIONS OF PROPOSED UTILITY POLES AND TRAFFIC SIGNS SHOWN ON THE PLANS ARE SCHEMATIC AND PRELIMINARY. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR FIELD-VERIFYING THEIR LOCATION. THE CONTRACTOR MUST COORDINATE THE RELOCATION OF TRAFFIC SIGNS WITH THE ENTITY WITH

5. ALL DIMENSIONS SHOWN ARE TO BOTTOM FACE OF CURB, EDGE OF PAVEMENT, OR EDGE OF BUILDING, EXCEPT WHEN DIMENSION IS TO A PROPERTY LINE, STAKE OUT OF LOCATIONS OF INLETS, LIGHT POLES, ETC. MUST BE PERFORMED IN STRICT ACCORDANCE WITH THE DETAILS, UNLESS NOTED CLEARLY

6. WHEN APPLICABLE, OWNER/ OPERATOR MUST FILE THE NOI FOR NPDES PERMITS AT APPROPRIATE AND/OR REQUIRED TIMEFRAMES BASED UPON THE DESIRED START OF CONSTRUCTION, LAND DISTURBING ACTIVITIES MUST NOT COMMENCE UNTIL APPROVAL TO DO SO HAS BEEN RECEIVED FROM GOVERNIN AUTHORITIES (INCLUDING STORMWATER POLLUTION PREVENTION PLAN). THE CONTRACTOR MUST STRICTLY ADHERE TO THE APPROVED SWPPP PLAN DURING

7. ALL CONCRETE MUST BE AIR ENTRAINED AND INCLUDE THE MINIMUM COMPRESSIVE STRENGTH OF JURISDICTIONAL STANDARD PSI AT 28 DAYS (OR 4,000 PSI)

UNLESS OTHERWISE NOTED ON THE PLANS, DETAILS AND/OR GEOTECHNICAL REPORT. 8. THE CONTRACTOR MUST FILE SITE SIGNAGE APPLICATION OR PERMIT UNDER SEPARATE APPLICATION UNLESS DONE SO AS PART OF JURISDICTIONAL

). THE CONTRACTOR MUST REPAIR OR REPLACE, AT THE CONTRACTOR'S SOLE COST AND EXPENSE, ALL SIDEWALKS, CURBS, PAVEMENT MARKINGS, AND PAVEMENT DAMAGED BY CONSTRUCTION ACTIVITIES WHETHER SPECIFIED ON THIS PLAN OR NOT

10. WORK WITHIN THE RIGHT-OF-WAY MUST BE PERFORMED IN ACCORDANCE WITH ALL APPLICABLE REQUIREMENTS AND STANDARDS OF THE DEPARTMENT OF

WHERE RETAINING WALLS ARE IDENTIFIED ON THE PLANS, TOP AND BOTTOM OF WALL WIDTHS DO NOT REPRESENT THE ACTUAL WIDTH OF THE PROPOSE WALL, RATHER THEY ARE AN ASSUMPTION BASED ON WALL TYPE AND WALL HEIGHT, WALL FOOTINGS AND /OR FOUNDATIONS ARE NOT IDENTIFIED HEREIN AND PREPARED BY THE APPROPRIATE PROFESSIONAL LICENSED IN THE STATE WHERE THE CONSTRUCTION OCCURS. THE CONTRACTOR MUST ENSURE THAT AN PPROPRIATELY LICENSED PROFESSIONAL DESIGNS ALL WALLS SHOWN HEREON AND PRIOR TO CONSTRUCTION. REFER TO GRADING NOTES REGARDING.

12. CONTRACTOR IS CAUTIONED OF EXISTING UTILITY SERVICES TO REMAIN IN PROXIMITY TO PROPOSED BOLLARDS AND SIGNS. CONTRACTOR SHALL PROVIDE FIELD MODIFICATION LOCATIONS OF BOLLARDS AND BOLLARDS WITH SIGNAGE AS NEEDED TO AVOID CONFLICTS WITH EXISTING UTILITY SERVICES TO REMAIN

GENERAL GRADING & UTILITY PLAN NOTES

1 LOCATIONS OF ALL EXISTING AND PROPOSED SERVICES ARE APPROXIMATE AND MUST BE INDEPENDENTLY CONFIRMED WITH LOCAL UTILITY COMPANIES PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION OR EXCAVATION. SANITARY SEWER AND ALL OTHER UTILITY SERVICE CONNECTION POINTS MUST BE INDEPENDENTLY CONFIRMED BY THE CONTRACTOR IN THE FIELD PRIOR TO THE COMMENCEMENT OF CONSTRUCTION. ALL DISCREPANCIES MUST IMMEDIATELY BE REPORTED, IN WRITING, TO THE ENGINEER. CONSTRUCTION MUST COMMENCE BEGINNING AT THE LOWEST INVERT (POINT OF CONNECTION) AND PROGRESS UP GRADIENT. PROPOSED INTERFACE POINTS (CROSSINGS) WITH EXISTING UNDERGROUND UTILITIES SHALL BE FIELD VERIFIED BY TEST PIT PRIOR TO COMMENCEMENT OF CONSTRUCTION.

2 CONTRACTOR MUST VERTICALLY AND HORIZONTALLY LOCATE ALL LITILITIES AND SERVICES INCLUDING BUT NOT LIMITED TO GAS WATER ELECTRIC SANITARY AND STORM SEWER ELEPHONE. CABLE. FIBER OPTIC CABLE. ETC. WITHIN THE LIMITS OF DISTURBANCE OR WORK SPACE. WHICHEVER IS GREATER. THE CONTRACTOR MUST USE. REFER TO. AND COMPLY WITH THE REQUIREMENTS OF THE APPLICABLE UTILITY NOTIFICATION SYSTEM TO LOCATE ALL THE UNDERGROUND UTILITIES. THE CONTRACTOR IS RESPONSIBLE FOR REPAIRING ALL DAMAGE TO ANY EXISTING UTILITIES DURING CONSTRUCTION, AT NO COST TO THE OWNER. CONTRACTOR SHALL BEAR ALL COSTS ASSOCIATED WITH DAMAGE TO ANY EXISTING

3. IT IS THE CONTRACTOR'S RESPONSIBILITY TO REVIEW ALL CONSTRUCTION CONTRACT DOCUMENTS INCLUDING. BUT NOT LIMITED TO, ALL OF THE DRAWINGS AND SPECIFICATIONS ASSOCIATED WITH THE PROJECT WORK SCOPE PRIOR TO THE INITIATION AND COMMENCEMENT OF CONSTRUCTION. SHOULD THE CONTRACTOR FIND A CONFLICT AND/OR DISCREPANCY BETWEEN THE DOCUMENTS RELATIVE TO THE SPECIFICATIONS OR THE RELATIVE OR APPLICABLE CODES, REGULATIONS, LAWS, RULES, STATUTES AND/OR ORDINANCES, IT IS THE ONTRACTOR'S SOLE RESPONSIBILITY TO NOTIFY THE PROJECT ENGINEER OF RECORD, IN WRITING, OF SAID CONFLICT AND/OR DISCREPANCY PRIOR TO THE START OF CONSTRUCTION. CONTRACTOR'S FAILURE TO NOTIFY THE PROJECT ENGINEER SHALL CONSTITUTE CONTRACTOR'S FULL AND COMPLETE ACCEPTANCE OF ALL RESPONSIBILITY TO COMPLETE THE SCOPE OF WORK AS DEFINED BY THE DRAWINGS AND IN FULL COMPLIANCE WITH ALL FEDERAL, STATE AND LOCAL REGULATIONS, LAWS, STATUTES, ORDINANCES AND CODES AND, FURTHER, CONTRACTOR SHALL BE RESPONSIBLE FOR ALL COSTS ASSOCIATED WITH SAME.

4. THE CONTRACTOR MUST LOCATE AND CLEARLY AND UNAMBIGUOUSLY DEFINE VERTICALLY AND HORIZONTALLY ALL ACTIVE AND INACTIVE UTILITY AND/OR SERVICE SYSTEMS THAT ARE TO BE REMOVED. THE CONTRACTOR IS RESPONSIBLE TO PROTECT AND MAINTAIN ALL ACTIVE AND INACTIVE SYSTEMS THAT ARE NOT BEING REMOVED/RELOCATED DURING SITE

5. THE CONTRACTOR MUST FAMILIARIZE ITSELF WITH THE APPLICABLE UTILITY SERVICE PROVIDER REQUIREMENTS AND IS RESPONSIBLE FOR ALL COORDINATION REGARDING UTILITY DEMOLITION AS IDENTIFIED OR REQUIRED FOR THE PROJECT. THE CONTRACTOR MUST PROVIDE THE OWNER WITH WRITTEN NOTIFICATION THAT THE EXISTING UTILITIES AND SERVICES HAVE BEEN TERMINATED AND ABANDONED IN ACCORDANCE WITH THE JURISDICTION AND UTILITY COMPANY REQUIREMENTS AND ALL OTHER APPLICABLE REQUIREMENTS, RULES,

6. THE CONTRACTOR MUST INSTALL ALL STORM SEWER AND SANITARY SEWER COMPONENTS WHICH FUNCTION BY GRAVITY PRIOR TO THE INSTALLATION OF ALL OTHER UTILITIES.

7. CONTRACTOR IS RESPONSIBLE FOR COORDINATION OF SITE PLAN DOCUMENTS AND ARCHITECTURAL DESIGN FOR EXACT BUILDING UTILITY CONNECTION LOCATIONS, GREASE TRAP EQUIREMENTS/DETAILS, DOOR ACCESS, AND EXTERIOR GRADING. THE ARCHITECT WILL DETERMINE THE UTILITY SERVICE SIZES. THE CONTRACTOR MUST COORDINATE INSTALLATION OF UTILITIES/SERVICES WITH THE INDIVIDUAL COMPANIES, TO AVOID CONFLICTS AND TO ENSURE THAT PROPER DEPTHS ARE ACHIEVED. THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT INSTALLATION OF ALL IMPROVEMENTS COMPLIES WITH ALL LITHLITY REQUIREMENTS WITH JURISDICTION AND/OR CONTROL OF THE SITE AND ALL OTHER APPLICABLE REQUIREMENTS, RULES, STATUTES, LAWS, ORDINANCES AND CODES AND FURTHER IS RESPONSIBLE FOR COORDINATING THE LITH ITY TIE-INS/CONNECTIONS PRIOR TO CONNECTING TO THE EXISTING UTILITY/SERVICE. WHERE A CONFLICT(S) EXISTS BETWEEN THESE SITE PLANS AND THE ARCHITECTURAL PLANS. OR WHERE ARCHITECTURAL PLAN UTILITY CONNECTION POINTS DIFFER, THE CONTRACTOR MUST IMMEDIATELY NOTIFY THE ENGINEER, IN WRITING, AND PRIOR TO CONSTRUCTION, RESOLVE SAME.

8. ALL NEW UTILITIES/SERVICES, INCLUDING ELECTRIC, TELEPHONE, CABLE TV, ETC. ARE TO BE INSTALLED UNDERGROUND. ALL NEW UTILITIES/SERVICES MUST BE INSTALLED IN ACCORDANCE WITH THE UTILITY/SERVICE PROVIDER INSTALLATION SPECIFICATIONS AND STANDARDS.

9. SITE GRADING MUST BE PERFORMED IN ACCORDANCE WITH THESE PLANS AND SPECIFICATIONS AND THE RECOMMENDATIONS SET FORTH IN THE GEOTECHNICAL REPORT REFERENCED IN THIS PLAN SET. THE CONTRACTOR IS RESPONSIBLE FOR REMOVING AND REPLACING UNSUITABLE MATERIALS WITH SUITABLE MATERIALS AS SPECIFIED IN THE GEOTECHNICAL REPORT. ALL EXCAVATED OR FILLED AREAS MUST BE COMPACTED AS OUTLINED IN THE GEOTECHNICAL REPORT. MOISTURE CONTENT AT TIME OF PLACEMENT MUST BE SUBMITTED IN A COMPACTION REPORT PREPARED BY A QUALIFIED GEOTECHNICAL ENGINEER, REGISTERED WITH THE STATE WHERE THE WORK IS PERFORMED, VERIFYING THAT ALL FILLED AREAS AND SUBGRADE AREAS WITHIN THE BUILDING PAD AREA AND AREAS TO BE PAVED HAVE BEEN COMPACTED IN ACCORDANCE WITH THESE PLANS. SPECIFICATIONS AND THE RECOMMENDATIONS SET FORTH IN THE GEOTECHNICAL REPORT AND ALL APPLICABLE REQUIREMENTS, RULES, STATUTES, LAWS, ORDINANCES AND CODES, SUBBASE MATERIAL FOR SIDEWALKS, CURB, OR ASPHALT MUST BE FREE OF ORGANICS AND OTHER UNSUITABLE MATERIALS. SHOULD SUBBASE BE DEEMED UNSUITABLE BY OWNER/DEVELOPER, OR /NER/DEVELOPER'S REPRESENTATIVE, SUBBASE IS TO BE REMOVED AND FILLED WITH APPROVED FILL MATERIAL COMPACTED AS DIRECTED BY THE GEOTECHNICAL REPORT EARTHWORK ACTIVITIES INCLUDING, BUT NOT LIMITED TO, EXCAVATION, BACKFILL, AND COMPACTING MUST COMPLY WITH THE RECOMMENDATIONS IN THE GEOTECHNICAL REPORT AND ALL APPLICABLE REQUIREMENTS, RULES, STATUTES, LAWS, ORDINANCES AND CODES. EARTHWORK ACTIVITIES MUST COMPLY WITH THE STANDARD STATE DOT SPECIFICATIONS FOR ROADWAY CONSTRUCTION (LATEST EDITION) AND ANY AMENDMENTS OR REVISIONS THERETO.

10. ALL FILL, COMPACTION, AND BACKFILL MATERIALS REQUIRED FOR UTILITY INSTALLATION MUST BE AS PER THE RECOMMENDATIONS PROVIDED IN THE GEOTECHNICAL REPORT AND MUST BE COORDINATED WITH THE APPLICABLE UTILITY COMPANY SPECIFICATIONS. WHEN THE PROJECT DOES NOT HAVE GEOTECHNICAL RECOMMENDATIONS, FILL AND COMPACTION MUST, AT A MINIMUM, COMPLY WITH THE STATE DOT REQUIREMENTS AND SPECIFICATIONS AND CONSULTANT SHALL HAVE NO LIABILITY OR RESPONSIBILITY FOR OR AS RELATED TO FILL, COMPACTION AND BACKFILL. FURTHER, CONTRACTOR IS FULLY RESPONSIBLE FOR EARTHWORK BALANCE.

11. THE CONTRACTOR MUST COMPLY, TO THE FULLEST EXTENT, WITH THE LATEST OSHA STANDARDS AND REGULATIONS, AND/OR ANY OTHER AGENCY WITH JURISDICTION FOR EXCAVATION AND TRENCHING PROCEDURES. THE CONTRACTOR IS RESPONSIBLE FOR DETERMINING THE "MEANS AND METHODS" REQUIRED TO MEET THE INTENT AND PERFORMANCE CRITERIA OF SHA, AS WELL AS ANY OTHER ENTITY THAT HAS JURISDICTION FOR EXCAVATION AND/OR TRENCHING PROCEDURES AND CONSULTANT SHALL HAVE NO RESPONSIBILITY FOR OR AS RELATED FOR OR AS RELATED TO EXCAVATION AND TRENCHING PROCEDURES

12. PAVEMENT MUST BE SAW CUT IN STRAIGHT LINES, AND EXCEPT FOR EDGE OF BUTT JOINTS, MUST EXTEND TO THE FULL DEPTH OF THE EXISTING PAVEMENT. ALL DEBRIS FROM REMOVAL OPERATIONS MUST BE REMOVED FROM THE SITE AT THE TIME OF EXCAVATION. STOCKPILING OF DEBRIS WILL NOT BE PERMITTED.

APPLICABLE STANDARDS, REQUIREMENTS, RULES, STATUTES, LAWS, ORDINANCES AND CODES. 14. DURING THE INSTALLATION OF SANITARY SEWER, STORM SEWER, AND ALL UTILITIES, THE CONTRACTOR MUST MAINTAIN A CONTEMPORANEOUS AND THOROUGH RECORD OF ONSTRUCTION TO IDENTIFY THE AS-INSTALLED LOCATIONS OF ALL UNDERGROUND INFRASTRUCTURE. THE CONTRACTOR MUST CAREFULLY NOTE ANY INSTALLATIONS THAT DEVIATE FROM THE INFORMATION CONTAINED IN THE UTILITY PLAN. THIS RECORD MUST BE KEPT ON A CLEAN COPY OF THE DRAINAGE OR UTILITY PLAN, WHICH CONTRACTOR MUST PROMPTLY

13. THE TOPS OF EXISTING MANHOLES, INLET STRUCTURES, AND SANITARY CLEANOUT TOPS MUST BE ADJUSTED, AS NECESSARY, TO MATCH PROPOSED GRADES IN ACCORDANCE WITH ALL

PROVIDE TO THE OWNER AT THE COMPLETION OF WORK. 15. THE CONTRACTOR IS FULLY RESPONSIBLE FOR VERIFICATION OF EXISTING TOPOGRAPHIC INFORMATION AND UTILITY INVERT ELEVATIONS PRIOR TO COMMENCING ANY CONSTRUCTION CONTRACTOR MUST CONFIRM AND ENSURE 0.75% MINIMUM SLOPE AGAINST ALL ISLANDS, GUTTERS, AND CURBS; 1.0% ON ALL CONCRETE SURFACES; AND 1.5% MINIMUM ON ASPHALT (EXCEPT WHERE ADA REQUIREMENTS OR EXISTING TOPOGRAPHY LIMIT GRADES), TO PREVENT PONDING. CONTRACTOR MUST IMMEDIATELY IDENTIFY, IN WRITING TO THE ENGINEER, ANY DISCREPANCIES THAT MAY OR COULD AFFECT THE PUBLIC SAFETY, HEALTH OR GENERAL WELFARE, OR PROJECT COST. IF CONTRACTOR PROCEEDS WITH CONSTRUCTION WITHOUT PROVIDING PROPER NOTIFICATION, MUST BE AT THE CONTRACTOR'S OWN RISK AND, FURTHER, CONTRACTOR SHALL INDEMNIFY, DEFEND AND HOLD HARMLESS THE DESIGN ENGINEER FOR ANY DAMAGES, COSTS, INJURIES, ATTORNEY'S FEES AND THE LIKE WHICH RESULT FROM SAME.

16. PROPOSED TOP OF CURB ELEVATIONS ARE GENERALLY 6" ABOVE EXISTING LOCAL ASPHALT GRADE UNLESS OTHERWISE NOTED. FIELD ADJUST TO CREATE A MINIMUM OF 0.75% GUTTER GRADE ALONG CURB FACE. IT IS CONTRACTOR'S OBLIGATION TO ENSURE THAT DESIGN ENGINEER APPROVES FINAL CURBING CUT SHEETS PRIOR TO INSTALLATION OF SAME.

IMMEDIATELY NOTIFY THE DESIGN ENGINEER. IN WRITING, OF ANY DISCREPANCIES AND/OR CONFLICTS. 18. CONTRACTOR IS REQUIRED TO SECURE ALL NECESSARY AND/OR REQUIRED PERMITS AND APPROVALS FOR ALL OFF SITE MATERIAL SOURCES AND DISPOSAL FACILITIES. CONTRACTOR

19 STORM DRAINAGE PIPE UNI ESS INDICATED OTHERWISE ALL STORM SEWER PIPE MUST BE REINFORCED CONCRETE PIPE (RCP) CLASS III WITH SILT TIGHT JOINTS. WHEN HIGH-DENSITY POLYETHYLENE PIPE (HDPE) IS CALLED FOR ON THE PLANS. IT MUST CONFORM TO AASHTO M294 AND TYPE S (SMOOTH INTERIOR WITH ANGULAR CORRUGATIONS) WITH GASKET FOR SILT TIGHT JOINT. PVC PIPE FOR ROOF DRAIN CONNECTION MUST BE SDR 26 OR SCHEDULE 40 UNLESS INDICATED OTHERWISE.

20. STORM AND SANITARY SEWER PIPE LENGTHS INDICATED ARE NOMINAL AND MEASURED CENTER OF INLET AND/OR MANHOLES STRUCTURE TO CENTER OF STRUCTURE. 21. STORMWATER ROOF DRAIN LOCATIONS ARE BASED ON PRELIMINARY ARCHITECTURAL PLANS. CONTRACTOR IS RESPONSIBLE TO AND FOR VERIFYING LOCATIONS OF SAME BASED ON

22. SEWERS CONVEYING SANITARY FLOW COMBINED SANITARY AND STORMWATER FLOW OR INDUSTRIAL FLOW MUST BE SEPARATED FROM WATER MAINS BY A DISTANCE OF AT LEAST 10 FEET HORIZONTALLY. IF SUCH LATERAL SEPARATION IS NOT POSSIBLE, THE PIPES MUST BE IN SEPARATE TRENCHES WITH THE SEWER AT LEAST 18 INCHES BELOW THE BOTTOM OF THE WATER MAIN, OR SUCH OTHER SEPARATION AS APPROVED BY THE GOVERNMENT AGENCY WITH JURISDICTION OVER SAME.

 WHERE APPROPRIATE SEPARATION FROM A WATER MAIN IS NOT POSSIBLE, THE SEWER MUST BE ENCASED IN CONCRETE, OR CONSTRUCTED OF DUCTILE IRON PIPE USING MECHANICAL OR SLIP-ON JOINTS FOR A DISTANCE OF AT LEAST 10 FEET ON EITHER SIDE OF THE CROSSING. IN ADDITION, ONE FULL LENGTH OF SEWER PIPE SHOULD BE LOCATED SO BOTH JOINTS WILL BE AS FAR FROM THE WATER LINE AS POSSIBLE. WHERE A WATER MAIN CROSSES UNDER A SEWER, ADEQUATE STRUCTURAL SUPPORT FOR THE SEWER

23. WATER MAIN PIPING MUST BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS AND SPECIFICATIONS OF THE LOCAL WATER PURVEYOR. IN THE ABSENCE OF SUCH REQUIREMENTS, WATER MAIN PIPING MUST BE CEMENT-LINED DUCTILE IRON (DIP) MINIMUM CLASS 52 THICKNESS. ALL PIPE AND APPURTENANCES MUST COMPLY WITH THE APPLICABLE

24. CONSULTANT IS NEITHER LIABLE NOR RESPONSIBLE FOR ANY SUBSURFACE CONDITIONS AND FURTHER, SHALL HAVE NO LIABILITY FOR ANY HAZARDOUS MATERIALS, HAZARDOUS SUBSTANCES OR POLITITANTS ON ABOUT OR LINDER THE PROPERTY

GENERAL DEMOLITION NOTES

- THIS PLAN REFERENCES DOCUMENTS AND INFORMATION BY:
- "ALTA/NSPS LAND TITLE SURVEY", PREPARED BY CONTROL POINT ASSOCIATES, DATED: 05/30/2023 • "INITIAL REPORT OF GEOTECHNICAL INVESTIGATION", PREPARED BY WHITESTONE ASSOCIATES, INC., DATED: 05/31/2023
- 2. CONTRACTOR SHALL PERFORM ALL WORK IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL SAFETY AND HEALTH ACT OF 1970, (29 U.S.C. 651 et seq.), AS AMENDED AND ANY MODIFICATIONS, AMENDMENTS OR REVISIONS TO SAME.
- 3. BOHLER ENGINEERING HAS NO CONTRACTUAL, LEGAL, OR OTHER RESPONSIBILITY FOR JOB SITE SAFETY OR JOB SITE SUPERVISION, OR ANYTHING RELATED TO SAME. 4. THE DEMOLITION PLAN IS INTENDED TO PROVIDE GENERAL INFORMATION, ONLY, REGARDING ITEMS TO BE DEMOLISHED AND/OR REMOVED. THE CONTRACTOR MUST ALSO REVIEW THE OTHER SITE PLAN DRAWINGS AND INCLUDE IN DEMOLITION ACTIVITIES ALL INCIDENTAL WORK NECESSARY FOR THE CONSTRUCTION OF THE NEW SITE
- 5. CONTRACTOR MUST RAISE ANY QUESTIONS CONCERNING THE ACCURACY OR INTENT OF THESE PLANS OR SPECIFICATIONS, CONCERNS REGARDING THE APPLICABLE SAFETY STANDARDS, OR THE SAFETY OF THE CONTRACTOR OR THIRD PARTIES IN PERFORMING THE WORK ON THIS PROJECT, WITH BOHLER ENGINEERING, IN WRITING, AND RESPONDED TO BY BOHLER, IN WRITING, PRIOR TO THE INITIATION OF ANY SITE ACTIVITY AND ANY DEMOLITION ACTIVITY. ALL DEMOLITION ACTIVITIES MUST BE PERFORMED IN ACCORDANCE WITH THE REQUIREMENTS OF THESE PLANS AND SPECIFICATIONS AND ALL APPLICABLE FEDERAL, STATE AND LOCAL REGULATIONS, RULES, REQUIREMENTS, STATUTES, ORDINANCES AND CODES.
- 6. PRIOR TO STARTING ANY DEMOLITION, CONTRACTOR IS RESPONSIBLE FOR/TO:
- A.OBTAINING ALL REQUIRED PERMITS AND MAINTAINING THE SAME ON SITE FOR REVIEW BY THE ENGINEER AND OTHER PUBLIC AGENCIES WITH JURISDICTION THROUGHOUT THE DURATION OF THE PROJECT, SITE WORK, AND DEMOLITION WORK. B. NOTIFYING, AT A MINIMUM, THE MUNICIPAL ENGINEER, DESIGN ENGINEER, AND LOCAL SOIL CONSERVATION DISTRICT, 72 HOURS PRIOR TO THE START OF WORK.

C.INSTALLING THE REQUIRED SOIL EROSION AND SEDIMENT CONTROL MEASURES PRIOR TO SITE DISTURBANCE.

AND SAFE MANNER, FOLLOWING ALL THE OSHA REQUIREMENTS, TO ENSURE PUBLIC AND CONTRACTOR SAFETY.

ENTERING THE EXCAVATION. FINISHED SURFACES MUST BE GRADED TO PROMOTE POSITIVE DRAINAGE

DIRECTION OF THE OWNER'S STRUCTURAL OR GEOTECHNICAL ENGINEER.

D.IN ACCORDANCE WITH STATE LAW, THE CONTRACTOR MUST CALL THE STATE ONE-CALL DAMAGE PROTECTION SYSTEM FOR UTILITY MARKOUT, IN ADVANCE OF ANY EXCAVATION. E.LOCATING AND PROTECTING ALL UTILITIES AND SERVICES, INCLUDING BUT NOT LIMITED TO GAS, WATER, ELECTRIC, SANITARY AND STORM SEWER, TELEPHONE, CABLE

FIBER OPTIC CABLE, ETC. WITHIN AND ADJACENT TO THE LIMITS OF PROJECT ACTIVITIES. THE CONTRACTOR MUST USE AND COMPLY WITH THE REQUIREMENTS OF THE APPLICABLE UTILITY NOTIFICATION SYSTEM TO LOCATE ALL THE UNDERGROUND UTILITIES.

G ARRANGING FOR AND COORDINATING WITH THE APPLICABLE LITILITY SERVICE PROVIDER(S) FOR THE TEMPORARY OR PERMANENT TERMINATION OF SERVICE REQUIRED BY THE PROJECT PLANS AND SPECIFICATIONS. THE CONTRACTOR MUST PROVIDE THE UTILITY ENGINEER AND OWNER WRITTEN NOTIFICATION THAT THE EXISTING UTILITIES AND SERVICES HAVE BEEN TERMINATED AND ABANDONED IN ACCORDANCE WITH JURISDICTIONAL AND UTILITY COMPANY REQUIREMENTS.

F. PROTECTING AND MAINTAINING IN OPERATION, ALL ACTIVE UTILITIES AND SYSTEMS THAT ARE NOT BEING REMOVED DURING ALL DEMOLITION ACTIVITIES.

H. COORDINATION WITH UTILITY COMPANIES REGARDING WORKING "OFF-PEAK" HOURS OR ON WEEKENDS AS MAY BE REQUIRED TO MINIMIZE THE IMPACT ON THE AFFECTED PARTIES. WORK REQUIRED TO BE DONE "OFF-PEAK" IS TO BE DONE AT NO ADDITIONAL COST TO THE OWNER I. IN THE EVENT THE CONTRACTOR DISCOVERS ANY HAZARDOUS MATERIAL, THE REMOVAL OF WHICH IS NOT ADDRESSED IN THE PROJECT PLANS AND SPECIFICATIONS, THE

CONTRACTOR MUST IMMEDIATELY CEASE ALL WORK AND IMMEDIATELY NOTIFY THE OWNER AND ENGINEER OF THE DISCOVERY OF SUCH MATERIALS. 7. THE FIRM OR ENGINEER OF RECORD IS NOT RESPONSIBLE FOR JOB SITE SAFETY OR SUPERVISION. CONTRACTOR MUST PROCEED WITH THE DEMOLITION IN A SYSTEMATIC

8. THE CONTRACTOR MUST PROVIDE ALL "MEANS AND METHODS" NECESSARY TO PREVENT MOVEMENT, SETTLEMENT, OR COLLAPSE OF EXISTING STRUCTURES, AND ANY OTHER IMPROVEMENTS THAT ARE REMAINING ON OR OFF SITE. THE CONTRACTOR IS RESPONSIBLE FOR ALL REPAIRS OF DAMAGE TO ALL ITEMS THAT ARE TO REMAIN CONTRACTOR MUST USE NEW MATERIAL FOR ALL REPAIRS. CONTRACTOR'S REPAIR MUST INCLUDE THE RESTORATION OF ANY ITEMS REPAIRED TO THE PRE-DEMOLITION CONDITION, OR BETTER, CONTRACTOR SHALL PERFORM ALL REPAIRS AT THE CONTRACTOR'S SOLE EXPENSE.

9. THE CONTRACTOR MUST NOT PERFORM ANY EARTH MOVEMENT ACTIVITIES, DEMOLITION OR REMOVAL OF FOUNDATION WALLS, FOOTINGS, OR OTHER MATERIALS WITHIN THE LIMITS OF DISTURBANCE UNLESS SAME IS IN STRICT ACCORDANCE AND CONFORMANCE WITH THE PROJECT PLANS AND SPECIFICATIONS, AND/OR UNDER THE WRITTEN

10. CONTRACTOR MUST BACKFILL ALL EXCAVATION RESULTING FROM, OR INCIDENTAL TO, DEMOLITION ACTIVITIES. BACKFILL MUST BE ACCOMPLISHED WITH APPROVED BACKFILL MATERIALS. AND MUST BE SUFFICIENTLY COMPACTED TO SUPPORT NEW IMPROVEMENTS AND PERFORMED IN COMPLIANCE WITH THE RECOMMENDATIONS AND GUIDANCE IN THE GEOTECHNICAL REPORT. BACKFILLING MUST OCCUR IMMEDIATELY AFTER DEMOLITION ACTIVITIES, AND MUST BE DONE SO AS TO PREVENT WATER

11. EXPLOSIVES MUST NOT BE USED WITHOUT PRIOR WRITTEN CONSENT OF BOTH THE OWNER AND ALL APPLICABLE GOVERNMENTAL AUTHORITIES. ALL THE REQUIRED PERMITS AND EXPLOSIVE CONTROL MEASURES THAT ARE REQUIRED BY THE FEDERAL, STATE, AND LOCAL GOVERNMENTS MUST BE IN PLACE PRIOR TO CONTRACTOR STARTING AN EXPLOSIVE PROGRAM AND/OR ANY DEMOLITION. THE CONTRACTOR IS ALSO RESPONSIBLE FOR ALL INSPECTION AND SEISMIC VIBRATION TESTING THAT IS

REQUIRED TO MONITOR THE EFFECTS ON ALL LOCAL STRUCTURES. 12. CONTRACTOR MUST CONDUCT DEMOLITION ACTIVITIES IN SUCH A MANNER TO ENSURE MINIMUM INTERFERENCE WITH ROADS, STREETS, SIDEWALKS, WALKWAYS, AND OTHER ADJACENT FACILITIES. STREET CLOSURE PERMITS MUST BE RECEIVED FROM THE APPROPRIATE GOVERNMENTAL AUTHORITY PRIOR TO THE COMMENCEMENT OF

ANY ROAD OPENING OR DEMOLITION ACTIVITIES IN OR ADJACENT TO THE RIGHT-OF-WAY. 13. DEMOLITION ACTIVITIES AND EQUIPMENT MUST NOT USE AREAS OUTSIDE THE DEFINED PROJECT LIMIT LINE, WITHOUT WRITTEN PERMISSION OF THE OWNER AND ALL

GOVERNMENTAL AGENCIES WITH JURISDICTION. 14. THE CONTRACTOR MUST USE DUST CONTROL MEASURES TO LIMIT AIRBORNE DUST AND DIRT RISING AND SCATTERING IN THE AIR IN ACCORDANCE WITH FEDERAL, STATE, AND/OR LOCAL STANDARDS. AFTER THE DEMOLITION IS COMPLETE, CONTRACTOR MUST CLEAN ALL ADJACENT STRUCTURES AND IMPROVEMENTS TO REMOVE ALL DUST

AND DEBRIS CAUSED BY THE DEMOLITION OPERATIONS. THE CONTRACTOR IS RESPONSIBLE FOR RETURNING ALL ADJACENT AREAS TO THEIR "PRE-DEMOLITION"

15. CONTRACTOR IS RESPONSIBLE TO SAFEGUARD THE SITE AS NECESSARY TO PERFORM THE DEMOLITION IN SUCH A MANNER AS TO PREVENT THE ENTRY OF UNAUTHORIZED 16. CONTRACTOR IS RESPONSIBLE FOR SITE JOB SAFETY, WHICH MUST INCLUDE, BUT NOT BE LIMITED TO, THE INSTALLATION AND MAINTENANCE OF BARRIERS, FENCING AND

OTHER APPROPRIATE SAFETY ITEMS NECESSARY TO PROTECT THE PUBLIC FROM AREAS OF CONSTRUCTION AND CONSTRUCTION ACTIVITY. 17. THIS DEMOLITION PLAN IS INTENDED TO IDENTIFY THOSE EXISTING ITEMS/CONDITIONS WHICH ARE TO BE REMOVED. IT IS NOT INTENDED TO PROVIDE DIRECTION AS TO THE

MEANS, METHODS, SEQUENCING, TECHNIQUES AND PROCEDURES TO BE USED TO ACCOMPLISH THAT WORK. ALL MEANS, METHODS, SEQUENCING, TECHNIQUES AND PROCEDURES TO BE USED MUST BE IN STRICT ACCORDANCE WITH ALL STATE, FEDERAL, LOCAL, AND JURISDICTIONAL REQUIREMENTS. THE CONTRACTOR MUST COMPLY WITH ALL OSHA AND OTHER SAFETY PRECAUTIONS NECESSARY TO PROVIDE A SAFE WORK SITE.

18. DEBRIS MUST NOT BE BURIED ON THE SUBJECT SITE. ALL DEMOLITION WASTES AND DEBRIS (SOLID WASTE) MUST BE DISPOSED OF IN ACCORDANCE WITH ALL MUNICIPAL,

COUNTY, STATE, AND FEDERAL LAWS AND APPLICABLE CODES. THE CONTRACTOR MUST MAINTAIN RECORDS TO DEMONSTRATE PROPER DISPOSAL ACTIVITIES, TO BE PROMPTLY PROVIDED TO THE OWNER UPON REQUEST. 19. CONTRACTOR MUST MAINTAIN A RECORD SET OF PLANS UPON WHICH IS INDICATED THE LOCATION OF EXISTING UTILITIES THAT ARE CAPPED, ABANDONED IN PLACE, OR

RELOCATED DUE TO DEMOLITION ACTIVITIES. THIS RECORD DOCUMENT MUST BE PREPARED IN A NEAT AND WORKMAN-LIKE MANNER, AND TURNED OVER TO THE

ADA INSTRUCTIONS TO CONTRACTOR:

THAN 1:50 IN ANY DIRECTION (1/4" PER FOOT OR NOMINALLY 2.0%) FOR POSITIVE DRAINAGE.

OWNER/DEVELOPER UPON COMPLETION OF THE WORK.

CONTRACTORS MUST EXERCISE APPROPRIATE CARE AND PRECISION IN CONSTRUCTION OF ADA (ACCESSIBLE) ACCESSIBLE COMPONENTS AND ACCESS ROUTES FOR THE SITE. THESE COMPONENTS, AS CONSTRUCTED, MUST COMPLY WITH ALL APPLICABLE STATE AND LOCAL ACCESSIBILITY LAWS AND REGULATIONS AND THE CURRENT ADA AND/OR STATE ARCHITECTURAL ACCESS BOARD STANDARDS AND REGULATIONS' BARRIER FREE ACCESS AND ANY MODIFICATIONS. REVISIONS OR UPDATES TO SAME. FINISHED SURFACES ALONG THE ACCESSIBLE ROUTE OF TRAVEL FROM PARKING SPACE, PUBLIC TRANSPORTATION, PEDESTRIAN ACCESS, INTER-BUILDING ACCESS. TO POINTS OF ACCESSIBLE BUILDING ENTRANCE/EXIT, MUST COMPLY WITH THESE ADA AND/OR ARCHITECTURAL ACCESS BOARD CODE REQUIREMENTS. THESE INCLUDE, BUT

• PARKING SPACES AND PARKING AISLES - SLOPE SHALL NOT EXCEED 1:50 (1/4" PER FOOT OR NOMINALLY 2.0%) IN ANY DIRECTION. • CURB RAMPS - SLOPE MUST NOT EXCEED 1:12 (8.3%) FOR A MAXIMUM OF SIX (6) FEET.

• LANDINGS - MUST BE PROVIDED AT EACH END OF RAMPS, MUST PROVIDE POSITIVE DRAINAGE, AND MUST NOT EXCEED 1:50 (1/4" PER FOOT OR NOMINALLY 2.0%) IN ANY

 PATH OF TRAVEL ALONG ACCESSIBLE ROUTE - MUST PROVIDE A 36-INCH OR GREATER UNOBSTRUCTED WIDTH OF TRAVEL (CAR OVERHANGS AND/OR HANDRAILS CANNOT REDUCE THIS MINIMUM WIDTH). THE SLOPE MUST BE NO GREATER THAN 1:20 (5.0%) IN THE DIRECTION OF TRAVEL, AND MUST NOT EXCEED 1:50 (1/4" PER FOOT OR NOMINALLY 2.0%) IN CROSS SLOPE. WHERE PATH OF TRAVEL WILL BE GREATER THAN 1:20 (5.0%), ADA RAMP MUST BE ADHERED TO. A MAXIMUM SLOPE OF 1:12 (8.3%), FOR A MAXIMUM RISE OF 2.5 FEET, MUST BE PROVIDED. THE RAMP MUST HAVE ADA HAND RAILS AND "LEVEL" LANDINGS ON EACH END THAT ARE CROSS SLOPED NO MORE

• DOORWAYS - MUST HAVE A "LEVEL" LANDING AREA ON THE EXTERIOR SIDE OF THE DOOR THAT IS SLOPED AWAY FROM THE DOOR NO MORE THAN 1:50 (1/4" PER FOOT OR NOMINALLY 2.0%) FOR POSITIVE DRAINAGE. THIS LANDING AREA MUST BE NO LESS THAN 60 INCHES (5 FEET) LONG, EXCEPT WHERE OTHERWISE PERMITTED BY ADA STANDARDS FOR ALTERNATIVE DOORWAY OPENING CONDITIONS. (SEE ICC/ANSI A117.1-2003 AND OTHER REFERENCED INCORPORATED BY CODE.)

 WHEN THE PROPOSED CONSTRUCTION INVOLVES RECONSTRUCTION. MODIFICATION. REVISION OR EXTENSION OF OR TO ADA COMPONENTS FROM EXISTING DOORWAYS OR SURFACES. CONTRACTOR MUST VERIFY EXISTING ELEVATIONS SHOWN ON THE PLAN. NOTE THAT TABLE 405.2 OF THE DEPARTMENT OF JUSTICE'S ADA STANDARDS FOR ACCESSIBLE DESIGN ALLOWS FOR STEEPER RAMP SLOPES. IN RARE CIRCUMSTANCES. THE CONTRACTOR MUST IMMEDIATELY NOTIFY THE DESIGN ENGINEER OF ANY DISCREPANCIES AND/OR FIELD CONDITIONS THAT DIFFER IN ANY WAY OR ANY RESPECT FROM WHAT IS SHOWN ON THE PLANS, IN WRITING, BEFORE COMMENCEMENT OF WORK. CONSTRUCTED IMPROVEMENTS MUST FALL WITHIN THE MAXIMUM AND MINIMUM LIMITATIONS IMPOSED BY THE BARRIER FREE REGULATIONS AND THE ADA

• THE CONTRACTOR MUST VERIFY THE SLOPES OF CONTRACTOR'S FORMS PRIOR TO POURING CONCRETE. IF ANY NON-CONFORMANCE IS OBSERVED OR EXISTS, CONTRACTOR MUST IMMEDIATELY NOTIFY THE ENGINEER PRIOR TO POURING CONCRETE. CONTRACTOR IS RESPONSIBLE FOR ALL COSTS TO REMOVE, REPAIR AND

IT IS STRONGLY RECOMMENDED THAT THE CONTRACTOR REVIEW THE INTENDED CONSTRUCTION WITH THE LOCAL BUILDING CODE PRIOR TO COMMENCEMENT OF

KEY	DESCRIPTION	KEY	DESCRIPTION
ВС	BOTTOM CURB	PROP.	PROPOSED
TC	TOP CURB	TBR/R	TO BE REMOVED AND REPLACED
вос	BACK OF CURB	TBR	TO BE REMOVED
BW	BOTTOM OF WALL GRADE	TPF	TREE PROTECTION FENC
TW	TOP OF WALL	BLDG.	BUILDING
EXIST.	EXISTING	SF	SQUARE FEET
BM.	BENCHMARK	SMH	SEWER MANHOLE
EOP	EDGE OF PAVEMENT	DMH	DRAIN MANHOLE
Ą.	CENTERLINE	STM.	STORM
FF	FINISHED FLOOR	SAN.	SANITARY
V.I.F.	VERIFY IN FIELD	CONC.	CONCRETE
GC	GENERAL CONTRACTOR	ARCH.	ARCHITECTURAL
HP	HIGH POINT	DEP.	DEPRESSED
LP	LOW POINT	R	RADIUS
TYP.	TYPICAL	MIN.	MINIMUM
INT.	INTERSECTION	MAX.	MAXIMUM
PC.	POINT OF CURVATURE	No. /#	NUMBER
PT.	POINT OF TANGENCY	W.	WIDE
PI.	POINT OF INTERSECTION	DEC.	DECORATIVE
PVI.	POINT OF VERTICAL INTERSECTION	ELEV.	ELEVATION
STA.	STATION	UNG.	UNDERGROUND
GRT	GRATE	R.O.W.	RIGHT OF WAY
INV.	INVERT	LF	LINEAR FOOT
DIP	DUCTILE IRON PIPE	LOD	LIMIT OF DISTURBANCE
PVC	POLYVINYL CHLORIDE PIPE	LOW	LIMIT OF WORK
HDPE	HIGH DENSITY POLYETHYLENE PIPE	L.S.A.	LANDSCAPED AREA
RCP	REINFORCED CONCRETE PIPE	±	PLUS OR MINUS
S	SLOPE	0	DEGREE
ME	MEET EXISTING	Ø / DIA.	DIAMETER

TYPICAL ABBREVIATIONS


TY	PICAL LEGE	ND
EXISTING		PROPOSED
	PROPERTY LINE	
	SETBACK	
	EASEMENT	
	CURB =	
Ø	STORM MANHOLE	©
<u></u>	SEWER MANHOLE	©
	CATCH BASIN	
₩F#5	WETLAND FLAG	
	WETLAND LINE	
× 54.83	SPOT ELEVATION	53.52
× TC 54.58 G 53.78	TOP & BOTTOM OF CURB	TC=54.32 BC=53.82
53	CONTOUR .	
	FLOW ARROW	5 %_
	PAINTED ARROW	
	RIDGE LINE	
	GAS LINE	G
	TELEPHONE LINE	ттт
EE	ELECTRIC LINE	EE
	WATER LINE	
	OVERHEAD WIRE	—— OH——— ОН—
======	STORM PIPE	
======	= = SANITARY LINE	SS
10	PARKING COUNT	•
+	SIGN	-
<5>	LIGHT POLE	
	GUIDE RAIL —	I I
Ø	UTILITY POLE	ø


REFER TO OVERALL SITE PLAN - STOP SIGNS AND MARKINGS PLAN FOR **ZONING ANALYSIS TABLE AND LAND USE | ZONING INFORMATION & NOTES**





CHECKED JJC/JGB 06/29/2023 AS NOTED MAA230031.00









450 PROVI
WAL-MAR
2001 SE 10


DRAWN
BTJ/TJN
CHECKED
JJC/JGB

DATE
06/29/2023

SCALE
AS NOTED


JOB No.
MAA230031.00

SHEET



KE VISIUNZ BY

SITE CIVIL AND CONSULTING ENGINEERING
LAND SURVEYING
PROGRAM MANAGEMENT
LANDSCAPE ARCHITECTURE
SUSTAINABLE DESIGN
PERMITTING SERVICES
TRANSPORTATION SERVICES
TRANSPORTATION SERVICES





RCENTER #5777-228
ROVIDENCE ROAD, TOWN OF BROOMMART STORES, INC.

Valmart > 1/2

DRAWN
BTJ/TJN
CHECKED
JJC/JGB
DATE
06/29/2023
SCALE
AS NOTED
JOB No.
MAA230031.00
SHEET

SSM-1









OOKLYN, CT


450 PROVIDENCE ROAD, TOWN O
WAL-MART STORES, INC.


Walmart >

DRAWN
BTJ/TJN
CHECKED
JJC/JGB

DATE
06/29/2023
SCALE
AS NOTED
JOB No.
MAA230031.00
SHEET

SECP-1











450 PROVIDENCE RC
WAL-MART STORES,
2001 SE 10TH STREE







SITE CIVIL AND CONSULTING ENGINEERING
LAND SURVEYING
PROGRAM MANAGEMENT
LANDSCAPE ARCHITECTURE
SUSTAINABLE DESIGN
PERMITTING SERVICES
TRANSPORTATION SERVICES
TRANSPORTATION SERVICES
TRANSPORTATION SERVICES

OBOSTED FOR MAY PROPER YEAR OF THE SERVICES

TRANSPORTATION SERVICES

TRANSPORTED FOR SERVICES

OBOSTED FOR MAY PROPER SERVICES

DESIGN PROPER ONLY MAPPENDE SIGNED PLANS SHALL BE UTLIZED FOR CONSTRUCTION PURPOSES

OB OTHER AND SHALL PROPER OF THE SERVICES


DE OTHER PLANS SHALL BE UTLIZED FOR CONSTRUCTION PURPOSES




450 PROVIDENCE
WAL-MART STORI
2001 SE 10TH STF

DRAWN
BTJ/TJN
CHECKED
JJC/JGB

DATE
06/29/2023
SCALE
AS NOTED
JOB No.
MAA230031.00
SHEET











Valmart // WAL

DRAWN
BTJ/TJN
CHECKED
JJC/JGB

DATE
06/29/2023
SCALE
AS NOTED
JOB No.
MAA230031.00
SHEET











CENTER #5777-228
OVIDENCE ROAD, TOWN OF BROOKLYN, CTIART STORES, INC.


Walmart >'\


DRAWN
BTJ/TJN
CHECKED
JJC/JGB
DATE
06/29/2023
SCALE
AS NOTED
JOB No.
MAA230031.00
SHEET
SECPI
SSMI
DETAILS

SHEET












KE VISIUNS BY










KE A 121 MIN 2 B 1





ERCENTER #5777-228
PROVIDENCE ROAD, TOWN OF B
-MART STORES, INC.



DRAWN
BTJ/TJN
CHECKED
JJC/JGB

DATE
06/29/2023
SCALE
AS NOTED
JOB No.
MAA230031.00
SHEET

3.4 PATCHING

- A. Where improvements are removed from paved areas, pavements shall be sawcut in straight lines at the perimeter and patched. Damaged pavement adjacent to removed improvements shall also be removed and patched.
- B. Pavement patches shall be paved with minimum 6" concrete, broom finished and flush with adjacent grades.

3.5 FILLING VOIDS

- A. Completely fill below grade areas and voids resulting from demolition or removal of structures, etc., using aggregate fill materials consisting of stone, gravel, or sand free from debris, trash, frozen materials, roots, and other organic matter.
- B. Areas to be filled shall be free of standing water, frost, frozen or unsuitable material, trash, and debris prior to fill placement. C. Place fill materials in lifts not to exceed 6 inches loose measure and compacted to 95 percent of maximum laboratory density per ASTM D698 with moisture content of not less than 1 percent below and not more than 3 percent above optimum moisture content.

3.6 DISPOSAL OF DEMOLISHED MATERIALS

A. Remove from site debris, rubbish, and other materials resulting from demolition operations. Leave areas of work in clean

D. Grade surface to match adjacent grades and to provide flow of surface drainage after fill placement and compaction.

- B. No burning of any material, debris, or trash on site or off site will be allowed.
- C. Transport materials removed from demolished structures with appropriate vehicles and dispose off-site to areas that are approved for disposal by governing authorities and appropriate property owners.

END OF SECTION

- Exterior Sidewalk Curbs and Guard posts: Yellow
- Exterior Light Pole Bases: Yellow (unless otherwise noted on Construction Detail).
- Fire Lanes: Red or per local code.
- Lane Striping where separating traffic moving in opposite directions: Yellow. Lane Striping where separating traffic moving in the same direction: White.
- ADA Symbols: Blue or per local code.
- ADA parking space markings as shown on the drawings.
- Parking Stall Striping: Yellow, unless otherwise noted on Construction Drawings.
- Associate Parking Area: White, unless otherwise noted on Construction Drawings.
- "Pickup" area striping and other areas as shown on site plan and in associated details Orange, as specified herein. D. Apply glass beads at pedestrian crosswalk striping and at lane striping and arrows at driveways connecting to public streets. Broadcast glass beads
- uniformly into wet markings at a rate of 6 lb/gal.

3.5 FIELD QUALITY CONTROL

A. Field quality control shall be the responsibility of the Contractor. Field quality control testing and inspection shall be at the discretion of the Contractor as necessary to assure compliance with Contract requirements.

CLEANING

END OF SECTION

A. Waste materials shall be removed at the end of each workday. Upon completion of the work, all containers and debris shall be removed from the site. Paint spots upon adjacent surfaces shall be carefully removed by approved procedures that will not damage the surfaces and the entire job left clean and acceptable.

TRAFFIC SIGNS AND SIGNALS SPECIFICATION

PART 1 - GENERAL

- 1.1 SUMMARY
- 1. Traffic control signs.

A. Section Includes:

- B. Related Requirements: 1. Section 09900 - Painting. Painting for painted posts where shown on the Drawings.
- 1.2 REFERENCES
- A. The publications listed below form a part of this specification to the extent referenced. Publications are referenced within the text by the basic designation only.
- B. ASTM International (ASTM): ASTM A53 - Pipe, Steel, Black and Hot Dipped, Zinc Coated Welded and Seamless.
- ASTM C94 Ready Mix Concrete
- ASTM D4956 Retroreflective Sheeting for Traffic Control.
- C. US Department of Transportation, Federal Highway Administration: Manual on Uniform Traffic Control Devices (MUTCD).

PART 2 - PRODUCTS

- 2.1 SIGNS
- A. Conform to US Department of Transportation MUTCD. Sign classification, type, size, and color shall be as shown on the drawings B. Retroreflectivity: Microprismatic type, diamond grade reflective sheeting conforming to ASTM D 4956, Type XI.
- 2.2 POSTS
- A. Square Post: Square tubular steel sign post, galvanized, 12 ga, perforated full-length with 7/16 inch holes on four sides. Post size shall be as shown on the Drawings.
- B. Steel Pipe: ASTM A 53, Type E (electric-resistance welded) or Type S (seamless), Grade B, Schedule 40, size as shown on the Drawings.
- 2.3 CONCRETE
- A. Mix concrete and deliver in accordance with ASTM C 94.
- B. Design mix to produce normal weight concrete consisting of Portland cement, aggregate, water reducing admixture, air entraining admixture, and water to produce following:
 - Compressive Strength: 3,500 psi, minimum at 28 days, unless otherwise indicated on the Drawings.
- Slump Range: 1 to 3-inches at time of placement Air Entrainment: 5 to 8 percent

3.1 PREPARATION

PART 3 - EXECUTION

- A. Field verify underground utilities prior to sign installation. Primary utilities of concern of shallow depths are lawn sprinkler systems, electric, telephone, fiber optic, cable and gas.
- INSTALLATION
- A. Install signs as shown on the Drawings and in accordance with MUTCD and manufacturer's instructions.
- B. Install signs of the type and at locations shown on the Drawings.
- C. Install posts of the type as shown on the drawing. D. Where shown as painted, field paint steel pipe posts in accordance with Section 09900.

END OF SECTION

SEAL COAT SHALL BE APPLIED WHERE EXISTING MARKINGS ARE REMOVED.

SMALL PROJECT SEAL COAT SPECIFICATION:

CRACK FILLING AND OIL SPOT TREATMENTS ARE NOT REQUIRED PRIOR TO SEAL COAT. OTHER THAN THESE EXCEPTIONS, PREPARE AND CLEAN AREA TO BE SEAL COATED CONSISTENT WITH

- MICRO-PAVE PRO-BLEND WITH ADDED SAND
- POLYMER MODIFIED MASTERSEAL WITH ADDED SAND

WITH ADDED SAND SINGLE COAT

MATERIALS IDENTIFIED IN SPECIFICATION SECTION 02787 CAN BE USED. COAL TAR BASED SEAL COAT

SPECIFICATIONS

SHEET

IN GENERAL:

MANUFACTURER'S INSTRUCTIONS AND SPECIFICATION.

APPROVED MATERIALS:

- STAR PRODUCTS
- · SINGLE COAT
- SEAL MASTER
- SINGLE COAT
- GEM SEAL BLACK DIAMOND XL

MATERIALS IN ANY FORM ARE PROHIBITED.

JJC/JGB AS NOTED

2.3 EQUIPMENT

A. Distributors. Distributors or spray units used for the spray application of the seal coat shall be self-propelled and capable of uniformly applying 0.10 to 0.30 gallons per square yard of material over the required width of application. Distributors shall be equipped with tachometers, pressure gauges, and volume measuring devices. The mix tank shall have a mechanically powered, full sweep, mixer with sufficient power to move and homogeneously mix the entire contents of the tank.

B. Spray Nozzles. Nozzles shall be free from clogs and debris and set at the same angle.

C. Mixing Equipment. The mixing machine shall have a continuous flow mixing unit capable of accurately delivering a predetermined proportion of aggregate, water, and emulsion, and of discharging the thoroughly mixed product on a continuous basis. The mixing unit

shall be capable of thoroughly blending all ingredients together and discharging the material without segregation. D. Spreading Equipment. Spreading equipment shall be a mechanical type squeegee/brush distributor attached to the mixing machine, equipped with flexible material in contact with the surface to prevent loss of slurry from the spreader box. It shall be maintained to prevent loss of slurry on varying grades and adjusted to assure uniform spread. There shall be a lateral control device and a flexible strike off capable of being adjusted to lay the slurry at the specified rate of application. The spreader box shall have an adjustable width. The box shall be kept clean. Emulsion and aggregate build up on the box shall not be permitted.

E. Clean equipment with a petroleum solvent if previously used with a different material.

F. Hand Squeegee or Brush Application. Hand spreading application shall be used only in places not accessible to the mechanized equipment or to accommodate neat trim work at curbs, etc. Material that is applied by hand shall meet the same standards as that applied by machine.

G. Calibration. Spreading equipment shall be provided with a method of calibration by the manufacturer. Equipment shall be calibrated to assure that it will produce and apply a mix that conforms to the job mix formula. Calibrations shall be made with the approved job materials prior to application of the seal coat.

2.4 PREPARATION

A. Remove all existing striping in areas subject to seal coating as noted in plans. Reference applicable specification section in Site Demolition.

B. Remediate distressed areas of existing pavement by saw-cutting and removing existing pavement, regrading and compacting the underlying base course and replacing with full depth asphalt at locations and as shown on the drawings. 1. Repairs not specifically shown on the plans but considered necessary by the contractor, store manager or construction manager (CM)

shall be identified and submitted as an RFI to the project team prior to commencement of repairs. 2. Repairs submitted by RFI and approved shall be performed as directed by the CEC. Cost for such work directed and performed will be paid for in accordance with the "Changes in the Work" Clause of the General Conditions.

C. Longitudinal and traverse cracks in excess of 0.25 inch, but less than 1 inch shall be sealed with a crack sealant. Cracks that contain weed or other live vegetable matter shall be treated with a locally approved, non-oil based sterilant prior to applying the crack filler.

D. Existing crack sealants in the parking lot shall be evaluated for compatibility with the specified emulsion. If not compatible with each other they can't be used together. Immediately prior to applying the seal coat, the surface shall be cleared of all loose material, dirt, dust, grease, oil, vegetation and other objectionable material. If water is used, cracks shall be allowed to dry thoroughly before applying the seal coat.

E. Protect existing manholes, inlets, value boxes, meter boxes, etc. as necessary to maintain free accessibility upon completion of seal coat application. Surfaces adjacent to seal coat application areas such as sidewalks, curb and/or gutter, storefronts, etc. shall be protected by use of felt paper anchored with clean aggregate, or by shielding components with plywood during application.

F. Coordinate limits of seal coat application operations with Owner's Construction Manager and Store Manager to avoid interruption to store operations. Protect adjacent areas of the parking lot outside of current seal coat application limits to avoid tracking onto adjacent areas. Partition off limits of current seal coat operations until surface is traffic ready.

G. Coordinate with Store Manager to deactivate lawn sprinkler systems least 48 hours prior to placing the seal coat and remain off for at

least 24 hours after the seal coat application.

A. Apply seal coat at a total rate (undiluted) of 0.17gal./SY.

B. Dampen pavement with a fog spray of water if ambient temperatures exceed 80°F. No standing water shall remain on the surface.

C. Apply the coat uniformly in a manner such that the combined application of the coat equals the total rate specified above.

D. Suspend application when the distribution tank has less than 100 gallons left and refill to prevent irregular patterns or misses. E. The coat shall be allowed to dry and cure initially a minimum of 2-4 hours before applying any markings. The initial drying shall allow

evaporation of water of the applied mixture, resulting in the coating being able to sustain light foot traffic. The initial curing shall enable the mixture to withstand vehicle traffic without damage to the seal coat.


F. The finished surface shall present a uniform texture with no streaks. G. The single coat shall be allowed to dry a minimum of eight hours in dry daylight conditions before opening to traffic, and initially cure enough to support vehicular traffic without damage to the seal coat.

H. Where marginal weather conditions exist during the eight hour drying time, additional drying time shall be allowed. The length of time shall be as specified by the supplier. The surface shall be checked after the additional drying time for trafficability before opening the section to vehicle traffic.


END OF SECTION

2.5 APPLICATION











Wetland Delineation • Wetland Assessment & Permitting • Wildlife & Botanical Surveys • Fisheries & Aquatics • GIS Mapping

June 23, 2023

Jeff Bord Bohler 65 LaSalle Rd, Suite 401 West Hartford, CT 06107

RE: Wetland and Watercourse Delineation Report
Walmart Property
450 Providence Road, Brooklyn

Mr. Bord,

At your request, I conducted an inspection on the above-referenced property on June 20, 2023 as depicted on the attached *Wetland Delineation Sketch Map*. The purpose of the inspection was to delineate the Connecticut jurisdictional wetlands and watercourses. The inspection was conducted by a soil scientist according to the requirements of the Connecticut Inland Wetlands and Watercourses Act (P.A. 155).

Inland wetlands include soil types designated as poorly drained, very poorly drained, alluvial, and floodplain by the National Cooperative Soils Survey as may be amended from time to time, of the National Resources Conservation Service (NRCS). Watercourses means rivers, streams, brooks, waterways, lakes, ponds, marshes, swamps, bogs and all other bodies of water, natural or artificial, vernal or intermittent. Intermittent watercourses shall be delineated by a defined permanent channel and bank and the occurrence of two or more of the following characteristics: (A) Evidence of scour or deposits of recent alluvium or detritus, (B) the presence of standing or flowing water for a duration longer than a particular storm incident, and (C) the presence of hydrophytic vegetation.

Wetlands were delineated by examining the upper 20" of the soil profile with an auger. Those areas meeting the requirements noted above were marked with pink flagging tape labeled "Wetland Delineation" and numbered 1-25. The field placed wetland flags are accurately depicted on the Project plans prepared by Bohler.

Wetland Description

The delineated wetlands consist of a series of constructed stormwater ponds. The ponds are entirely anthropogenic in origin, created to manage stormwater runoff from the developed areas of the site. There are four ponds in total, all of which are connected during larger storm events via stone-lined swales. The ponds have naturalized, with shoreline vegetation including areas of emergent vegetation in the shallow water portions. No areas of bank erosion were observed, and there was no visible turbidity in the water column, sediment plumes or excessive algal blooms.

Vegetation present includes cattails, willows, soft rush, various sedges, sensitive fern, and goldenrods, with some small areas of the invasive reed canary grass. Both bullfrog and green frog are abundant, as is typical in urban pond systems. A fisherman was present who indicating that the large eastern pond supports "panfish", presumably bluegill or other warmwater fish species. Overall, considering the design purpose of these ponds, they have naturalized nicely and likely provide habitat for a number of common wetland-dependent species.

The surrounding uplands are maintained via mowing to prevent woody growth, but mowing appears infrequent, and thus the habitat presents as a meadow that offers habitat for a variety of insect species.

Soil Types

Soils present in the delineation area reflect the intended construction of both upland and wetland resources. Both wetland and upland soil types are anthropogenic soil. Wetland soils are classified as Aquents. Aquents is a miscellaneous land type used to denote areas of anthropogenic origin or disturbance that are poorly drained or very poorly drained, and hydric. These soils have an aquic soil moisture regime and can be expected to support hydrophytic vegetation. Typically, these soils occur in places where less than two feet of earthen material have been placed over poorly or very poorly drained soils; areas where the natural soils have been mixed so that the natural soil layers are not identifiable; or where the soil materials have been excavated to the watertable.

The non-wetland soils consist of the Udorthents. Udorthents is a miscellaneous land type used to denote moderately well to excessively drained earthen material which has been so disturbed by cutting, filling, or grading that the original soil profile can no longer be discerned.

Project Review and Impact Evaluation

Davison Environmental reviewed the project plans prepared by Bohler. Specifically, we

considered the potential for the project to impact the function of the stormwater ponds. The project

consists of a building expansion along with reconfiguration of the eastern parking area. Based on

our review, we see no impact to wetland functions resulting from the proposed project, based on

the following facts:

1. The project is sited within an existing area of development. No naturalized areas will be

disturbed.

2. There are no direct wetland impacts proposed. All activities are located outside of the 50-

foot Upland Review Area.

3. The primary means by which these stormwater ponds could be impacted is by increasing

runoff that exceeds the design flows. This would occur if the project resulted in additional

impervious cover. In this case, the proposed project will decrease total impervious cover

slightly (<660s.f.). Therefore, there will be no increase in total volume or peak flow of runoff

entering the system.

If you have any questions regarding these findings, please feel free to contact me.

Respectfully submitted,

Eric Davison

Professional Wetland Scientist

Registered Soil Scientist

eric@davisonenvironmental.com

www.davisonenvironmental.com

Attachments: (1) Wetland Photographs

-3-



Photo 1: View of easternmost stormwater pond looking north.



Photo 2: View across all three field delineated ponds, looking east.



Photo 3: Culvert outlet to second pond. Note dense emergent vegetation (cattails).



Photo 4: View of second pond, looking east. Note naturalized shoreline and bordering meadow vegetation.






69 South Main Street Brooklyn CT 06234 (860) 779-3411 x 31

Inland Wetlands	Zoning Enforcement	Blight Enforcement
SITE INSPECT	ION NUMBER	1 2 3 4 5
450 Provid	enco Rd.	7-19-23
Add		Date
I met 13	Ben Jednak	and Janet
Booth,	inspected a	and Janet nd took photos.
	V	
We revis	rured the plans	Hisa
	g expansion	
	ation, with	
	ervious surfac	
		,
There will	be more per v.	· ous
- suffect	<u>,</u> (20	
approv	al is recommo	nded.
Commission Repres	entative M. Was	Moure
Owner or Authories	ed Signature By Jales	
Owner or Authorize	su signature proposition	


















8/2/23

Hi Margaret,

I apologize for getting my comments to you on the Walmart expansion plan.

I have reviewed the very detailed plans and have no issues, especially seeing that the planned expansion with parking lot modifications will decrease the amount of impermeable surface. There are no drainage issues with the proposed work.

The wetland report contains a lot of good information - a good example for some of our local soil scientists to emulate with their analysis and reports.

If you have any questions, please do not hesitate to contact me.

Syl



TOWN OF BROOKLYN

Land Use Department 69 South Main Street • Suite 22 BROOKLYN, CONNECTICUT 06234 860-779-3411 Ext. 12

ORDER TO CORRECT WETLANDS VIOLATIONS

CERTIFIED#

9489 0090 0027 6215 8965 51

Janessa Choquette 648 Cooper Road Glocester, RI 02814 August 1, 2023

Re: Collapse of side slope and fill in wetlands at 253 Wolf Den Road

Dear Ms. Choquette,

Heavy rains in July caused a portion of the recent site work done at your property at 253 Wolf Den Road CT (Assessors Map 17 Lot 32-3) in Brooklyn, to collapse, following the installation of the permitted wetlands crossing. Several cubic yards of material flowed down the slope into wetlands and an intermittent watercourse, which is now partially buried. Please refer to the attached inspection report and photographs.

The wetland filling is in violation of IWWC permit, # IWWC 22-004, issued to Keith Pasay on November 8, 2022.

YOU ARE HEREBY REQUIRED TO:

- 1. Attend the Inland Wetlands and Watercourses Commission meeting on August 8, 2023 at 6 pm at 31 Tiffany Street (upper level) in Brooklyn, CT. At that meeting, a hearing will take place to provide you the opportunity to be heard and show cause why the Order to Correct should not remain in effect.
- 2. Submit an engineer's plan and construction sequence designed to
- (a) remove the sediment from the wetland;
- (b) repair the slope; and
- (c) provide a design solution so that it doesn't occur again.

Please refer to the attached copy of Section 6 of the Town of Brooklyn IWWC Regulations, which states that any person violating provisions of these regulations shall be subject to enforcement proceedings and penalties.

Refer to the attached copy of the CT Wetlands Statutes, Section 22a – 44(b) which enables municipalities to assess civil penalties for violations.

Your cooperation would be greatly appreciated.

Please feel free to contact me if you have any questions.

Issued by:

Margaret Washburn

ZEO/WEO/Blight Enforcement Officer

Margaret Washburn

69 South Main Street, Suite 23

Brooklyn, CT 06234

(860) 779-3411 ext. 31

Mon. – Thurs. 8:00 am - 3:30 pm

m.washburn@brooklynct.org


CC: Austin Tanner, First Selectman; Jana Roberson, Town Planner; Keith Pasay




69 South Main Street Brooklyn CT 06234 (860) 779-3411 x 31

Inland Wetlands	Zoning Enforcement_	Blight Enforcement
SITE INSPECTI	ON NUMBER	1 2 3 4 5
253 WolfT Addr	en Rd	7/26/23
		Date
- Juspertod	and took	photos inresponse
to a compl	and from	Charles Browning.
There has	been a was	hout on the
i i		the driveway and
_ the wetla	nds to the	west of the
_ location	where the	pipes were recently tended pipes appear
_externeled	, The ex	tended pipes appear
to be stal	Lo, for nou	Vi
	7 0	
The siltfen	ce May ba	les are holding back
_ the sedimon	t from wash	ing downstroam.
Dontact (hairman Oli	verson and IWWC monders
_ B schedul	ea show cou	use hearing/issue NOV
Commission Represen	tative <u>M. Wa</u>	shburn
Owner or Authorized S	Signature	







ction **O**

Regulated Activities to be Licensed

No person shall conduct or maintain a regulated activity without first obtaining a permit for such activity from the Brooklyn Inland Wetlands and Watercourses Commission of the Town of Brooklyn.

Any person found to be conducting or maintaining a regulated activity without the prior authorization of the Commission, or violating any other provision of these regulations, shall be subject to the enforcement proceedings and penalties prescribed in section 14 of these regulations and any other remedies as provided by law.

its inland wetlands regulations, or (2) for which an approval is required under sections 22a-36 to 22a-45, inclusive, and for which such approval has not been obtained.

- (b) Any person who commits, takes part in, or assists in any violation of any provision of sections 22a-36 to 22a-45, inclusive, including regulations adopted by the commissioner and ordinances and regulations promulgated by municipalities or districts pursuant to the grant of authority herein contained, shall be assessed a civil penalty of not more than one thousand dollars for each offense. Each violation of said sections shall be a separate and distinct offense, and, in the case of a continuing violation, each day's continuance thereof shall be deemed to be a separate and distinct offense. The Superior Court, in an action brought by the commissioner, municipality, district or any person, shall have jurisdiction to restrain a continuing violation of said sections, to issue orders directing that the violation be corrected or removed and to assess civil penalties pursuant to this section. All costs, fees and expenses in connection with such action shall be assessed as damages against the violator together with reasonable attorney's fees which may be allowed, all of which shall be awarded to the commissioner, municipality, district or person which brought such action. All penalties collected pursuant to this section shall be used solely by the Commissioner of Energy and Environmental Protection (1) to restore the affected wetlands or watercourses to their condition prior to the violation, wherever possible, (2) to restore other degraded wetlands or watercourses, (3) to inventory or index wetlands and watercourses of the state, or (4) to implement a comprehensive training program for inland wetlands agency members.
- (c) Any person who wilfully or knowingly violates any provision of sections 22a-36 to 22a-45, inclusive, shall be fined not more than one thousand dollars for each day during which such violation continues or be imprisoned not more than six months or both. For a subsequent violation, such person shall be fined not more than two thousand dollars for each day during which such violation continues or be imprisoned not more than one year or both. For the purposes of this subsection, "person" shall be construed to include any responsible corporate officer.

(1972, P.A. 155, S. 9; P.A. 75-387, S. 2; P.A. 76-330; P.A. 77-599, S. 4, 7; P.A. 81-125, S. 1; P.A. 87-338, S. 9, 11; P.A. 95-151, S. 2; 95-218, S. 13, 24; P.A. 96-269, S. 2; P.A. 11-80, S. 1.)

History: P.A. 75-387 made previous provisions Subsec. (b) and inserted new Subsec. (a) re orders issued upon discovery of violation of Secs. 22a-36 to 22a-45 or regulations of inland wetlands agency; P.A. 76-330 allowed assessment of attorneys fees against violator and required that all costs, etc. be awarded to the initiator of the action; P.A. 77-599 amended Subsec. (a) to allow issuance of orders to cease an activity as well as orders to correct facilities or conditions; P.A. 81-125 amended Subsec. (a) to authorize



	Δ,	
A	service no.	· nart
	to leget	
	Toll skell	8

69 South Main Street


Brooklyn CT (860) 779-341	
Inland Wetlands Zoning Enforcement_	Blight Enforcement
SITE INSPECTION NUMBER	1 2 3 4 5
183 Barrett Hill Rd Address	7/20/23 Date
A horse barn is pro building envelope p	for, and Lonce of Ag- Tinspected + posed with
There are no young issu The Town has to wai	es; there are no wetlands issues.
Zoning permit until	^
approval has been iss	
The Murphys agree not excavaled to soil in	to spread the any wetlands.
Commission Representative	
Owner or Authorized Signature Notify Tommy of now	mughs barn re


X

20161671 - PDR Survey....






















69 South Main Street Brooklyn CT 06234 (860) 779-3411 x 31

Inland Wetlands	Zoning Enforce	cement	Blight Enforcement
SITE INSPEC	TION NUMBER	2	1 2 3 4 5
409+4/1 Church	St drive	way	7/31/23 Date
The drive	way ha	heen o	overed with
· // / .	1	am Br	in damour,
Janet 1	Booth and	d Juis	pected. The
milling	have n	nade to	
1	. 0	1 1 1	Sides of the
pipe a		_ ^	ost wetlands
cross	a a constant of the constant o		ater flowing through
this pipe, 1	Water is flor	wing throu	ight the other 2 pipes.
^ .	ausch wr		, , , ,
//	nove the	4	
	The pip		I the westernmost
crossir	19:		
_ [Email Ja	the task hi	m to let n	ic know when the
millingsha	ve been ren	noved pro	m the wetlands.
V	entative <u>M. W</u>		u
Owner or Authorized	d Sionature		











69 South Main Street Brooklyn CT 06234 (860) 779-3411 x 31

Inland Wetlands Zoning Enforcement	
Inland Wetlands V Zoning Enforcement V	Blight Enforcement
SITE INSPECTION NUMBER	1 2 3 4 5
FCR Gravel Pit	6/29/23
Address	Date
I met David Held, inspecto.	d and took
photographs, Work reg 3/3/22 I wwc Order	wired in the
3/3/22 I WWC Order	to Remediate
and in the 3/3/22 Order	to Remediate
for Zoning Violations has	been completed
to my satisfaction.	
The Orders described above a	ire hereby closed
	đ
Commission Representative	ashburn
Owner or Authorized Signature	





CLOSED 7/26/23



TOWN OF BROOKLYN

Land Use Department
69 South Main Street • Suite 22
BROOKLYN, CONNECTICUT 06234
860-779-3411 Ext. 12

ORDER TO REMEDIATE Inland Wetlands and Watercourses Violations

CERTIFIED

2057 5250 0007 350P 57PO

To: FCR Realty, LLC 10 Day Street Brooklyn, CT 06234 March 3, 2022

Location of Violation: Westerly of Day Street Brooklyn, CT 06234

Assessor's Map 41 Lot 6 and Map 35 Lot 7

Facts

On 11/30/21, Provost & Rovero, Inc. submitted to the Brooklyn Land Use Office a Topographic Survey as of 11/25/2021 prepared for FCR Realty LLC.

Refer to the attached copy of this plan, which shows approximately one acre of earth removal has been conducted beyond the project limits approved by the Inland Wetlands Commission in their Notice of Decision dated June 20. 2018.

On 12/1/21, Margaret Washburn, Wetlands Enforcement Officer, inspected the site to conduct a compliance inspection with Keith Green.

That inspection resulted in the issuance of a Cease and Desist Order on 1/3/22.

The following activities have been observed to have occurred on your property in violation of your Inland Wetlands and Watercourses Permit # 041018A: Vegetation has been removed and material has been excavated in the Upland Review Area, beyond the approved limit of work shown on the approved plan titled Proposed Gravel Removal Plan Prepared for FCR Realty LLC Westerly of Day Street, Brooklyn, Connecticut, ("the approved plan") prepared by KWP Associates, revised October 2, 2018.

Your activities, conducted in violation of your Inland Wetlands and Watercourses Permit, are in violation of the Brooklyn Inland Wetlands and Watercourses Regulations.

On 2/2/22, at a meeting at the Clifford B. Green Memorial Center, attended by Austin Tanner, Jana Roberson, Margaret Washburn, David Held and Keith Green, Keith Green informed Town staff that FCR did not intend to renew its Gravel Special Permit with the Planning and Zoning Commission (PZC).

On 2/15/22, the PZC accepted the withdrawal of the Gravel Bank Renewal Application (GBR 21-005) by FCR Realty, LLC.

On 2/22/22, at a site inspection attended by Margaret Washburn, David Held and Keith Green, all parties agreed that when gravel bank restoration begins, the first area to be regraded will be near the undercut, overhanging vegetated banks between the gravel pit and the closest wetlands.

Applicable Laws and Regulations

The Brooklyn Inland Wetlands and Watercourses Regulations define, in part, a "regulated activity" as "any operation within or use of a wetland or watercourse involving removal or deposition of material, or any obstruction, construction, alteration or pollution, of such wetlands or watercourses...." "Material" is defined to include "means any substance, solid or liquid, organic or inorganic, including but not limited to soil, sediment, aggregate, land, gravel, clay, bog, mud, debris, sand, refuse or waste". The term "pollution" is defined to include "harmful thermal effect or the contamination or rendering unclean or impure of any waters of the state by reason of any waste or other materials discharged or deposited therein by any public or private sewer or otherwise so as directly or indirectly to come in contact with any waters. This includes, but is not limited to, erosion and sedimentation resulting from any filling, land clearing or excavation activity".

The phrase "rendering unclean or impure" is further defined as "any alteration of the physical, chemical or biological properties of any waters of the state, including, but not limited to, change in odor, color, turbidity or taste".

Furthermore, a "significant impact" is defined as "any activity, including, but not limited to, the following activities which may have a major effect:

- 1. Any activity involving deposition or removal of material which will or may have a substantial effect on the wetland or watercourse or on wetlands or watercourses outside the area for which the activity is proposed.
- 2. Any activity which substantially changes the natural channel or may inhibit the natural dynamics of a watercourse system.
- 3. Any activity which substantially diminishes the natural capacity of an inland wetland or watercourse to: support aquatic, plant or animal life and habitats; prevent flooding; supply water; assimilate waste; facilitate drainage; provide recreation or open space; or perform other functions.
- 4. Any activity which is likely to cause or has the potential to cause substantial turbidity, siltation or sedimentation in a wetland or watercourse.
- 5. Any activity which causes substantial diminution of flow of a natural watercourse or groundwater levels of the wetland or watercourse.
- 6. Any activity which is likely to cause or has the potential to cause pollution of a wetland or watercourse.
- 7. Any activity which damages or destroys unique wetland or watercourse areas or such areas having demonstrable scientific or educational value."

"Upland Review Area" means "non-wetland or non-watercourse areas where activities are likely to impact or affect wetlands or continuous watercourses".

Section 4 of the Regulations addresses exemptions, and Section 6.1 provides that any regulated activity requires a permit.

Section 6.2 states "Any person found to be conducting or maintaining a regulated activity without the prior authorization of the Commission, or violating any other provision of these regulations, shall be subject to the enforcement proceedings and penalties prescribed in section 14 of these regulations and any other remedies as provided by law".

The deposition of material within the upland review area and wetlands without a permit constitutes both a "regulated activity" and a "significant impact" under the Regulations and fall within no allowable exception. Therefore, said activities constitute a violation of the Brooklyn Inland Wetlands and Watercourses Regulations because of, at a minimum, the following condition:

a. The "deposition or removal of material which will or may have a substantial effect on the wetland or watercourse".

<u>Order</u>

You are hereby ordered to do the following: Submit to the Brooklyn Inland Wetlands and Watercourses Commission a Site Restoration Plan showing the restoration of the disturbed areas within one hundred and seventy-five (175) feet of regulated areas on or before 3/8/2022.

The Site Restoration Plan must be approved by the Commission prior to starting any work.

No grades steeper than 3:1 shall remain after restoration is complete.

Leave the undercut, overhanging vegetated banks on the edge of the gravel pit intact. This refers to the undercut, overhanging vegetated banks between the gravel pit and the closest wetlands. Do not pull the undercut, overhanging vegetated banks down.

Phase 1: Push fill in the existing gravel pit, toward the overhanging vegetated banks between the gravel pit and the closest wetlands. Do not pull the undercut, overhanging vegetated banks down. Smooth out the material so no slopes are steeper than 3:1.

TARGET DATE FOR COMPLETION: Thursday 4/7/22

Phase 2: Pull down the steep slopes near the existing road into the gravel pit. Smooth out the slopes so that no slopes are steeper than 3:1.

TARGET DATE FOR COMPLETION: Thursday, 6/9/22

Phase 3: Push the material from the slopes near the existing road, and the material from the unprocessed material stockpile, into the gravel pit and smooth out the fill. TARGET DATE FOR COMPLETION: Thursday, 7/28/22

Phase 4: Spread dark brown topsoil over the material. TARGET DATE FOR COMPLETION: Thursday, 8/18/22

Phase 5: Seed all disturbed areas in accordance with the Site Restoration Plan. TARGET DATE FOR COMPLETION: Thursday, 9/1/22

Inspections are scheduled for 9:00 am on-site meetings with Keith Green and David Held in attendance on the target dates listed above. The Commission or its duly authorized agent may make regular inspections of the required remediation work during any other reasonable hours.

All restoration work must be done under the timeline established by the Commission.

Failure to meet any of the deadlines in this Order may result in the issuance of citations.

The Brooklyn Inland Wetlands and Watercourses Duly Authorized Agent is to be notified if any phase is completed prior to its target date at 860-779-3411 ext. 31.

For each day during which to violation continues beyond the deadline in this Order, the Town may commence an enforcement action and the seek a civil penalty of up to \$1,000.00 per day for such violation, plus its attorney's fees and costs. The civil penalties are assessed by the Superior Court when an action is brought before the court by the municipality. Refer to the attached Chapter 20-2: Citation Procedures and Fines for Zoning and Wetlands Violations.

Show Cause Hearing

In accordance with Section 15.7 of the Regulations, a Show Cause Hearing will be held on this Order on Tuesday, March 8, 2022 at 6:00 p.m. via Zoom as well as in person. At this hearing, you will be given an opportunity to be heard and to show cause why this Order to Remediate should not remain in effect. Depending on the decision of the Agency, a copy of this Order, or a modified version of it, may be filed on the Brooklyn Land Records. To attend this hearing follow the instructions on the attached draft meeting agenda.

Dated at Brooklyn, this 3rd day of March 2022.

Margaret Washburn

Margaret Washburn, Enforcement Officer of the Brooklyn

Inland Wetlands and Watercourses Commission

CC: Austin Tanner, Jana Roberson, Peter Alter

Town of Brooklyn

Inland Wetlands Bu	udget FY23				From	n Date: 7/1/	2023	To Date:	7/31/2023	
Fiscal Year: 2023-2024		Include pre e	ncumbrance tive accounts wi	_	t accounts with z	ero balance	Filter Encu	ımbrance Detail b	y Date Range	€
Account Number	Description	Budget	Adjustments	GL Budget	Current	YTD	Balance	Encumbrance	Budget Bal	% Rem
1005.41.4163.51900	Inland Wetlands-Wages-Recording Secretary	\$1,000.00	\$0.00	\$1,000.00	\$87.50	\$87.50	\$912.50	\$0.00	\$912.50	91.25%
1005.41.4163.53020	Inland Wetlands-Legal Fees	\$3,500.00	\$0.00	\$3,500.00	\$0.00	\$0.00	\$3,500.00	\$0.00	\$3,500.00	100.00%
1005.41.4163.53200	Inland Wetlands-Professional Affiliations	\$65.00	\$0.00	\$65.00	\$0.00	\$0.00	\$65.00	\$0.00	\$65.00	100.00%
1005.41.4163.53400	Inland Wetlands-Professional Services	\$500.00	\$0.00	\$500.00	\$0.00	\$0.00	\$500.00	\$0.00	\$500.00	100.00%
1005.41.4163.55400	Inland Wetlands-Advertising & Legal Notices	\$500.00	\$0.00	\$500.00	\$0.00	\$0.00	\$500.00	\$0.00	\$500.00	100.00%
1005.41.4163.55500	Inland Wetlands-Printing & Publications	\$120.00	\$0.00	\$120.00	\$0.00	\$0.00	\$120.00	\$0.00	\$120.00	100.00%
1005.41.4163.56900	Inland Wetlands-Other Supplies	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$45.00	(\$45.00)	0.00%
Grand Total:		\$5,685.00	\$0.00	\$5,685.00	\$87.50	\$87.50	\$5,597.50	\$45.00	\$5,552.50	97.67%

End of Report

Printed: 08/01/2023 10:56:48 AM Report: rptGLGenRptwBudgetAdj 2023.1.18 Page: