

DRAINAGE REPORT

Prepared for

PROPOSED MULTI-FAMILY DEVELOPMENT LOUISE BERRY DRIVE BROOKLYN, CT

August 2020

Revised to January 2021

Prepared for

Shane Pollock

Prepared by

Killingly Engineering Associates

Civil Engineering & Surveying



Normand Thibeault Jr., P.E.
CT License #22834

Introduction

Shane Pollock has submitted a proposal to the Town of Brooklyn to construct a 51-unit condominium development with access from Louise Berry Drive in Brooklyn. The project will require construction of a 1000-foot-long paved roadway with a cul-de-sac turnaround, and public water and sewer. The proposal is the second version of the project, the first of which proposed 100-units. The current design results in creation of impervious surfaces consisting of pavement and roof but a significant reduction from the amount of impervious surface from the design that was originally proposed.

Summary

According to the USDA-SCS Soil Survey, the area of disturbance consists of Canton and Charlton fine sandy loams and wetlands consist of Ridgebury, Leicester and Whitman Soils. A walk of the property appears to verify that these descriptions are accurate. These soils are associated with hydrologic soil groups B and D. The site sheet flow primarily to the south to a linear wetlands system and west to areas off site. To the greatest degree possible, the drainage patterns will be preserved.

The bulk of the drainage from developed areas will be collected in a closed stormwater collection system consisting of catch basins and HDPE pipe and will be conveyed to a proposed stormwater basin at the southwestern portion of the property. Overland runoff from newly landscaped and grassed areas will be collected in a swale at the toe of fill slopes and also conveyed to the stormwater basin. Discharge from the basin will be directed back toward the wetlands that flows off the property at the southwestern boundary.

The calculations utilized HydroCAD® Stormwater Modeling System, a computer model, to analyze pre-and post-development drainage conditions, and to aid in the design of the stormwater detention system. The model used the Soil Conservation Service TR-20 method with a Type III 24-hour rainfall to calculate the runoff. The 2 through 100-year frequency storms were analyzed to evaluate peak runoff for pre-and post-construction conditions. Table 1 summarizes our findings:

Table 1. Existing & Proposed Peak Flows to

Design Storm	Depth (in)	Existing peak	Proposed peak	Difference
2-Year	3.37	3.01 CFS	2.64 CFS	-0.37 CFS
5-Year	4.28	6.48 CFS	6.18 CFS	-0.30 CFS
10-Year	5.04	10.87 CFS	10.06 CFS	-0.81 CFS
25-Year	6.08	17.63 CFS	15.11 CFS	-2.52 CFS
50-Year	6.85	23.03 CFS	18.90 CFS	-4.13 CFS
100-Year	7.68	29.21 CFS	24.03 CFS	-5.18 CFS

Installation of the proposed stormwater basin will reduce peak runoff rates from the site for all design storms. To keep the basin functioning properly and alleviate the potential for standing water in the basin, the design incorporates an underdrain around the perimeter of the basin that will discharge through the outlet structure. Based upon the channelized topography that the

wetlands follow, it is our opinion that the discharge rates for this storm will not detrimentally impact downstream properties.

In addition to addressing pre- and post-construction peak runoff rates from the property to the wetlands and adjacent property, the design considers stormwater treatment and water quality for the project. Wherever possible, overland sheet flow is encouraged, catch basins will be constructed with 4ø sediment sumps, the final catch basin prior to discharge to the stormwater basin will be retrofitted with a hooded outlet, and the detention/water quality basin accounts for Water Quality Volume (WQV) in accordance with the parameters set forth in the 2004 CTDEEP Stormwater Quality Guidelines. Following are computation for the stormwater basin and the WQV provided.

Section 7.4.1 Water Quality Volume

Basin Water Quality Volume (WQV)

$$WQV = (1.0) (R)(A)/12$$

$$R = 0.05 + 0.009(I) \quad I = \% \text{ Impervious} = 48.33\% \text{ (Stormwater System Drainage Area)}$$

$$R = 0.05 + 0.009(48.33) = 0.485$$

$$A = 4.781 \text{ acres}$$

$$WQV = (1.0) (0.485) (4.781)/12 = 0.193 \text{ ac-ft}$$

$$8417 \text{ c.f.}$$

Basin forebay + outlet side of basin provides 8,628 c.f.

Section 7.4.2 Water Quality Volume

This section is utilized for treatment mechanisms such as grass swales or proprietary treatment devices. Although the project calls for a grassed swale at the toe of the fill slope, this swale will not convey runoff from impervious surfaces.

Section 7.5.1 Groundwater Recharge Volume (GRV)

Intended to maintain pre-development and groundwater recharge volumes by capturing and infiltrating stormwater runoff.

$$GRV = (D)(A)(I) / 12$$

D = Depth of runoff to be recharged per table 7-4 of the CSQM based upon soil type

A = Site Area in acres

I = Percent Impervious (or net increase in impervious)

$$D = 0.25 \text{ (Hydrologic Soil Group } \delta B \delta)$$

$$A = 5.46 \text{ Acres}$$

$$I = 40.6\% (0.0453)$$

$$\text{GRV} = 0.25 \times 5.46 \times 0.406 / 12 = 0.0462 \text{ ac-ft}$$

$$= 2,011 \text{ c.f.}$$

Based upon soil testing, the bottom of the basin will remain wet. The area of the basin from elevations 242.5 to 245 will be available to provide the opportunity to infiltrate. The percolation rate measured in this area was 6.7 minutes per inch (about 8.9 inches per hour). We utilized a conservative rate of 4.5 inches per hour over the horizontal area (assuming no infiltration in the basin bottom) which provides the following infiltration volumes for each design storm.

Table 2. Summary of Infiltration Volume

Design Storm	Depth (in)	Infiltration Volume (Ac-ft)	Infiltration Volume (Cubic ft.)
2-Year	3.37	0.433	18,861 CF
5-Year	4.27	0.562	24,481 CF
10-Year	5.02	0.628	27,355 CF
25-Year	6.05	0.679	29,577 CF
50-Year	6.85	0.718	31,276 CF
100-Year	7.64	0.755	32,888 CF

Infiltration requirements are exceeded for all design storms

Section 7.5.2 Runoff Capture Volume (RCV)

Not utilized for this application. This method is typically utilized to capture clean stormwater from surfaces such as rooftops and infiltrate it into the soil.

Section 7.6 Peak Flow Control

Summary of Peak Flow to Wetlands

Design Storm	Depth (in)	Existing peak	Proposed peak	Difference
10-Year	5.08	10.87 CFS	8.96 CFS	-1.91 CFS
25-Year	6.08	17.63 CFS	14.21 CFS	-3.42 CFS
100-Year	7.69	29.21 CFS	25.66 CFS	-3.55 CFS

As shown above and in table 2 previously in this report, the peak flows will be attenuated for all design storms.

HYDROCAD CALCULATIONS

EXISTING CONDITIONS

3S
Off Site West



2S
Drainage Area 2

1S
Drainage Area 1

1R
Wetland Section 1

2R
Peak off Site

1R'
Wetland Section 2



Routing Diagram for Existing Conditions
Prepared by Killingly Engineering Associates, LLC, Printed 2/4/2021
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Existing Conditions

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Printed 2/4/2021

Page 2

Area Listing (all nodes)

Area (acres)	CN	Description (subcatchment-numbers)
11.986	55	Woods, Good, HSG B (1S, 2S, 3S)
2.348	77	Woods, Good, HSG D - Wetlands (1S, 2S)
14.334	59	TOTAL AREA

Existing Conditions

Prepared by Killingly Engineering Associates, LLC

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 2-year Rainfall=3.37"

Printed 2/4/2021

Page 3

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points

Runoff by SCS TR-20 method, UH=SCS

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Drainage Area 1

Runoff Area=3.314 ac 0.00% Impervious Runoff Depth>0.45"
Flow Length=270' Slope=0.1110 '/' Tc=5.6 min CN=61 Runoff=1.37 cfs 0.125 af

Subcatchment 2S: Drainage Area 2

Runoff Area=7.387 ac 0.00% Impervious Runoff Depth>0.38"
Flow Length=600' Slope=0.1240 '/' Tc=10.6 min CN=59 Runoff=1.90 cfs 0.235 af

Subcatchment 3S: Off Site West

Runoff Area=3.633 ac 0.00% Impervious Runoff Depth>0.26"
Flow Length=564' Slope=0.1250 '/' Tc=11.2 min CN=55 Runoff=0.48 cfs 0.078 af

Reach 1R: Wetland Section 1

Avg. Flow Depth=0.07' Max Vel=1.02 fps Inflow=1.37 cfs 0.125 af
n=0.050 L=240.0' S=0.0667 '/' Capacity=1,610.63 cfs Outflow=1.17 cfs 0.124 af

Reach 1R': Wetland Section 2

Avg. Flow Depth=0.06' Max Vel=4.59 fps Inflow=1.17 cfs 0.124 af
n=0.013 L=145.0' S=0.1241 '/' Capacity=2,590.64 cfs Outflow=1.16 cfs 0.124 af

Reach 2R: Peak off Site

Avg. Flow Depth=0.14' Max Vel=1.19 fps Inflow=3.01 cfs 0.359 af
n=0.050 L=640.0' S=0.0375 '/' Capacity=789.38 cfs Outflow=2.52 cfs 0.351 af

Total Runoff Area = 14.334 ac Runoff Volume = 0.437 af Average Runoff Depth = 0.37"
100.00% Pervious = 14.334 ac 0.00% Impervious = 0.000 ac

Existing Conditions

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 2-year Rainfall=3.37"
Printed 2/4/2021
Page 4

Summary for Subcatchment 1S: Drainage Area 1

Runoff = 1.37 cfs @ 12.12 hrs, Volume= 0.125 af, Depth> 0.45"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 2-year Rainfall=3.37"

Area (ac)	CN	Description
* 0.930	77	Woods, Good, HSG D - Wetlands
2.384	55	Woods, Good, HSG B
3.314	61	Weighted Average
3.314		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.6	270	0.1110	0.80		Lag/CN Method, Tc 1

Summary for Subcatchment 2S: Drainage Area 2

Runoff = 1.90 cfs @ 12.22 hrs, Volume= 0.235 af, Depth> 0.38"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 2-year Rainfall=3.37"

Area (ac)	CN	Description
* 1.418	77	Woods, Good, HSG D - Wetlands
5.969	55	Woods, Good, HSG B
7.387	59	Weighted Average
7.387		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.6	600	0.1240	0.94		Lag/CN Method, Tc-2

Summary for Subcatchment 3S: Off Site West

Runoff = 0.48 cfs @ 12.38 hrs, Volume= 0.078 af, Depth> 0.26"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 2-year Rainfall=3.37"

Area (ac)	CN	Description
3.633	55	Woods, Good, HSG B
3.633		100.00% Pervious Area

Existing Conditions

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 2-year Rainfall=3.37"
Printed 2/4/2021
Page 5

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.2	564	0.1250	0.84		Lag/CN Method, Tc-3

Summary for Reach 1R: Wetland Section 1

Inflow Area = 3.314 ac, 0.00% Impervious, Inflow Depth > 0.45" for 2-year event
Inflow = 1.37 cfs @ 12.12 hrs, Volume= 0.125 af
Outflow = 1.17 cfs @ 12.25 hrs, Volume= 0.124 af, Atten= 15%, Lag= 8.3 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Max. Velocity= 1.02 fps, Min. Travel Time= 3.9 min
Avg. Velocity = 0.55 fps, Avg. Travel Time= 7.3 min

Peak Storage= 283 cf @ 12.17 hrs
Average Depth at Peak Storage= 0.07'
Bank-Full Depth= 2.00' Flow Area= 173.3 sf, Capacity= 1,610.63 cfs

130.00' x 2.00' deep Parabolic Channel, n= 0.050 Scattered brush, heavy weeds
Length= 240.0' Slope= 0.0667 '/'
Inlet Invert= 296.00', Outlet Invert= 280.00'



Summary for Reach 1R': Wetland Section 2

Inflow Area = 3.314 ac, 0.00% Impervious, Inflow Depth > 0.45" for 2-year event
Inflow = 1.17 cfs @ 12.25 hrs, Volume= 0.124 af
Outflow = 1.16 cfs @ 12.27 hrs, Volume= 0.124 af, Atten= 1%, Lag= 0.9 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Max. Velocity= 4.59 fps, Min. Travel Time= 0.5 min
Avg. Velocity = 2.60 fps, Avg. Travel Time= 0.9 min

Peak Storage= 37 cf @ 12.26 hrs
Average Depth at Peak Storage= 0.06'
Bank-Full Depth= 2.00' Flow Area= 53.3 sf, Capacity= 2,590.64 cfs

40.00' x 2.00' deep Parabolic Channel, n= 0.013 Asphalt, smooth
Length= 145.0' Slope= 0.1241 '/'
Inlet Invert= 280.00', Outlet Invert= 262.00'

Existing Conditions

Prepared by Killingly Engineering Associates, LLC

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 2-year Rainfall=3.37"

Printed 2/4/2021

Page 6



Summary for Reach 2R: Peak off Site

Inflow Area = 10.701 ac, 0.00% Impervious, Inflow Depth > 0.40" for 2-year event
Inflow = 3.01 cfs @ 12.26 hrs, Volume= 0.359 af
Outflow = 2.52 cfs @ 12.57 hrs, Volume= 0.351 af, Atten= 16%, Lag= 18.8 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Max. Velocity= 1.19 fps, Min. Travel Time= 9.0 min

Avg. Velocity = 0.70 fps, Avg. Travel Time= 15.3 min

Peak Storage= 1,357 cf @ 12.42 hrs

Average Depth at Peak Storage= 0.14'

Bank-Full Depth= 2.00' Flow Area= 113.3 sf, Capacity= 789.38 cfs

85.00' x 2.00' deep Parabolic Channel, n= 0.050 Scattered brush, heavy weeds

Length= 640.0' Slope= 0.0375 '/'

Inlet Invert= 262.00', Outlet Invert= 238.00'



Existing Conditions

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 5-year Rainfall=4.28"
Printed 2/4/2021
Page 7

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Drainage Area 1 Runoff Area=3.314 ac 0.00% Impervious Runoff Depth>0.86"
Flow Length=270' Slope=0.1110 '/' Tc=5.6 min CN=61 Runoff=3.17 cfs 0.237 af

Subcatchment 2S: Drainage Area 2 Runoff Area=7.387 ac 0.00% Impervious Runoff Depth>0.75"
Flow Length=600' Slope=0.1240 '/' Tc=10.6 min CN=59 Runoff=4.92 cfs 0.465 af

Subcatchment 3S: Off Site West Runoff Area=3.633 ac 0.00% Impervious Runoff Depth>0.57"
Flow Length=564' Slope=0.1250 '/' Tc=11.2 min CN=55 Runoff=1.53 cfs 0.171 af

Reach 1R: Wetland Section 1 Avg. Flow Depth=0.11' Max Vel=1.33 fps Inflow=3.17 cfs 0.237 af
n=0.050 L=240.0' S=0.0667 '/' Capacity=1,610.63 cfs Outflow=2.90 cfs 0.236 af

Reach 1R': Wetland Section 2 Avg. Flow Depth=0.09' Max Vel=6.06 fps Inflow=2.90 cfs 0.236 af
n=0.013 L=145.0' S=0.1241 '/' Capacity=2,590.64 cfs Outflow=2.87 cfs 0.236 af

Reach 2R: Peak off Site Avg. Flow Depth=0.22' Max Vel=1.59 fps Inflow=7.74 cfs 0.700 af
n=0.050 L=640.0' S=0.0375 '/' Capacity=789.38 cfs Outflow=6.48 cfs 0.690 af

Total Runoff Area = 14.334 ac Runoff Volume = 0.873 af Average Runoff Depth = 0.73"
100.00% Pervious = 14.334 ac 0.00% Impervious = 0.000 ac

Existing Conditions

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 5-year Rainfall=4.28"
Printed 2/4/2021
Page 8

Summary for Subcatchment 1S: Drainage Area 1

Runoff = 3.17 cfs @ 12.10 hrs, Volume= 0.237 af, Depth> 0.86"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 5-year Rainfall=4.28"

Area (ac)	CN	Description
* 0.930	77	Woods, Good, HSG D - Wetlands
2.384	55	Woods, Good, HSG B
3.314	61	Weighted Average
3.314		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.6	270	0.1110	0.80		Lag/CN Method, Tc 1

Summary for Subcatchment 2S: Drainage Area 2

Runoff = 4.92 cfs @ 12.18 hrs, Volume= 0.465 af, Depth> 0.75"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 5-year Rainfall=4.28"

Area (ac)	CN	Description
* 1.418	77	Woods, Good, HSG D - Wetlands
5.969	55	Woods, Good, HSG B
7.387	59	Weighted Average
7.387		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.6	600	0.1240	0.94		Lag/CN Method, Tc-2

Summary for Subcatchment 3S: Off Site West

Runoff = 1.53 cfs @ 12.21 hrs, Volume= 0.171 af, Depth> 0.57"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 5-year Rainfall=4.28"

Area (ac)	CN	Description
3.633	55	Woods, Good, HSG B
3.633		100.00% Pervious Area

Existing Conditions

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 5-year Rainfall=4.28"
Printed 2/4/2021
Page 9

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.2	564	0.1250	0.84		Lag/CN Method, Tc-3


Summary for Reach 1R: Wetland Section 1

Inflow Area = 3.314 ac, 0.00% Impervious, Inflow Depth > 0.86" for 5-year event
Inflow = 3.17 cfs @ 12.10 hrs, Volume= 0.237 af
Outflow = 2.90 cfs @ 12.20 hrs, Volume= 0.236 af, Atten= 9%, Lag= 5.5 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Max. Velocity= 1.33 fps, Min. Travel Time= 3.0 min
Avg. Velocity = 0.64 fps, Avg. Travel Time= 6.2 min

Peak Storage= 521 cf @ 12.15 hrs
Average Depth at Peak Storage= 0.11'
Bank-Full Depth= 2.00' Flow Area= 173.3 sf, Capacity= 1,610.63 cfs

130.00' x 2.00' deep Parabolic Channel, n= 0.050 Scattered brush, heavy weeds
Length= 240.0' Slope= 0.0667 '/
Inlet Invert= 296.00', Outlet Invert= 280.00'



Summary for Reach 1R': Wetland Section 2

Inflow Area = 3.314 ac, 0.00% Impervious, Inflow Depth > 0.85" for 5-year event
Inflow = 2.90 cfs @ 12.20 hrs, Volume= 0.236 af
Outflow = 2.87 cfs @ 12.21 hrs, Volume= 0.236 af, Atten= 1%, Lag= 0.7 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Max. Velocity= 6.06 fps, Min. Travel Time= 0.4 min
Avg. Velocity = 2.94 fps, Avg. Travel Time= 0.8 min

Peak Storage= 70 cf @ 12.20 hrs
Average Depth at Peak Storage= 0.09'
Bank-Full Depth= 2.00' Flow Area= 53.3 sf, Capacity= 2,590.64 cfs

40.00' x 2.00' deep Parabolic Channel, n= 0.013 Asphalt, smooth
Length= 145.0' Slope= 0.1241 '/
Inlet Invert= 280.00', Outlet Invert= 262.00'

Existing Conditions


Prepared by Killingly Engineering Associates, LLC

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 5-year Rainfall=4.28"

Printed 2/4/2021

Page 10



Summary for Reach 2R: Peak off Site

Inflow Area = 10.701 ac, 0.00% Impervious, Inflow Depth > 0.79" for 5-year event
Inflow = 7.74 cfs @ 12.19 hrs, Volume= 0.700 af
Outflow = 6.48 cfs @ 12.41 hrs, Volume= 0.690 af, Atten= 16%, Lag= 12.7 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Max. Velocity= 1.59 fps, Min. Travel Time= 6.7 min

Avg. Velocity= 0.82 fps, Avg. Travel Time= 13.0 min

Peak Storage= 2,615 cf @ 12.29 hrs

Average Depth at Peak Storage= 0.22'

Bank-Full Depth= 2.00' Flow Area= 113.3 sf, Capacity= 789.38 cfs

85.00' x 2.00' deep Parabolic Channel, n= 0.050 Scattered brush, heavy weeds

Length= 640.0' Slope= 0.0375 '/'

Inlet Invert= 262.00', Outlet Invert= 238.00'



Existing Conditions

Prepared by Killingly Engineering Associates, LLC

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 10-year Rainfall=5.04"

Printed 2/4/2021

Page 11

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points

Runoff by SCS TR-20 method, UH=SCS

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Drainage Area 1

Runoff Area=3.314 ac 0.00% Impervious Runoff Depth>1.26"
Flow Length=270' Slope=0.1110 '/' Tc=5.6 min CN=61 Runoff=4.92 cfs 0.348 af

Subcatchment 2S: Drainage Area 2

Runoff Area=7.387 ac 0.00% Impervious Runoff Depth>1.13"
Flow Length=600' Slope=0.1240 '/' Tc=10.6 min CN=59 Runoff=8.13 cfs 0.696 af

Subcatchment 3S: Off Site West

Runoff Area=3.633 ac 0.00% Impervious Runoff Depth>0.89"
Flow Length=564' Slope=0.1250 '/' Tc=11.2 min CN=55 Runoff=2.81 cfs 0.269 af

Reach 1R: Wetland Section 1

Avg. Flow Depth=0.13' Max Vel=1.53 fps Inflow=4.92 cfs 0.348 af
n=0.050 L=240.0' S=0.0667 '/' Capacity=1,610.63 cfs Outflow=4.49 cfs 0.347 af

Reach 1R': Wetland Section 2

Avg. Flow Depth=0.11' Max Vel=6.89 fps Inflow=4.49 cfs 0.347 af
n=0.013 L=145.0' S=0.1241 '/' Capacity=2,590.64 cfs Outflow=4.46 cfs 0.346 af

Reach 2R: Peak off Site

Avg. Flow Depth=0.28' Max Vel=1.87 fps Inflow=12.42 cfs 1.042 af
n=0.050 L=640.0' S=0.0375 '/' Capacity=789.38 cfs Outflow=10.87 cfs 1.030 af

Total Runoff Area = 14.334 ac Runoff Volume = 1.313 af Average Runoff Depth = 1.10"
100.00% Pervious = 14.334 ac 0.00% Impervious = 0.000 ac

Existing Conditions

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 10-year Rainfall=5.04"
Printed 2/4/2021
Page 12

Summary for Subcatchment 1S: Drainage Area 1

Runoff = 4.92 cfs @ 12.10 hrs, Volume= 0.348 af, Depth> 1.26"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 10-year Rainfall=5.04"

Area (ac)	CN	Description
* 0.930	77	Woods, Good, HSG D - Wetlands
2.384	55	Woods, Good, HSG B
3.314	61	Weighted Average
3.314		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.6	270	0.1110	0.80		Lag/CN Method, Tc 1

Summary for Subcatchment 2S: Drainage Area 2

Runoff = 8.13 cfs @ 12.17 hrs, Volume= 0.696 af, Depth> 1.13"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 10-year Rainfall=5.04"

Area (ac)	CN	Description
* 1.418	77	Woods, Good, HSG D - Wetlands
5.969	55	Woods, Good, HSG B
7.387	59	Weighted Average
7.387		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.6	600	0.1240	0.94		Lag/CN Method, Tc-2

Summary for Subcatchment 3S: Off Site West

Runoff = 2.81 cfs @ 12.19 hrs, Volume= 0.269 af, Depth> 0.89"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 10-year Rainfall=5.04"

Area (ac)	CN	Description
3.633	55	Woods, Good, HSG B
3.633		100.00% Pervious Area

Existing Conditions

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 10-year Rainfall=5.04"
Printed 2/4/2021
Page 13

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.2	564	0.1250	0.84		Lag/CN Method, Tc-3

Summary for Reach 1R: Wetland Section 1

Inflow Area = 3.314 ac, 0.00% Impervious, Inflow Depth > 1.26" for 10-year event
Inflow = 4.92 cfs @ 12.10 hrs, Volume= 0.348 af
Outflow = 4.49 cfs @ 12.18 hrs, Volume= 0.347 af, Atten= 9%, Lag= 4.7 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Max. Velocity= 1.53 fps, Min. Travel Time= 2.6 min
Avg. Velocity= 0.70 fps, Avg. Travel Time= 5.7 min

Peak Storage= 714 cf @ 12.13 hrs
Average Depth at Peak Storage= 0.13'
Bank-Full Depth= 2.00' Flow Area= 173.3 sf, Capacity= 1,610.63 cfs

130.00' x 2.00' deep Parabolic Channel, n= 0.050 Scattered brush, heavy weeds
Length= 240.0' Slope= 0.0667 '/'
Inlet Invert= 296.00', Outlet Invert= 280.00'



Summary for Reach 1R': Wetland Section 2

Inflow Area = 3.314 ac, 0.00% Impervious, Inflow Depth > 1.26" for 10-year event
Inflow = 4.49 cfs @ 12.18 hrs, Volume= 0.347 af
Outflow = 4.46 cfs @ 12.19 hrs, Volume= 0.346 af, Atten= 1%, Lag= 0.8 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Max. Velocity= 6.89 fps, Min. Travel Time= 0.4 min
Avg. Velocity= 3.21 fps, Avg. Travel Time= 0.8 min

Peak Storage= 94 cf @ 12.18 hrs
Average Depth at Peak Storage= 0.11'
Bank-Full Depth= 2.00' Flow Area= 53.3 sf, Capacity= 2,590.64 cfs

40.00' x 2.00' deep Parabolic Channel, n= 0.013 Asphalt, smooth
Length= 145.0' Slope= 0.1241 '/'
Inlet Invert= 280.00', Outlet Invert= 262.00'

Existing Conditions


Prepared by Killingly Engineering Associates, LLC

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 10-year Rainfall=5.04"

Printed 2/4/2021

Page 14



Summary for Reach 2R: Peak off Site

Inflow Area = 10.701 ac, 0.00% Impervious, Inflow Depth > 1.17" for 10-year event
Inflow = 12.42 cfs @ 12.18 hrs, Volume= 1.042 af
Outflow = 10.87 cfs @ 12.35 hrs, Volume= 1.030 af, Atten= 12%, Lag= 10.5 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Max. Velocity= 1.87 fps, Min. Travel Time= 5.7 min

Avg. Velocity = 0.89 fps, Avg. Travel Time= 12.0 min

Peak Storage= 3,743 cf @ 12.25 hrs

Average Depth at Peak Storage= 0.28'

Bank-Full Depth= 2.00' Flow Area= 113.3 sf, Capacity= 789.38 cfs

85.00' x 2.00' deep Parabolic Channel, n= 0.050 Scattered brush, heavy weeds

Length= 640.0' Slope= 0.0375 '/'

Inlet Invert= 262.00', Outlet Invert= 238.00'



Existing Conditions

Prepared by Killingly Engineering Associates, LLC

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 25-year Rainfall=6.08"

Printed 2/4/2021

Page 15

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points

Runoff by SCS TR-20 method, UH=SCS

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Drainage Area 1

Runoff Area=3.314 ac 0.00% Impervious Runoff Depth>1.88"
Flow Length=270' Slope=0.1110 '/' Tc=5.6 min CN=61 Runoff=7.60 cfs 0.520 af

Subcatchment 2S: Drainage Area 2

Runoff Area=7.387 ac 0.00% Impervious Runoff Depth>1.72"
Flow Length=600' Slope=0.1240 '/' Tc=10.6 min CN=59 Runoff=13.01 cfs 1.057 af

Subcatchment 3S: Off Site West

Runoff Area=3.633 ac 0.00% Impervious Runoff Depth>1.41"
Flow Length=564' Slope=0.1250 '/' Tc=11.2 min CN=55 Runoff=4.88 cfs 0.426 af

Reach 1R: Wetland Section 1

Avg. Flow Depth=0.16' Max Vel=1.75 fps Inflow=7.60 cfs 0.520 af
n=0.050 L=240.0' S=0.0667 '/' Capacity=1,610.63 cfs Outflow=7.07 cfs 0.518 af

Reach 1R': Wetland Section 2

Avg. Flow Depth=0.13' Max Vel=7.91 fps Inflow=7.07 cfs 0.518 af
n=0.013 L=145.0' S=0.1241 '/' Capacity=2,590.64 cfs Outflow=6.97 cfs 0.517 af

Reach 2R: Peak off Site

Avg. Flow Depth=0.35' Max Vel=2.16 fps Inflow=19.96 cfs 1.574 af
n=0.050 L=640.0' S=0.0375 '/' Capacity=789.38 cfs Outflow=17.63 cfs 1.559 af

Total Runoff Area = 14.334 ac Runoff Volume = 2.003 af Average Runoff Depth = 1.68"
100.00% Pervious = 14.334 ac 0.00% Impervious = 0.000 ac

Existing Conditions

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 25-year Rainfall=6.08"
Printed 2/4/2021
Page 16

Summary for Subcatchment 1S: Drainage Area 1

Runoff = 7.60 cfs @ 12.09 hrs, Volume= 0.520 af, Depth> 1.88"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 25-year Rainfall=6.08"

Area (ac)	CN	Description
* 0.930	77	Woods, Good, HSG D - Wetlands
2.384	55	Woods, Good, HSG B
3.314	61	Weighted Average
3.314		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.6	270	0.1110	0.80		Lag/CN Method, Tc 1

Summary for Subcatchment 2S: Drainage Area 2

Runoff = 13.01 cfs @ 12.16 hrs, Volume= 1.057 af, Depth> 1.72"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 25-year Rainfall=6.08"

Area (ac)	CN	Description
* 1.418	77	Woods, Good, HSG D - Wetlands
5.969	55	Woods, Good, HSG B
7.387	59	Weighted Average
7.387		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.6	600	0.1240	0.94		Lag/CN Method, Tc-2

Summary for Subcatchment 3S: Off Site West

Runoff = 4.88 cfs @ 12.18 hrs, Volume= 0.426 af, Depth> 1.41"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 25-year Rainfall=6.08"

Area (ac)	CN	Description
3.633	55	Woods, Good, HSG B
3.633		100.00% Pervious Area

Existing Conditions

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 25-year Rainfall=6.08"
Printed 2/4/2021
Page 17

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.2	564	0.1250	0.84		Lag/CN Method, Tc-3

Summary for Reach 1R: Wetland Section 1

Inflow Area = 3.314 ac, 0.00% Impervious, Inflow Depth > 1.88" for 25-year event
Inflow = 7.60 cfs @ 12.09 hrs, Volume= 0.520 af
Outflow = 7.07 cfs @ 12.16 hrs, Volume= 0.518 af, Atten= 7%, Lag= 4.1 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Max. Velocity= 1.75 fps, Min. Travel Time= 2.3 min
Avg. Velocity = 0.76 fps, Avg. Travel Time= 5.3 min

Peak Storage= 985 cf @ 12.12 hrs
Average Depth at Peak Storage= 0.16'
Bank-Full Depth= 2.00' Flow Area= 173.3 sf, Capacity= 1,610.63 cfs

130.00' x 2.00' deep Parabolic Channel, n= 0.050 Scattered brush, heavy weeds
Length= 240.0' Slope= 0.0667 '/'
Inlet Invert= 296.00', Outlet Invert= 280.00'



Summary for Reach 1R': Wetland Section 2

Inflow Area = 3.314 ac, 0.00% Impervious, Inflow Depth > 1.87" for 25-year event
Inflow = 7.07 cfs @ 12.16 hrs, Volume= 0.518 af
Outflow = 6.97 cfs @ 12.17 hrs, Volume= 0.517 af, Atten= 1%, Lag= 0.5 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Max. Velocity= 7.91 fps, Min. Travel Time= 0.3 min
Avg. Velocity = 3.49 fps, Avg. Travel Time= 0.7 min

Peak Storage= 129 cf @ 12.17 hrs
Average Depth at Peak Storage= 0.13'
Bank-Full Depth= 2.00' Flow Area= 53.3 sf, Capacity= 2,590.64 cfs

40.00' x 2.00' deep Parabolic Channel, n= 0.013 Asphalt, smooth
Length= 145.0' Slope= 0.1241 '/'
Inlet Invert= 280.00', Outlet Invert= 262.00'

Existing Conditions

Prepared by Killingly Engineering Associates, LLC

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 25-year Rainfall=6.08"

Printed 2/4/2021

Page 18



Summary for Reach 2R: Peak off Site

Inflow Area = 10.701 ac, 0.00% Impervious, Inflow Depth > 1.77" for 25-year event
Inflow = 19.96 cfs @ 12.17 hrs, Volume= 1.574 af
Outflow = 17.63 cfs @ 12.31 hrs, Volume= 1.559 af, Atten= 12%, Lag= 8.9 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Max. Velocity= 2.16 fps, Min. Travel Time= 4.9 min

Avg. Velocity = 0.97 fps, Avg. Travel Time= 11.0 min

Peak Storage= 5,237 cf @ 12.23 hrs

Average Depth at Peak Storage= 0.35'

Bank-Full Depth= 2.00' Flow Area= 113.3 sf, Capacity= 789.38 cfs

85.00' x 2.00' deep Parabolic Channel, n= 0.050 Scattered brush, heavy weeds

Length= 640.0' Slope= 0.0375 '/'

Inlet Invert= 262.00', Outlet Invert= 238.00'



Existing Conditions

Prepared by Killingly Engineering Associates, LLC

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 50-year Rainfall=6.85"

Printed 2/4/2021

Page 19

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points

Runoff by SCS TR-20 method, UH=SCS

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Drainage Area 1

Runoff Area=3.314 ac 0.00% Impervious Runoff Depth>2.38"
Flow Length=270' Slope=0.1110 '/' Tc=5.6 min CN=61 Runoff=9.74 cfs 0.658 af

Subcatchment 2S: Drainage Area 2

Runoff Area=7.387 ac 0.00% Impervious Runoff Depth>2.19"
Flow Length=600' Slope=0.1240 '/' Tc=10.6 min CN=59 Runoff=16.95 cfs 1.351 af

Subcatchment 3S: Off Site West

Runoff Area=3.633 ac 0.00% Impervious Runoff Depth>1.84"
Flow Length=564' Slope=0.1250 '/' Tc=11.2 min CN=55 Runoff=6.67 cfs 0.557 af

Reach 1R: Wetland Section 1

Avg. Flow Depth=0.19' Max Vel=1.90 fps Inflow=9.74 cfs 0.658 af
n=0.050 L=240.0' S=0.0667 '/' Capacity=1,610.63 cfs Outflow=9.08 cfs 0.655 af

Reach 1R': Wetland Section 2

Avg. Flow Depth=0.15' Max Vel=8.56 fps Inflow=9.08 cfs 0.655 af
n=0.013 L=145.0' S=0.1241 '/' Capacity=2,590.64 cfs Outflow=8.97 cfs 0.655 af

Reach 2R: Peak off Site

Avg. Flow Depth=0.40' Max Vel=2.36 fps Inflow=25.91 cfs 2.006 af
n=0.050 L=640.0' S=0.0375 '/' Capacity=789.38 cfs Outflow=23.03 cfs 1.989 af

Total Runoff Area = 14.334 ac Runoff Volume = 2.565 af Average Runoff Depth = 2.15"
100.00% Pervious = 14.334 ac 0.00% Impervious = 0.000 ac

Existing Conditions

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 50-year Rainfall=6.85"
Printed 2/4/2021
Page 20

Summary for Subcatchment 1S: Drainage Area 1

Runoff = 9.74 cfs @ 12.09 hrs, Volume= 0.658 af, Depth> 2.38"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 50-year Rainfall=6.85"

Area (ac)	CN	Description
* 0.930	77	Woods, Good, HSG D - Wetlands
2.384	55	Woods, Good, HSG B
3.314	61	Weighted Average
3.314		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.6	270	0.1110	0.80		Lag/CN Method, Tc 1

Summary for Subcatchment 2S: Drainage Area 2

Runoff = 16.95 cfs @ 12.16 hrs, Volume= 1.351 af, Depth> 2.19"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 50-year Rainfall=6.85"

Area (ac)	CN	Description
* 1.418	77	Woods, Good, HSG D - Wetlands
5.969	55	Woods, Good, HSG B
7.387	59	Weighted Average
7.387		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.6	600	0.1240	0.94		Lag/CN Method, Tc-2

Summary for Subcatchment 3S: Off Site West

Runoff = 6.67 cfs @ 12.17 hrs, Volume= 0.557 af, Depth> 1.84"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 50-year Rainfall=6.85"

Area (ac)	CN	Description
3.633	55	Woods, Good, HSG B
3.633		100.00% Pervious Area

Existing Conditions

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 50-year Rainfall=6.85"
Printed 2/4/2021
Page 21

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.2	564	0.1250	0.84		Lag/CN Method, Tc-3

Summary for Reach 1R: Wetland Section 1

Inflow Area = 3.314 ac, 0.00% Impervious, Inflow Depth > 2.38" for 50-year event
Inflow = 9.74 cfs @ 12.09 hrs, Volume= 0.658 af
Outflow = 9.08 cfs @ 12.16 hrs, Volume= 0.655 af, Atten= 7%, Lag= 3.8 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Max. Velocity= 1.90 fps, Min. Travel Time= 2.1 min
Avg. Velocity = 0.79 fps, Avg. Travel Time= 5.0 min

Peak Storage= 1,176 cf @ 12.12 hrs
Average Depth at Peak Storage= 0.19'
Bank-Full Depth= 2.00' Flow Area= 173.3 sf, Capacity= 1,610.63 cfs

130.00' x 2.00' deep Parabolic Channel, n= 0.050 Scattered brush, heavy weeds
Length= 240.0' Slope= 0.0667 '/'
Inlet Invert= 296.00', Outlet Invert= 280.00'



Summary for Reach 1R': Wetland Section 2

Inflow Area = 3.314 ac, 0.00% Impervious, Inflow Depth > 2.37" for 50-year event
Inflow = 9.08 cfs @ 12.16 hrs, Volume= 0.655 af
Outflow = 8.97 cfs @ 12.16 hrs, Volume= 0.655 af, Atten= 1%, Lag= 0.4 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Max. Velocity= 8.56 fps, Min. Travel Time= 0.3 min
Avg. Velocity = 3.66 fps, Avg. Travel Time= 0.7 min

Peak Storage= 154 cf @ 12.16 hrs
Average Depth at Peak Storage= 0.15'
Bank-Full Depth= 2.00' Flow Area= 53.3 sf, Capacity= 2,590.64 cfs

40.00' x 2.00' deep Parabolic Channel, n= 0.013 Asphalt, smooth
Length= 145.0' Slope= 0.1241 '/'
Inlet Invert= 280.00', Outlet Invert= 262.00'

Existing Conditions

Prepared by Killingly Engineering Associates, LLC

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock

Type III 24-hr 50-year Rainfall=6.85"

Printed 2/4/2021

Page 22



Summary for Reach 2R: Peak off Site

Inflow Area = 10.701 ac, 0.00% Impervious, Inflow Depth > 2.25" for 50-year event
Inflow = 25.91 cfs @ 12.16 hrs, Volume= 2.006 af
Outflow = 23.03 cfs @ 12.30 hrs, Volume= 1.989 af, Atten= 11%, Lag= 8.2 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Max. Velocity= 2.36 fps, Min. Travel Time= 4.5 min

Avg. Velocity= 1.02 fps, Avg. Travel Time= 10.5 min

Peak Storage= 6,367 cf @ 12.22 hrs

Average Depth at Peak Storage= 0.40'

Bank-Full Depth= 2.00' Flow Area= 113.3 sf, Capacity= 789.38 cfs

85.00' x 2.00' deep Parabolic Channel, n= 0.050 Scattered brush, heavy weeds

Length= 640.0' Slope= 0.0375 '/'

Inlet Invert= 262.00', Outlet Invert= 238.00'



Existing Conditions

Prepared by Killingly Engineering Associates, LLC

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 100-year Rainfall=7.68"

Printed 2/4/2021

Page 23

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points

Runoff by SCS TR-20 method, UH=SCS

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Drainage Area 1

Runoff Area=3.314 ac 0.00% Impervious Runoff Depth>2.95"
Flow Length=270' Slope=0.1110 '/' Tc=5.6 min CN=61 Runoff=12.15 cfs 0.815 af

Subcatchment 2S: Drainage Area 2

Runoff Area=7.387 ac 0.00% Impervious Runoff Depth>2.74"
Flow Length=600' Slope=0.1240 '/' Tc=10.6 min CN=59 Runoff=21.44 cfs 1.688 af

Subcatchment 3S: Off Site West

Runoff Area=3.633 ac 0.00% Impervious Runoff Depth>2.34"
Flow Length=564' Slope=0.1250 '/' Tc=11.2 min CN=55 Runoff=8.67 cfs 0.708 af

Reach 1R: Wetland Section 1

Avg. Flow Depth=0.21' Max Vel=2.04 fps Inflow=12.15 cfs 0.815 af
n=0.050 L=240.0' S=0.0667 '/' Capacity=1,610.63 cfs Outflow=11.35 cfs 0.813 af

Reach 1R': Wetland Section 2

Avg. Flow Depth=0.16' Max Vel=9.17 fps Inflow=11.35 cfs 0.813 af
n=0.013 L=145.0' S=0.1241 '/' Capacity=2,590.64 cfs Outflow=11.23 cfs 0.812 af

Reach 2R: Peak off Site

Avg. Flow Depth=0.44' Max Vel=2.54 fps Inflow=32.66 cfs 2.500 af
n=0.050 L=640.0' S=0.0375 '/' Capacity=789.38 cfs Outflow=29.21 cfs 2.481 af

Total Runoff Area = 14.334 ac Runoff Volume = 3.211 af Average Runoff Depth = 2.69"
100.00% Pervious = 14.334 ac 0.00% Impervious = 0.000 ac

Existing Conditions

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 100-year Rainfall=7.68"
Printed 2/4/2021
Page 24

Summary for Subcatchment 1S: Drainage Area 1

Runoff = 12.15 cfs @ 12.09 hrs, Volume= 0.815 af, Depth> 2.95"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 100-year Rainfall=7.68"

Area (ac)	CN	Description
* 0.930	77	Woods, Good, HSG D - Wetlands
2.384	55	Woods, Good, HSG B
3.314	61	Weighted Average
3.314		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.6	270	0.1110	0.80		Lag/CN Method, Tc 1

Summary for Subcatchment 2S: Drainage Area 2

Runoff = 21.44 cfs @ 12.16 hrs, Volume= 1.688 af, Depth> 2.74"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 100-year Rainfall=7.68"

Area (ac)	CN	Description
* 1.418	77	Woods, Good, HSG D - Wetlands
5.969	55	Woods, Good, HSG B
7.387	59	Weighted Average
7.387		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.6	600	0.1240	0.94		Lag/CN Method, Tc-2

Summary for Subcatchment 3S: Off Site West

Runoff = 8.67 cfs @ 12.17 hrs, Volume= 0.708 af, Depth> 2.34"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 100-year Rainfall=7.68"

Area (ac)	CN	Description
3.633	55	Woods, Good, HSG B
3.633		100.00% Pervious Area

Existing Conditions

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 100-year Rainfall=7.68"
Printed 2/4/2021
Page 25

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.2	564	0.1250	0.84		Lag/CN Method, Tc-3

Summary for Reach 1R: Wetland Section 1

Inflow Area = 3.314 ac, 0.00% Impervious, Inflow Depth > 2.95" for 100-year event
Inflow = 12.15 cfs @ 12.09 hrs, Volume= 0.815 af
Outflow = 11.35 cfs @ 12.15 hrs, Volume= 0.813 af, Atten= 7%, Lag= 3.6 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Max. Velocity= 2.04 fps, Min. Travel Time= 2.0 min
Avg. Velocity = 0.83 fps, Avg. Travel Time= 4.8 min

Peak Storage= 1,378 cf @ 12.11 hrs
Average Depth at Peak Storage= 0.21'
Bank-Full Depth= 2.00' Flow Area= 173.3 sf, Capacity= 1,610.63 cfs

130.00' x 2.00' deep Parabolic Channel, n= 0.050 Scattered brush, heavy weeds
Length= 240.0' Slope= 0.0667 '/'
Inlet Invert= 296.00', Outlet Invert= 280.00'



Summary for Reach 1R': Wetland Section 2

Inflow Area = 3.314 ac, 0.00% Impervious, Inflow Depth > 2.94" for 100-year event
Inflow = 11.35 cfs @ 12.15 hrs, Volume= 0.813 af
Outflow = 11.23 cfs @ 12.16 hrs, Volume= 0.812 af, Atten= 1%, Lag= 0.4 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Max. Velocity= 9.17 fps, Min. Travel Time= 0.3 min
Avg. Velocity = 3.82 fps, Avg. Travel Time= 0.6 min

Peak Storage= 180 cf @ 12.16 hrs
Average Depth at Peak Storage= 0.16'
Bank-Full Depth= 2.00' Flow Area= 53.3 sf, Capacity= 2,590.64 cfs

40.00' x 2.00' deep Parabolic Channel, n= 0.013 Asphalt, smooth
Length= 145.0' Slope= 0.1241 '/'
Inlet Invert= 280.00', Outlet Invert= 262.00'

Existing Conditions

Prepared by Killingly Engineering Associates, LLC

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 100-year Rainfall=7.68"

Printed 2/4/2021

Page 26



Summary for Reach 2R: Peak off Site

Inflow Area = 10.701 ac, 0.00% Impervious, Inflow Depth > 2.80" for 100-year event
Inflow = 32.66 cfs @ 12.16 hrs, Volume= 2.500 af
Outflow = 29.21 cfs @ 12.28 hrs, Volume= 2.481 af, Atten= 11%, Lag= 7.5 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Max. Velocity= 2.54 fps, Min. Travel Time= 4.2 min

Avg. Velocity= 1.07 fps, Avg. Travel Time= 10.0 min

Peak Storage= 7,527 cf @ 12.21 hrs

Average Depth at Peak Storage= 0.44'

Bank-Full Depth= 2.00' Flow Area= 113.3 sf, Capacity= 789.38 cfs




85.00' x 2.00' deep Parabolic Channel, n= 0.050 Scattered brush, heavy weeds

Length= 640.0' Slope= 0.0375 '/'

Inlet Invert= 262.00', Outlet Invert= 238.00'



PROPOSED CONDITIONS



Routing Diagram for Proposed Conditions
 Prepared by Killingly Engineering Associates, LLC, Printed 2/4/2021
 HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 2

Area Listing (all nodes)

Area (acres)	CN	Description (subcatchment-numbers)
0.523	55	Woods, Good, HSG B (4S, 6S)
0.772	58	>75% Grass cover, Good, HSG B (8S)
1.786	61	>75% Grass cover, Good, HSG B (1S, 3S, 4S, 5S, 6S)
0.161	74	>75% Grass cover, Good, HSG B/D (2S, 7S)
0.693	98	Paved parking & roof HSG A (4S)
0.095	98	Paved parking, HSG B (1S)
0.196	98	Paved parking/roof (3S)
0.309	98	Paved surfaces & roof (5S)
0.483	98	Pavement/Roofs, HSG B (6S)
0.282	98	Roof & Pavement (7S)
0.161	98	Roof/pavement (2S)
5.461	75	TOTAL AREA

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 2-year Rainfall=3.37"
Printed 2/4/2021
Page 3

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Drainage Area 1 Runoff Area=8,570 sf 48.07% Impervious Runoff Depth>1.35"
Flow Length=111' Slope=0.0710 '/' Tc=9.1 min CN=79 Runoff=0.29 cfs 0.022 af

Subcatchment 2S: Drainage Area 2 Runoff Area=13,320 sf 52.80% Impervious Runoff Depth>1.94"
Flow Length=125' Slope=0.0100 '/' Tc=1.0 min CN=87 Runoff=0.82 cfs 0.049 af

Subcatchment 3S: Drainage Area 3 Runoff Area=24,738 sf 34.48% Impervious Runoff Depth>1.05"
Flow Length=265' Tc=5.7 min CN=74 Runoff=0.73 cfs 0.050 af

Subcatchment 4S: Drainage Area 4 Runoff Area=69,700 sf 43.33% Impervious Runoff Depth>1.11"
Flow Length=130' Slope=0.0100 '/' Tc=1.9 min CN=75 Runoff=2.43 cfs 0.148 af

Subcatchment 5S: Drainage Area 5 Runoff Area=27,597 sf 48.74% Impervious Runoff Depth>1.36"
Flow Length=180' Slope=0.0500 '/' Tc=1.3 min CN=79 Runoff=1.18 cfs 0.072 af

Subcatchment 6S: Drainage Area 6 Runoff Area=47,315 sf 44.44% Impervious Runoff Depth>1.23"
Flow Length=180' Slope=0.0500 '/' Tc=3.9 min CN=77 Runoff=1.75 cfs 0.111 af

Subcatchment 7S: Drainage Area 7 Runoff Area=13,011 sf 94.50% Impervious Runoff Depth>2.84"
Flow Length=175' Slope=0.0580 '/' Tc=1.2 min CN=97 Runoff=1.07 cfs 0.071 af

Subcatchment 8S: Overland to Swales Runoff Area=33,644 sf 0.00% Impervious Runoff Depth>0.35"
Flow Length=130' Slope=0.1240 '/' Tc=8.3 min CN=58 Runoff=0.18 cfs 0.022 af

Reach 3R: Riprap Swale Avg. Flow Depth=0.04' Max Vel=1.13 fps Inflow=0.18 cfs 0.022 af
n=0.045 L=210.0' S=0.0952 '/' Capacity=48.58 cfs Outflow=0.17 cfs 0.022 af

Reach 4R: Grass swale to basin Avg. Flow Depth=0.04' Max Vel=1.02 fps Inflow=0.17 cfs 0.022 af
n=0.035 L=205.0' S=0.0439 '/' Capacity=42.41 cfs Outflow=0.17 cfs 0.022 af

Reach 9R: Peak off Site Inflow=2.64 cfs 0.352 af
Outflow=2.64 cfs 0.352 af

Pond 1P: CB_1-2 Peak Elev=311.75' Inflow=0.29 cfs 0.022 af
15.0" Round Culvert n=0.012 L=128.7' S=0.0975 '/' Outflow=0.29 cfs 0.022 af

Pond 2P: CB_3-4 Peak Elev=299.32' Inflow=0.97 cfs 0.072 af
15.0" Round Culvert n=0.012 L=131.1' S=0.0934 '/' Outflow=0.97 cfs 0.072 af

Pond 3P: CB_5-6 Peak Elev=287.11' Inflow=1.59 cfs 0.121 af
15.0" Round Culvert n=0.012 L=168.9' S=0.0823 '/' Outflow=1.59 cfs 0.121 af

Pond 4P: CB_7-8 Peak Elev=273.58' Inflow=4.00 cfs 0.269 af
15.0" Round Culvert n=0.012 L=128.2' S=0.0686 '/' Outflow=4.00 cfs 0.269 af

Pond 5P: CB-9 Peak Elev=264.99' Inflow=5.16 cfs 0.341 af
15.0" Round Culvert n=0.012 L=100.6' S=0.1044 '/' Outflow=5.16 cfs 0.341 af

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 2-year Rainfall=3.37"

Printed 2/4/2021

Page 4

Pond 6P: CB_10-11

Peak Elev=254.39' Inflow=6.86 cfs 0.452 af
18.0" Round Culvert n=0.012 L=172.0' S=0.0459 '/ Outflow=6.86 cfs 0.452 af

Pond 7P: CB_12-13

Peak Elev=246.60' Inflow=7.84 cfs 0.523 af
18.0" Round Culvert n=0.012 L=36.0' S=0.0278 '/ Outflow=7.84 cfs 0.523 af

Pond 10P: Stormwater Basin

Peak Elev=243.69' Storage=9,216 cf Inflow=7.84 cfs 0.545 af
Discarded=0.69 cfs 0.447 af Primary=0.41 cfs 0.076 af Secondary=0.00 cfs 0.000 af Outflow=1.10 cfs 0.523 af

Link 1L:

2-year Outflow Imported from Proposed Wetlands Drainage~Reach 2R.hce Inflow=2.24 cfs 0.276 af
Area= 5.540 ac 1.13% Imperv. Primary=2.24 cfs 0.276 af

Total Runoff Area = 5.461 ac Runoff Volume = 0.545 af Average Runoff Depth = 1.20"
59.37% Pervious = 3.242 ac 40.63% Impervious = 2.219 ac

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC
 HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
 Type III 24-hr 2-year Rainfall=3.37"
 Printed 2/4/2021
 Page 5

Summary for Subcatchment 1S: Drainage Area 1

Runoff = 0.29 cfs @ 12.14 hrs, Volume= 0.022 af, Depth> 1.35"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 2-year Rainfall=3.37"

Area (sf)	CN	Description
4,120	98	Paved parking, HSG B
4,450	61	>75% Grass cover, Good, HSG B
8,570	79	Weighted Average
4,450		51.93% Pervious Area
4,120		48.07% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.1	111	0.0710	0.20		Sheet Flow, Tc-1 Grass: Dense n= 0.240 P2= 3.37"

Summary for Subcatchment 2S: Drainage Area 2

Runoff = 0.82 cfs @ 12.02 hrs, Volume= 0.049 af, Depth> 1.94"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 2-year Rainfall=3.37"

Area (sf)	CN	Description
* 6,287	74	>75% Grass cover, Good, HSG B/D
* 7,033	98	Roof/pavement
13,320	87	Weighted Average
6,287		47.20% Pervious Area
7,033		52.80% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.0	125	0.0100	2.03		Shallow Concentrated Flow, Tc-2 Paved Kv= 20.3 fps

Summary for Subcatchment 3S: Drainage Area 3

Runoff = 0.73 cfs @ 12.10 hrs, Volume= 0.050 af, Depth> 1.05"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 2-year Rainfall=3.37"

Proposed Conditions

Type III 24-hr 2-year Rainfall=3.37"

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 6

Area (sf)	CN	Description
* 8,529	98	Paved parking/roof
16,209	61	>75% Grass cover, Good, HSG B
24,738	74	Weighted Average
16,209		65.52% Pervious Area
8,529		34.48% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0	105	0.1100	0.35		Sheet Flow, Tc-4a Grass: Short n= 0.150 P2= 3.37"
0.7	160	0.0310	3.57		Shallow Concentrated Flow, Tc-4b Paved Kv= 20.3 fps
5.7	265	Total			

Summary for Subcatchment 4S: Drainage Area 4

Runoff = 2.43 cfs @ 12.04 hrs, Volume= 0.148 af, Depth> 1.11"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 2-year Rainfall=3.37"

Area (sf)	CN	Description
* 30,200	98	Paved parking & roof HSG A
20,000	61	>75% Grass cover, Good, HSG B
19,500	55	Woods, Good, HSG B
69,700	75	Weighted Average
39,500		56.67% Pervious Area
30,200		43.33% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.9	130	0.0100	1.13		Sheet Flow, Tc-3 Smooth surfaces n= 0.011 P2= 3.37"

Summary for Subcatchment 5S: Drainage Area 5

Runoff = 1.18 cfs @ 12.03 hrs, Volume= 0.072 af, Depth> 1.36"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 2-year Rainfall=3.37"

Area (sf)	CN	Description
* 13,450	98	Paved surfaces & roof
14,147	61	>75% Grass cover, Good, HSG B
27,597	79	Weighted Average
14,147		51.26% Pervious Area
13,450		48.74% Impervious Area

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC
 HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
 Type III 24-hr 2-year Rainfall=3.37"
 Printed 2/4/2021
 Page 7

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.3	180	0.0500	2.29		Sheet Flow, Tc-5 Smooth surfaces n= 0.011 P2= 3.37"

Summary for Subcatchment 6S: Drainage Area 6

Runoff = 1.75 cfs @ 12.06 hrs, Volume= 0.111 af, Depth> 1.23"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 2-year Rainfall=3.37"

Area (sf)	CN	Description
* 21,025	98	Pavement/Roofs, HSG B
22,990	61	>75% Grass cover, Good, HSG B
3,300	55	Woods, Good, HSG B
47,315	77	Weighted Average
26,290		55.56% Pervious Area
21,025		44.44% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.9	180	0.0500	0.76		Lag/CN Method, Tc-6

Summary for Subcatchment 7S: Drainage Area 7

Runoff = 1.07 cfs @ 12.02 hrs, Volume= 0.071 af, Depth> 2.84"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 2-year Rainfall=3.37"

Area (sf)	CN	Description
* 12,295	98	Roof & Pavement
* 716	74	>75% Grass cover, Good, HSG B/D
13,011	97	Weighted Average
716		5.50% Pervious Area
12,295		94.50% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.2	175	0.0580	2.42		Sheet Flow, Tc-7 Smooth surfaces n= 0.011 P2= 3.37"

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 2-year Rainfall=3.37"
Printed 2/4/2021
Page 8

Summary for Subcatchment 8S: Overland to Swales

Runoff = 0.18 cfs @ 12.19 hrs, Volume= 0.022 af, Depth> 0.35"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 2-year Rainfall=3.37"

Area (sf)	CN	Description
* 33,644	58	>75% Grass cover, Good, HSG B
33,644		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.3	130	0.1240	0.26		Sheet Flow, Tc=8 Grass: Dense n= 0.240 P2= 3.37"


Summary for Reach 3R: Riprap Swale

Inflow Area = 0.772 ac, 0.00% Impervious, Inflow Depth > 0.35" for 2-year event
Inflow = 0.18 cfs @ 12.19 hrs, Volume= 0.022 af
Outflow = 0.17 cfs @ 12.31 hrs, Volume= 0.022 af, Atten= 3%, Lag= 6.7 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Max. Velocity= 1.13 fps, Min. Travel Time= 3.1 min
Avg. Velocity= 0.58 fps, Avg. Travel Time= 6.0 min

Peak Storage= 32 cf @ 12.25 hrs
Average Depth at Peak Storage= 0.04'
Bank-Full Depth= 1.00' Flow Area= 6.0 sf, Capacity= 48.58 cfs

4.00' x 1.00' deep channel, n= 0.045
Side Slope Z-value= 2.0 '/' Top Width= 8.00'
Length= 210.0' Slope= 0.0952 '/'
Inlet Invert= 276.00', Outlet Invert= 256.00'



Summary for Reach 4R: Grass swale to basin

Inflow Area = 0.772 ac, 0.00% Impervious, Inflow Depth > 0.35" for 2-year event
Inflow = 0.17 cfs @ 12.31 hrs, Volume= 0.022 af
Outflow = 0.17 cfs @ 12.42 hrs, Volume= 0.022 af, Atten= 2%, Lag= 7.0 min

Proposed Conditions

Type III 24-hr 2-year Rainfall=3.37"

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 9

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Max. Velocity= 1.02 fps, Min. Travel Time= 3.3 min

Avg. Velocity = 0.53 fps, Avg. Travel Time= 6.5 min

Peak Storage= 33 cf @ 12.37 hrs

Average Depth at Peak Storage= 0.04'

Bank-Full Depth= 1.00' Flow Area= 6.0 sf, Capacity= 42.41 cfs

4.00' x 1.00' deep channel, n= 0.035

Side Slope Z-value= 2.0 '/' Top Width= 8.00'

Length= 205.0' Slope= 0.0439 '/'

Inlet Invert= 256.00', Outlet Invert= 247.00'

**Summary for Reach 9R: Peak off Site**

Inflow Area = 11.002 ac, 20.74% Impervious, Inflow Depth > 0.38" for 2-year event

Inflow = 2.64 cfs @ 12.60 hrs, Volume= 0.352 af

Outflow = 2.64 cfs @ 12.60 hrs, Volume= 0.352 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Summary for Pond 1P: CB_1-2

Inflow Area = 0.197 ac, 48.07% Impervious, Inflow Depth > 1.35" for 2-year event

Inflow = 0.29 cfs @ 12.14 hrs, Volume= 0.022 af

Outflow = 0.29 cfs @ 12.14 hrs, Volume= 0.022 af, Atten= 0%, Lag= 0.0 min

Primary = 0.29 cfs @ 12.14 hrs, Volume= 0.022 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 311.75' @ 12.14 hrs

Flood Elev= 316.00'

Device	Routing	Invert	Outlet Devices
#1	Primary	311.50'	15.0" Round Culvert L= 128.7' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 311.50' / 298.95' S= 0.0975 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf

Primary OutFlow Max=0.29 cfs @ 12.14 hrs HW=311.75' (Free Discharge)↑ **1=Culvert** (Inlet Controls 0.29 cfs @ 1.69 fps)

Proposed Conditions

Type III 24-hr 2-year Rainfall=3.37"

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 10

Summary for Pond 2P: CB_3-4

Inflow Area = 0.503 ac, 50.95% Impervious, Inflow Depth > 1.71" for 2-year event
 Inflow = 0.97 cfs @ 12.03 hrs, Volume= 0.072 af
 Outflow = 0.97 cfs @ 12.03 hrs, Volume= 0.072 af, Atten= 0%, Lag= 0.0 min
 Primary = 0.97 cfs @ 12.03 hrs, Volume= 0.072 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 299.32' @ 12.03 hrs

Flood Elev= 303.30'

Device	Routing	Invert	Outlet Devices
#1	Primary	298.85'	15.0" Round Culvert L= 131.1' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 298.85' / 286.60' S= 0.0934 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf

Primary OutFlow Max=0.95 cfs @ 12.03 hrs HW=299.31' (Free Discharge)↑**1=Culvert** (Inlet Controls 0.95 cfs @ 2.31 fps)**Summary for Pond 3P: CB_5-6**

Inflow Area = 1.070 ac, 42.21% Impervious, Inflow Depth > 1.36" for 2-year event
 Inflow = 1.59 cfs @ 12.06 hrs, Volume= 0.121 af
 Outflow = 1.59 cfs @ 12.06 hrs, Volume= 0.121 af, Atten= 0%, Lag= 0.0 min
 Primary = 1.59 cfs @ 12.06 hrs, Volume= 0.121 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 287.11' @ 12.06 hrs

Flood Elev= 291.00'

Device	Routing	Invert	Outlet Devices
#1	Primary	286.50'	15.0" Round Culvert L= 168.9' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 286.50' / 272.60' S= 0.0823 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf

Primary OutFlow Max=1.56 cfs @ 12.06 hrs HW=287.11' (Free Discharge)↑**1=Culvert** (Inlet Controls 1.56 cfs @ 2.65 fps)**Summary for Pond 4P: CB_7-8**

Inflow Area = 2.671 ac, 42.88% Impervious, Inflow Depth > 1.21" for 2-year event
 Inflow = 4.00 cfs @ 12.05 hrs, Volume= 0.269 af
 Outflow = 4.00 cfs @ 12.05 hrs, Volume= 0.269 af, Atten= 0%, Lag= 0.0 min
 Primary = 4.00 cfs @ 12.05 hrs, Volume= 0.269 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Proposed Conditions

Type III 24-hr 2-year Rainfall=3.37"

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 11

Peak Elev= 273.58' @ 12.05 hrs

Flood Elev= 277.00'

Device	Routing	Invert	Outlet Devices
#1	Primary	272.50'	15.0" Round Culvert L= 128.2' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 272.50' / 263.70' S= 0.0686 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf

Primary OutFlow Max=3.96 cfs @ 12.05 hrs HW=273.57' (Free Discharge)↑**1=Culvert** (Inlet Controls 3.96 cfs @ 3.53 fps)**Summary for Pond 5P: CB-9**

Inflow Area = 3.304 ac, 44.00% Impervious, Inflow Depth > 1.24" for 2-year event
Inflow = 5.16 cfs @ 12.04 hrs, Volume= 0.341 af
Outflow = 5.16 cfs @ 12.04 hrs, Volume= 0.341 af, Atten= 0%, Lag= 0.0 min
Primary = 5.16 cfs @ 12.04 hrs, Volume= 0.341 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 264.99' @ 12.04 hrs

Flood Elev= 267.30'

Device	Routing	Invert	Outlet Devices
#1	Primary	263.60'	15.0" Round Culvert L= 100.6' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 263.60' / 253.10' S= 0.1044 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf

Primary OutFlow Max=5.05 cfs @ 12.04 hrs HW=264.95' (Free Discharge)↑**1=Culvert** (Inlet Controls 5.05 cfs @ 4.11 fps)**Summary for Pond 6P: CB_10-11**

Inflow Area = 4.390 ac, 44.11% Impervious, Inflow Depth > 1.24" for 2-year event
Inflow = 6.86 cfs @ 12.05 hrs, Volume= 0.452 af
Outflow = 6.86 cfs @ 12.05 hrs, Volume= 0.452 af, Atten= 0%, Lag= 0.0 min
Primary = 6.86 cfs @ 12.05 hrs, Volume= 0.452 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 254.39' @ 12.05 hrs

Flood Elev= 259.50'

Device	Routing	Invert	Outlet Devices
#1	Primary	253.00'	18.0" Round Culvert L= 172.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 253.00' / 245.10' S= 0.0459 '/' Cc= 0.900 n= 0.012, Flow Area= 1.77 sf

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 2-year Rainfall=3.37"
Printed 2/4/2021
Page 12

Primary OutFlow Max=6.84 cfs @ 12.05 hrs HW=254.39' (Free Discharge)

↑**1=Culvert** (Inlet Controls 6.84 cfs @ 4.01 fps)

Summary for Pond 7P: CB_12-13

Inflow Area = 4.689 ac, 47.32% Impervious, Inflow Depth > 1.34" for 2-year event
Inflow = 7.84 cfs @ 12.04 hrs, Volume= 0.523 af
Outflow = 7.84 cfs @ 12.04 hrs, Volume= 0.523 af, Atten= 0%, Lag= 0.0 min
Primary = 7.84 cfs @ 12.04 hrs, Volume= 0.523 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 246.60' @ 12.05 hrs

Flood Elev= 249.60'

Device	Routing	Invert	Outlet Devices
#1	Primary	245.00'	18.0" Round Culvert L= 36.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 245.00' / 244.00' S= 0.0278 '/' Cc= 0.900 n= 0.012, Flow Area= 1.77 sf

Primary OutFlow Max=7.72 cfs @ 12.04 hrs HW=246.57' (Free Discharge)

↑**1=Culvert** (Inlet Controls 7.72 cfs @ 4.37 fps)

Summary for Pond 10P: Stormwater Basin

Inflow Area = 5.461 ac, 40.63% Impervious, Inflow Depth > 1.20" for 2-year event
Inflow = 7.84 cfs @ 12.04 hrs, Volume= 0.545 af
Outflow = 1.10 cfs @ 12.77 hrs, Volume= 0.523 af, Atten= 86%, Lag= 43.3 min
Discarded = 0.69 cfs @ 12.77 hrs, Volume= 0.447 af
Primary = 0.41 cfs @ 12.77 hrs, Volume= 0.076 af
Secondary = 0.00 cfs @ 5.00 hrs, Volume= 0.000 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 243.69' @ 12.77 hrs Surf.Area= 6,623 sf Storage= 9,216 cf

Plug-Flow detention time= 115.2 min calculated for 0.523 af (96% of inflow)

Center-of-Mass det. time= 100.3 min (899.7 - 799.4)

Volume	Invert	Avail.Storage	Storage Description
#1	242.00'	46,796 cf	Custom Stage Data (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
242.00	4,270	0	0
244.00	7,051	11,321	11,321
246.00	8,985	16,036	27,357
248.00	10,454	19,439	46,796

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 13

Device	Routing	Invert	Outlet Devices
#1	Primary	242.50'	15.0" Round Culvert L= 100.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 242.50' / 242.00' S= 0.0050 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf
#2	Device 1	243.00'	4.0" Vert. Orifice/Grate C= 0.600
#3	Device 1	243.50'	6.0" Vert. Orifice/Grate C= 0.600
#4	Device 1	244.00'	10.0" Vert. Orifice/Grate C= 0.600
#5	Device 1	246.50'	36.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#6	Secondary	247.00'	18.0' long x 2.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 Coef. (English) 2.54 2.61 2.61 2.60 2.66 2.70 2.77 2.89 2.88 2.85 3.07 3.20 3.32
#7	Discarded	242.00'	4.500 in/hr Exfiltration over Horizontal area

Discarded OutFlow Max=0.69 cfs @ 12.77 hrs HW=243.69' (Free Discharge)↑ **7=Exfiltration** (Exfiltration Controls 0.69 cfs)**Primary OutFlow** Max=0.41 cfs @ 12.77 hrs HW=243.69' (Free Discharge)
↑ **1=Culvert** (Passes 0.41 cfs of 3.84 cfs potential flow)
↑ **2=Orifice/Grate** (Orifice Controls 0.30 cfs @ 3.49 fps)
↑ **3=Orifice/Grate** (Orifice Controls 0.10 cfs @ 1.49 fps)
↑ **4=Orifice/Grate** (Controls 0.00 cfs)
↑ **5=Orifice/Grate** (Controls 0.00 cfs)
Secondary OutFlow Max=0.00 cfs @ 5.00 hrs HW=242.00' (Free Discharge)↑ **6=Broad-Crested Rectangular Weir** (Controls 0.00 cfs)**Summary for Link 1L: Wetlands Drainage**
Inflow Area = 5.540 ac, 1.13% Impervious, Inflow Depth > 0.60" for 2-year event
Inflow = 2.24 cfs @ 12.59 hrs, Volume= 0.276 af
Primary = 2.24 cfs @ 12.59 hrs, Volume= 0.276 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

2-year Outflow Imported from Proposed Wetlands Drainage~Reach 2R.hce

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 5-year Rainfall=4.27"
Printed 2/4/2021
Page 14

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Drainage Area 1	Runoff Area=8,570 sf 48.07% Impervious Runoff Depth>2.03"
Flow Length=111'	Slope=0.0710 '/ Tc=9.1 min CN=79 Runoff=0.44 cfs 0.033 af
Subcatchment 2S: Drainage Area 2	Runoff Area=13,320 sf 52.80% Impervious Runoff Depth>2.72"
Flow Length=125'	Slope=0.0100 '/ Tc=1.0 min CN=87 Runoff=1.14 cfs 0.069 af
Subcatchment 3S: Drainage Area 3	Runoff Area=24,738 sf 34.48% Impervious Runoff Depth>1.66"
Flow Length=265'	Tc=5.7 min CN=74 Runoff=1.17 cfs 0.078 af
Subcatchment 4S: Drainage Area 4	Runoff Area=69,700 sf 43.33% Impervious Runoff Depth>1.73"
Flow Length=130'	Slope=0.0100 '/ Tc=1.9 min CN=75 Runoff=3.83 cfs 0.231 af
Subcatchment 5S: Drainage Area 5	Runoff Area=27,597 sf 48.74% Impervious Runoff Depth>2.03"
Flow Length=180'	Slope=0.0500 '/ Tc=1.3 min CN=79 Runoff=1.78 cfs 0.107 af
Subcatchment 6S: Drainage Area 6	Runoff Area=47,315 sf 44.44% Impervious Runoff Depth>1.88"
Flow Length=180'	Slope=0.0500 '/ Tc=3.9 min CN=77 Runoff=2.71 cfs 0.170 af
Subcatchment 7S: Drainage Area 7	Runoff Area=13,011 sf 94.50% Impervious Runoff Depth>3.67"
Flow Length=175'	Slope=0.0580 '/ Tc=1.2 min CN=97 Runoff=1.36 cfs 0.091 af
Subcatchment 8S: Overland to Swales	Runoff Area=33,644 sf 0.00% Impervious Runoff Depth>0.70"
Flow Length=130'	Slope=0.1240 '/ Tc=8.3 min CN=58 Runoff=0.50 cfs 0.045 af
Reach 3R: Riprap Swale	Avg. Flow Depth=0.07' Max Vel=1.68 fps Inflow=0.50 cfs 0.045 af
	n=0.045 L=210.0' S=0.0952 '/ Capacity=48.58 cfs Outflow=0.48 cfs 0.045 af
Reach 4R: Grass swale to basin	Avg. Flow Depth=0.07' Max Vel=1.53 fps Inflow=0.48 cfs 0.045 af
	n=0.035 L=205.0' S=0.0439 '/ Capacity=42.41 cfs Outflow=0.46 cfs 0.045 af
Reach 9R: Peak off Site	Inflow=6.18 cfs 0.741 af
	Outflow=6.18 cfs 0.741 af
Pond 1P: CB_1-2	Peak Elev=311.81' Inflow=0.44 cfs 0.033 af
	15.0" Round Culvert n=0.012 L=128.7' S=0.0975 '/ Outflow=0.44 cfs 0.033 af
Pond 2P: CB_3-4	Peak Elev=299.41' Inflow=1.37 cfs 0.102 af
	15.0" Round Culvert n=0.012 L=131.1' S=0.0934 '/ Outflow=1.37 cfs 0.102 af
Pond 3P: CB_5-6	Peak Elev=287.28' Inflow=2.40 cfs 0.181 af
	15.0" Round Culvert n=0.012 L=168.9' S=0.0823 '/ Outflow=2.40 cfs 0.181 af
Pond 4P: CB_7-8	Peak Elev=274.22' Inflow=6.19 cfs 0.412 af
	15.0" Round Culvert n=0.012 L=128.2' S=0.0686 '/ Outflow=6.19 cfs 0.412 af
Pond 5P: CB-9	Peak Elev=266.02' Inflow=7.92 cfs 0.519 af
	15.0" Round Culvert n=0.012 L=100.6' S=0.1044 '/ Outflow=7.92 cfs 0.519 af

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 5-year Rainfall=4.27"

Printed 2/4/2021

Page 15

Pond 6P: CB_10-11

Peak Elev=255.29' Inflow=10.56 cfs 0.689 af
18.0" Round Culvert n=0.012 L=172.0' S=0.0459 '/ Outflow=10.56 cfs 0.689 af

Pond 7P: CB_12-13

Peak Elev=247.68' Inflow=11.82 cfs 0.781 af
18.0" Round Culvert n=0.012 L=36.0' S=0.0278 '/ Outflow=11.82 cfs 0.781 af

Pond 10P: Stormwater Basin

Peak Elev=244.34' Storage=13,799 cf Inflow=11.84 cfs 0.825 af
Discarded=0.77 cfs 0.508 af Primary=1.61 cfs 0.253 af Secondary=0.00 cfs 0.000 af Outflow=2.38 cfs 0.761 af

Link 1L:

5-year Outflow Imported from Proposed Wetlands Drainage~Reach 2R.hce Inflow=4.58 cfs 0.488 af
Area= 5.540 ac 1.13% Imperv. Primary=4.58 cfs 0.488 af

Total Runoff Area = 5.461 ac Runoff Volume = 0.826 af Average Runoff Depth = 1.81"
59.37% Pervious = 3.242 ac 40.63% Impervious = 2.219 ac

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 5-year Rainfall=4.27"
Printed 2/4/2021
Page 16

Summary for Subcatchment 1S: Drainage Area 1

Runoff = 0.44 cfs @ 12.13 hrs, Volume= 0.033 af, Depth> 2.03"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 5-year Rainfall=4.27"

Area (sf)	CN	Description
4,120	98	Paved parking, HSG B
4,450	61	>75% Grass cover, Good, HSG B
8,570	79	Weighted Average
4,450		51.93% Pervious Area
4,120		48.07% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.1	111	0.0710	0.20		Sheet Flow, Tc-1 Grass: Dense n= 0.240 P2= 3.37"

Summary for Subcatchment 2S: Drainage Area 2

Runoff = 1.14 cfs @ 12.02 hrs, Volume= 0.069 af, Depth> 2.72"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 5-year Rainfall=4.27"

Area (sf)	CN	Description
* 6,287	74	>75% Grass cover, Good, HSG B/D
* 7,033	98	Roof/pavement
13,320	87	Weighted Average
6,287		47.20% Pervious Area
7,033		52.80% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.0	125	0.0100	2.03		Shallow Concentrated Flow, Tc-2 Paved Kv= 20.3 fps

Summary for Subcatchment 3S: Drainage Area 3

Runoff = 1.17 cfs @ 12.09 hrs, Volume= 0.078 af, Depth> 1.66"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 5-year Rainfall=4.27"

Proposed Conditions

Type III 24-hr 5-year Rainfall=4.27"

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 17

Area (sf)	CN	Description
* 8,529	98	Paved parking/roof
16,209	61	>75% Grass cover, Good, HSG B
24,738	74	Weighted Average
16,209		65.52% Pervious Area
8,529		34.48% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0	105	0.1100	0.35		Sheet Flow, Tc-4a Grass: Short n= 0.150 P2= 3.37"
0.7	160	0.0310	3.57		Shallow Concentrated Flow, Tc-4b Paved Kv= 20.3 fps
5.7	265	Total			

Summary for Subcatchment 4S: Drainage Area 4

Runoff = 3.83 cfs @ 12.04 hrs, Volume= 0.231 af, Depth> 1.73"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Type III 24-hr 5-year Rainfall=4.27"

Area (sf)	CN	Description
* 30,200	98	Paved parking & roof HSG A
20,000	61	>75% Grass cover, Good, HSG B
19,500	55	Woods, Good, HSG B
69,700	75	Weighted Average
39,500		56.67% Pervious Area
30,200		43.33% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.9	130	0.0100	1.13		Sheet Flow, Tc-3 Smooth surfaces n= 0.011 P2= 3.37"

Summary for Subcatchment 5S: Drainage Area 5

Runoff = 1.78 cfs @ 12.02 hrs, Volume= 0.107 af, Depth> 2.03"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Type III 24-hr 5-year Rainfall=4.27"

Area (sf)	CN	Description
* 13,450	98	Paved surfaces & roof
14,147	61	>75% Grass cover, Good, HSG B
27,597	79	Weighted Average
14,147		51.26% Pervious Area
13,450		48.74% Impervious Area

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC
 HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
 Type III 24-hr 5-year Rainfall=4.27"
 Printed 2/4/2021
 Page 18

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.3	180	0.0500	2.29		Sheet Flow, Tc-5 Smooth surfaces n= 0.011 P2= 3.37"

Summary for Subcatchment 6S: Drainage Area 6

Runoff = 2.71 cfs @ 12.06 hrs, Volume= 0.170 af, Depth> 1.88"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 5-year Rainfall=4.27"

Area (sf)	CN	Description
* 21,025	98	Pavement/Roofs, HSG B
22,990	61	>75% Grass cover, Good, HSG B
3,300	55	Woods, Good, HSG B
47,315	77	Weighted Average
26,290		55.56% Pervious Area
21,025		44.44% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.9	180	0.0500	0.76		Lag/CN Method, Tc-6

Summary for Subcatchment 7S: Drainage Area 7

Runoff = 1.36 cfs @ 12.02 hrs, Volume= 0.091 af, Depth> 3.67"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 5-year Rainfall=4.27"

Area (sf)	CN	Description
* 12,295	98	Roof & Pavement
* 716	74	>75% Grass cover, Good, HSG B/D
13,011	97	Weighted Average
716		5.50% Pervious Area
12,295		94.50% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.2	175	0.0580	2.42		Sheet Flow, Tc-7 Smooth surfaces n= 0.011 P2= 3.37"

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 5-year Rainfall=4.27"
Printed 2/4/2021
Page 19

Summary for Subcatchment 8S: Overland to Swales

Runoff = 0.50 cfs @ 12.15 hrs, Volume= 0.045 af, Depth> 0.70"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 5-year Rainfall=4.27"

Area (sf)	CN	Description
* 33,644	58	>75% Grass cover, Good, HSG B
33,644		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.3	130	0.1240	0.26		Sheet Flow, Tc=8 Grass: Dense n= 0.240 P2= 3.37"


Summary for Reach 3R: Riprap Swale

Inflow Area = 0.772 ac, 0.00% Impervious, Inflow Depth > 0.70" for 5-year event
Inflow = 0.50 cfs @ 12.15 hrs, Volume= 0.045 af
Outflow = 0.48 cfs @ 12.22 hrs, Volume= 0.045 af, Atten= 3%, Lag= 3.9 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Max. Velocity= 1.68 fps, Min. Travel Time= 2.1 min
Avg. Velocity= 0.71 fps, Avg. Travel Time= 4.9 min

Peak Storage= 61 cf @ 12.17 hrs
Average Depth at Peak Storage= 0.07'
Bank-Full Depth= 1.00' Flow Area= 6.0 sf, Capacity= 48.58 cfs

4.00' x 1.00' deep channel, n= 0.045
Side Slope Z-value= 2.0 '/' Top Width= 8.00'
Length= 210.0' Slope= 0.0952 '/'
Inlet Invert= 276.00', Outlet Invert= 256.00'



Summary for Reach 4R: Grass swale to basin

Inflow Area = 0.772 ac, 0.00% Impervious, Inflow Depth > 0.70" for 5-year event
Inflow = 0.48 cfs @ 12.22 hrs, Volume= 0.045 af
Outflow = 0.46 cfs @ 12.29 hrs, Volume= 0.045 af, Atten= 4%, Lag= 4.4 min

Proposed Conditions

Type III 24-hr 5-year Rainfall=4.27"

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 20

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Max. Velocity= 1.53 fps, Min. Travel Time= 2.2 min

Avg. Velocity = 0.66 fps, Avg. Travel Time= 5.2 min

Peak Storage= 63 cf @ 12.25 hrs

Average Depth at Peak Storage= 0.07'

Bank-Full Depth= 1.00' Flow Area= 6.0 sf, Capacity= 42.41 cfs

4.00' x 1.00' deep channel, n= 0.035

Side Slope Z-value= 2.0 '/' Top Width= 8.00'

Length= 205.0' Slope= 0.0439 '/'

Inlet Invert= 256.00', Outlet Invert= 247.00'

**Summary for Reach 9R: Peak off Site**

Inflow Area = 11.002 ac, 20.74% Impervious, Inflow Depth > 0.81" for 5-year event

Inflow = 6.18 cfs @ 12.49 hrs, Volume= 0.741 af

Outflow = 6.18 cfs @ 12.49 hrs, Volume= 0.741 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Summary for Pond 1P: CB_1-2

Inflow Area = 0.197 ac, 48.07% Impervious, Inflow Depth > 2.03" for 5-year event

Inflow = 0.44 cfs @ 12.13 hrs, Volume= 0.033 af

Outflow = 0.44 cfs @ 12.13 hrs, Volume= 0.033 af, Atten= 0%, Lag= 0.0 min

Primary = 0.44 cfs @ 12.13 hrs, Volume= 0.033 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 311.81' @ 12.13 hrs

Flood Elev= 316.00'

Device	Routing	Invert	Outlet Devices
#1	Primary	311.50'	15.0" Round Culvert L= 128.7' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 311.50' / 298.95' S= 0.0975 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf

Primary OutFlow Max=0.43 cfs @ 12.13 hrs HW=311.80' (Free Discharge)↑ **1=Culvert** (Inlet Controls 0.43 cfs @ 1.88 fps)

Proposed Conditions

Type III 24-hr 5-year Rainfall=4.27"

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 21

Summary for Pond 2P: CB_3-4

Inflow Area = 0.503 ac, 50.95% Impervious, Inflow Depth > 2.45" for 5-year event
 Inflow = 1.37 cfs @ 12.03 hrs, Volume= 0.102 af
 Outflow = 1.37 cfs @ 12.03 hrs, Volume= 0.102 af, Atten= 0%, Lag= 0.0 min
 Primary = 1.37 cfs @ 12.03 hrs, Volume= 0.102 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 299.41' @ 12.03 hrs

Flood Elev= 303.30'

Device	Routing	Invert	Outlet Devices
#1	Primary	298.85'	15.0" Round Culvert L= 131.1' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 298.85' / 286.60' S= 0.0934 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf

Primary OutFlow Max=1.34 cfs @ 12.03 hrs HW=299.41' (Free Discharge)↑**1=Culvert** (Inlet Controls 1.34 cfs @ 2.54 fps)**Summary for Pond 3P: CB_5-6**

Inflow Area = 1.070 ac, 42.21% Impervious, Inflow Depth > 2.03" for 5-year event
 Inflow = 2.40 cfs @ 12.06 hrs, Volume= 0.181 af
 Outflow = 2.40 cfs @ 12.06 hrs, Volume= 0.181 af, Atten= 0%, Lag= 0.0 min
 Primary = 2.40 cfs @ 12.06 hrs, Volume= 0.181 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 287.28' @ 12.06 hrs

Flood Elev= 291.00'

Device	Routing	Invert	Outlet Devices
#1	Primary	286.50'	15.0" Round Culvert L= 168.9' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 286.50' / 272.60' S= 0.0823 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf

Primary OutFlow Max=2.35 cfs @ 12.06 hrs HW=287.27' (Free Discharge)↑**1=Culvert** (Inlet Controls 2.35 cfs @ 2.98 fps)**Summary for Pond 4P: CB_7-8**

Inflow Area = 2.671 ac, 42.88% Impervious, Inflow Depth > 1.85" for 5-year event
 Inflow = 6.19 cfs @ 12.04 hrs, Volume= 0.412 af
 Outflow = 6.19 cfs @ 12.04 hrs, Volume= 0.412 af, Atten= 0%, Lag= 0.0 min
 Primary = 6.19 cfs @ 12.04 hrs, Volume= 0.412 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Proposed Conditions

Type III 24-hr 5-year Rainfall=4.27"

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 22

Peak Elev= 274.22' @ 12.05 hrs

Flood Elev= 277.00'

Device	Routing	Invert	Outlet Devices
#1	Primary	272.50'	15.0" Round Culvert L= 128.2' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 272.50' / 263.70' S= 0.0686 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf

Primary OutFlow Max=6.10 cfs @ 12.04 hrs HW=274.19' (Free Discharge)↑**1=Culvert** (Inlet Controls 6.10 cfs @ 4.97 fps)**Summary for Pond 5P: CB-9**

Inflow Area = 3.304 ac, 44.00% Impervious, Inflow Depth > 1.89" for 5-year event
Inflow = 7.92 cfs @ 12.04 hrs, Volume= 0.519 af
Outflow = 7.92 cfs @ 12.04 hrs, Volume= 0.519 af, Atten= 0%, Lag= 0.0 min
Primary = 7.92 cfs @ 12.04 hrs, Volume= 0.519 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 266.02' @ 12.04 hrs

Flood Elev= 267.30'

Device	Routing	Invert	Outlet Devices
#1	Primary	263.60'	15.0" Round Culvert L= 100.6' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 263.60' / 253.10' S= 0.1044 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf

Primary OutFlow Max=7.73 cfs @ 12.04 hrs HW=265.94' (Free Discharge)↑**1=Culvert** (Inlet Controls 7.73 cfs @ 6.30 fps)**Summary for Pond 6P: CB_10-11**

Inflow Area = 4.390 ac, 44.11% Impervious, Inflow Depth > 1.88" for 5-year event
Inflow = 10.56 cfs @ 12.05 hrs, Volume= 0.689 af
Outflow = 10.56 cfs @ 12.05 hrs, Volume= 0.689 af, Atten= 0%, Lag= 0.0 min
Primary = 10.56 cfs @ 12.05 hrs, Volume= 0.689 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 255.29' @ 12.05 hrs

Flood Elev= 259.50'

Device	Routing	Invert	Outlet Devices
#1	Primary	253.00'	18.0" Round Culvert L= 172.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 253.00' / 245.10' S= 0.0459 '/' Cc= 0.900 n= 0.012, Flow Area= 1.77 sf

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 5-year Rainfall=4.27"
Printed 2/4/2021
Page 23

Primary OutFlow Max=10.45 cfs @ 12.05 hrs HW=255.26' (Free Discharge)

↑**1=Culvert** (Inlet Controls 10.45 cfs @ 5.92 fps)

Summary for Pond 7P: CB_12-13

Inflow Area = 4.689 ac, 47.32% Impervious, Inflow Depth > 2.00" for 5-year event
Inflow = 11.82 cfs @ 12.04 hrs, Volume= 0.781 af
Outflow = 11.82 cfs @ 12.04 hrs, Volume= 0.781 af, Atten= 0%, Lag= 0.0 min
Primary = 11.82 cfs @ 12.04 hrs, Volume= 0.781 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 247.68' @ 12.04 hrs

Flood Elev= 249.60'

Device	Routing	Invert	Outlet Devices
#1	Primary	245.00'	18.0" Round Culvert L= 36.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 245.00' / 244.00' S= 0.0278 '/' Cc= 0.900 n= 0.012, Flow Area= 1.77 sf

Primary OutFlow Max=11.60 cfs @ 12.04 hrs HW=247.61' (Free Discharge)

↑**1=Culvert** (Inlet Controls 11.60 cfs @ 6.57 fps)

Summary for Pond 10P: Stormwater Basin

Inflow Area = 5.461 ac, 40.63% Impervious, Inflow Depth > 1.81" for 5-year event
Inflow = 11.84 cfs @ 12.04 hrs, Volume= 0.825 af
Outflow = 2.38 cfs @ 12.52 hrs, Volume= 0.761 af, Atten= 80%, Lag= 28.7 min
Discarded = 0.77 cfs @ 12.52 hrs, Volume= 0.508 af
Primary = 1.61 cfs @ 12.52 hrs, Volume= 0.253 af
Secondary = 0.00 cfs @ 5.00 hrs, Volume= 0.000 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 244.34' @ 12.52 hrs Surf.Area= 7,383 sf Storage= 13,799 cf

Plug-Flow detention time= 106.8 min calculated for 0.759 af (92% of inflow)

Center-of-Mass det. time= 80.2 min (872.5 - 792.3)

Volume	Invert	Avail.Storage	Storage Description
#1	242.00'	46,796 cf	Custom Stage Data (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
242.00	4,270	0	0
244.00	7,051	11,321	11,321
246.00	8,985	16,036	27,357
248.00	10,454	19,439	46,796

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 24

Device	Routing	Invert	Outlet Devices
#1	Primary	242.50'	15.0" Round Culvert L= 100.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 242.50' / 242.00' S= 0.0050 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf
#2	Device 1	243.00'	4.0" Vert. Orifice/Grate C= 0.600
#3	Device 1	243.50'	6.0" Vert. Orifice/Grate C= 0.600
#4	Device 1	244.00'	10.0" Vert. Orifice/Grate C= 0.600
#5	Device 1	246.50'	36.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#6	Secondary	247.00'	18.0' long x 2.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 Coef. (English) 2.54 2.61 2.61 2.60 2.66 2.70 2.77 2.89 2.88 2.85 3.07 3.20 3.32
#7	Discarded	242.00'	4.500 in/hr Exfiltration over Horizontal area

Discarded OutFlow Max=0.77 cfs @ 12.52 hrs HW=244.34' (Free Discharge)↑ **7=Exfiltration** (Exfiltration Controls 0.77 cfs)**Primary OutFlow** Max=1.60 cfs @ 12.52 hrs HW=244.34' (Free Discharge)
 ↑ **1=Culvert** (Passes 1.60 cfs of 5.51 cfs potential flow)
 ↑ **2=Orifice/Grate** (Orifice Controls 0.46 cfs @ 5.22 fps)
 ↑ **3=Orifice/Grate** (Orifice Controls 0.73 cfs @ 3.70 fps)
 ↑ **4=Orifice/Grate** (Orifice Controls 0.42 cfs @ 1.99 fps)
 ↑ **5=Orifice/Grate** (Controls 0.00 cfs)
Secondary OutFlow Max=0.00 cfs @ 5.00 hrs HW=242.00' (Free Discharge)↑ **6=Broad-Crested Rectangular Weir** (Controls 0.00 cfs)**Summary for Link 1L: Wetlands Drainage**

Inflow Area = 5.540 ac, 1.13% Impervious, Inflow Depth > 1.06" for 5-year event
 Inflow = 4.58 cfs @ 12.49 hrs, Volume= 0.488 af
 Primary = 4.58 cfs @ 12.49 hrs, Volume= 0.488 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

5-year Outflow Imported from Proposed Wetlands Drainage~Reach 2R.hce

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 10-year Rainfall=5.02"
Printed 2/4/2021
Page 25

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Drainage Area 1 Runoff Area=8,570 sf 48.07% Impervious Runoff Depth>2.63"
Flow Length=111' Slope=0.0710 '/' Tc=9.1 min CN=79 Runoff=0.57 cfs 0.043 af

Subcatchment 2S: Drainage Area 2 Runoff Area=13,320 sf 52.80% Impervious Runoff Depth>3.38"
Flow Length=125' Slope=0.0100 '/' Tc=1.0 min CN=87 Runoff=1.41 cfs 0.086 af

Subcatchment 3S: Drainage Area 3 Runoff Area=24,738 sf 34.48% Impervious Runoff Depth>2.21"
Flow Length=265' Tc=5.7 min CN=74 Runoff=1.56 cfs 0.104 af

Subcatchment 4S: Drainage Area 4 Runoff Area=69,700 sf 43.33% Impervious Runoff Depth>2.29"
Flow Length=130' Slope=0.0100 '/' Tc=1.9 min CN=75 Runoff=5.07 cfs 0.306 af

Subcatchment 5S: Drainage Area 5 Runoff Area=27,597 sf 48.74% Impervious Runoff Depth>2.63"
Flow Length=180' Slope=0.0500 '/' Tc=1.3 min CN=79 Runoff=2.30 cfs 0.139 af

Subcatchment 6S: Drainage Area 6 Runoff Area=47,315 sf 44.44% Impervious Runoff Depth>2.46"
Flow Length=180' Slope=0.0500 '/' Tc=3.9 min CN=77 Runoff=3.54 cfs 0.222 af

Subcatchment 7S: Drainage Area 7 Runoff Area=13,011 sf 94.50% Impervious Runoff Depth>4.36"
Flow Length=175' Slope=0.0580 '/' Tc=1.2 min CN=97 Runoff=1.61 cfs 0.109 af

Subcatchment 8S: Overland to Swales Runoff Area=33,644 sf 0.00% Impervious Runoff Depth>1.06"
Flow Length=130' Slope=0.1240 '/' Tc=8.3 min CN=58 Runoff=0.83 cfs 0.068 af

Reach 3R: Riprap Swale Avg. Flow Depth=0.10' Max Vel=2.06 fps Inflow=0.83 cfs 0.068 af
n=0.045 L=210.0' S=0.0952 '/' Capacity=48.58 cfs Outflow=0.80 cfs 0.068 af

Reach 4R: Grass swale to basin Avg. Flow Depth=0.10' Max Vel=1.86 fps Inflow=0.80 cfs 0.068 af
n=0.035 L=205.0' S=0.0439 '/' Capacity=42.41 cfs Outflow=0.78 cfs 0.068 af

Reach 9R: Peak off Site Inflow=10.06 cfs 1.133 af
Outflow=10.06 cfs 1.133 af

Pond 1P: CB_1-2 Peak Elev=311.85' Inflow=0.57 cfs 0.043 af
15.0" Round Culvert n=0.012 L=128.7' S=0.0975 '/' Outflow=0.57 cfs 0.043 af

Pond 2P: CB_3-4 Peak Elev=299.49' Inflow=1.71 cfs 0.129 af
15.0" Round Culvert n=0.012 L=131.1' S=0.0934 '/' Outflow=1.71 cfs 0.129 af

Pond 3P: CB_5-6 Peak Elev=287.41' Inflow=3.10 cfs 0.234 af
15.0" Round Culvert n=0.012 L=168.9' S=0.0823 '/' Outflow=3.10 cfs 0.234 af

Pond 4P: CB_7-8 Peak Elev=275.01' Inflow=8.12 cfs 0.539 af
15.0" Round Culvert n=0.012 L=128.2' S=0.0686 '/' Outflow=8.12 cfs 0.539 af

Pond 5P: CB-9 Peak Elev=267.28' Inflow=10.35 cfs 0.678 af
15.0" Round Culvert n=0.012 L=100.6' S=0.1044 '/' Outflow=10.35 cfs 0.678 af

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 10-year Rainfall=5.02"

Printed 2/4/2021

Page 26

Pond 6P: CB_10-11

Peak Elev=256.38' Inflow=13.80 cfs 0.901 af
18.0" Round Culvert n=0.012 L=172.0' S=0.0459 '/' Outflow=13.80 cfs 0.901 af

Pond 7P: CB_12-13

Peak Elev=248.97' Inflow=15.29 cfs 1.009 af
18.0" Round Culvert n=0.012 L=36.0' S=0.0278 '/' Outflow=15.29 cfs 1.009 af

Pond 10P: Stormwater Basin

Peak Elev=244.81' Storage=17,356 cf Inflow=15.46 cfs 1.077 af
Discarded=0.82 cfs 0.547 af Primary=3.17 cfs 0.441 af Secondary=0.00 cfs 0.000 af Outflow=3.98 cfs 0.989 af

Link 1L:

10-year Outflow Imported from Proposed Wetlands Drainage~Reach 2R.hce Inflow=6.89 cfs 0.691 af
Area= 5.540 ac 1.13% Imperv. Primary=6.89 cfs 0.691 af

Total Runoff Area = 5.461 ac Runoff Volume = 1.077 af Average Runoff Depth = 2.37"
59.37% Pervious = 3.242 ac 40.63% Impervious = 2.219 ac

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC
 HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
 Type III 24-hr 10-year Rainfall=5.02"
 Printed 2/4/2021
 Page 27

Summary for Subcatchment 1S: Drainage Area 1

Runoff = 0.57 cfs @ 12.13 hrs, Volume= 0.043 af, Depth> 2.63"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-year Rainfall=5.02"

Area (sf)	CN	Description
4,120	98	Paved parking, HSG B
4,450	61	>75% Grass cover, Good, HSG B
8,570	79	Weighted Average
4,450		51.93% Pervious Area
4,120		48.07% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.1	111	0.0710	0.20		Sheet Flow, Tc-1 Grass: Dense n= 0.240 P2= 3.37"

Summary for Subcatchment 2S: Drainage Area 2

Runoff = 1.41 cfs @ 12.01 hrs, Volume= 0.086 af, Depth> 3.38"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-year Rainfall=5.02"

Area (sf)	CN	Description
* 6,287	74	>75% Grass cover, Good, HSG B/D
* 7,033	98	Roof/pavement
13,320	87	Weighted Average
6,287		47.20% Pervious Area
7,033		52.80% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.0	125	0.0100	2.03		Shallow Concentrated Flow, Tc-2 Paved Kv= 20.3 fps

Summary for Subcatchment 3S: Drainage Area 3

Runoff = 1.56 cfs @ 12.09 hrs, Volume= 0.104 af, Depth> 2.21"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-year Rainfall=5.02"

Proposed Conditions

Type III 24-hr 10-year Rainfall=5.02"

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 28

	Area (sf)	CN	Description
*	8,529	98	Paved parking/roof
	16,209	61	>75% Grass cover, Good, HSG B
	24,738	74	Weighted Average
	16,209		65.52% Pervious Area
	8,529		34.48% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0	105	0.1100	0.35		Sheet Flow, Tc-4a Grass: Short n= 0.150 P2= 3.37"
0.7	160	0.0310	3.57		Shallow Concentrated Flow, Tc-4b Paved Kv= 20.3 fps
5.7	265	Total			

Summary for Subcatchment 4S: Drainage Area 4

Runoff = 5.07 cfs @ 12.04 hrs, Volume= 0.306 af, Depth> 2.29"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Type III 24-hr 10-year Rainfall=5.02"

	Area (sf)	CN	Description
*	30,200	98	Paved parking & roof HSG A
	20,000	61	>75% Grass cover, Good, HSG B
	19,500	55	Woods, Good, HSG B
	69,700	75	Weighted Average
	39,500		56.67% Pervious Area
	30,200		43.33% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.9	130	0.0100	1.13		Sheet Flow, Tc-3 Smooth surfaces n= 0.011 P2= 3.37"

Summary for Subcatchment 5S: Drainage Area 5

Runoff = 2.30 cfs @ 12.02 hrs, Volume= 0.139 af, Depth> 2.63"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Type III 24-hr 10-year Rainfall=5.02"

	Area (sf)	CN	Description
*	13,450	98	Paved surfaces & roof
	14,147	61	>75% Grass cover, Good, HSG B
	27,597	79	Weighted Average
	14,147		51.26% Pervious Area
	13,450		48.74% Impervious Area

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC
 HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
 Type III 24-hr 10-year Rainfall=5.02"
 Printed 2/4/2021
 Page 29

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.3	180	0.0500	2.29		Sheet Flow, Tc-5 Smooth surfaces n= 0.011 P2= 3.37"

Summary for Subcatchment 6S: Drainage Area 6

Runoff = 3.54 cfs @ 12.06 hrs, Volume= 0.222 af, Depth> 2.46"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-year Rainfall=5.02"

Area (sf)	CN	Description
* 21,025	98	Pavement/Roofs, HSG B
22,990	61	>75% Grass cover, Good, HSG B
3,300	55	Woods, Good, HSG B
47,315	77	Weighted Average
26,290		55.56% Pervious Area
21,025		44.44% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.9	180	0.0500	0.76		Lag/CN Method, Tc-6

Summary for Subcatchment 7S: Drainage Area 7

Runoff = 1.61 cfs @ 12.02 hrs, Volume= 0.109 af, Depth> 4.36"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-year Rainfall=5.02"

Area (sf)	CN	Description
* 12,295	98	Roof & Pavement
* 716	74	>75% Grass cover, Good, HSG B/D
13,011	97	Weighted Average
716		5.50% Pervious Area
12,295		94.50% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.2	175	0.0580	2.42		Sheet Flow, Tc-7 Smooth surfaces n= 0.011 P2= 3.37"

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 10-year Rainfall=5.02"
Printed 2/4/2021
Page 30

Summary for Subcatchment 8S: Overland to Swales

Runoff = 0.83 cfs @ 12.14 hrs, Volume= 0.068 af, Depth> 1.06"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 10-year Rainfall=5.02"

Area (sf)	CN	Description
* 33,644	58	>75% Grass cover, Good, HSG B
33,644		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.3	130	0.1240	0.26		Sheet Flow, Tc=8 Grass: Dense n= 0.240 P2= 3.37"

Summary for Reach 3R: Riprap Swale

Inflow Area = 0.772 ac, 0.00% Impervious, Inflow Depth > 1.06" for 10-year event
Inflow = 0.83 cfs @ 12.14 hrs, Volume= 0.068 af
Outflow = 0.80 cfs @ 12.20 hrs, Volume= 0.068 af, Atten= 4%, Lag= 3.3 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Max. Velocity= 2.06 fps, Min. Travel Time= 1.7 min
Avg. Velocity= 0.81 fps, Avg. Travel Time= 4.3 min

Peak Storage= 85 cf @ 12.16 hrs
Average Depth at Peak Storage= 0.10'
Bank-Full Depth= 1.00' Flow Area= 6.0 sf, Capacity= 48.58 cfs

4.00' x 1.00' deep channel, n= 0.045
Side Slope Z-value= 2.0 '/' Top Width= 8.00'
Length= 210.0' Slope= 0.0952 '/'
Inlet Invert= 276.00', Outlet Invert= 256.00'



Summary for Reach 4R: Grass swale to basin

Inflow Area = 0.772 ac, 0.00% Impervious, Inflow Depth > 1.05" for 10-year event
Inflow = 0.80 cfs @ 12.20 hrs, Volume= 0.068 af
Outflow = 0.78 cfs @ 12.25 hrs, Volume= 0.068 af, Atten= 3%, Lag= 3.4 min

Proposed Conditions

Type III 24-hr 10-year Rainfall=5.02"

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 31

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Max. Velocity= 1.86 fps, Min. Travel Time= 1.8 min

Avg. Velocity = 0.75 fps, Avg. Travel Time= 4.6 min

Peak Storage= 87 cf @ 12.22 hrs

Average Depth at Peak Storage= 0.10'

Bank-Full Depth= 1.00' Flow Area= 6.0 sf, Capacity= 42.41 cfs

4.00' x 1.00' deep channel, n= 0.035

Side Slope Z-value= 2.0 '/' Top Width= 8.00'

Length= 205.0' Slope= 0.0439 '/'

Inlet Invert= 256.00', Outlet Invert= 247.00'

**Summary for Reach 9R: Peak off Site**

Inflow Area = 11.002 ac, 20.74% Impervious, Inflow Depth > 1.24" for 10-year event

Inflow = 10.06 cfs @ 12.44 hrs, Volume= 1.133 af

Outflow = 10.06 cfs @ 12.44 hrs, Volume= 1.133 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Summary for Pond 1P: CB_1-2

Inflow Area = 0.197 ac, 48.07% Impervious, Inflow Depth > 2.63" for 10-year event

Inflow = 0.57 cfs @ 12.13 hrs, Volume= 0.043 af

Outflow = 0.57 cfs @ 12.13 hrs, Volume= 0.043 af, Atten= 0%, Lag= 0.0 min

Primary = 0.57 cfs @ 12.13 hrs, Volume= 0.043 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 311.85' @ 12.13 hrs

Flood Elev= 316.00'

Device	Routing	Invert	Outlet Devices
#1	Primary	311.50'	15.0" Round Culvert L= 128.7' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 311.50' / 298.95' S= 0.0975 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf

Primary OutFlow Max=0.56 cfs @ 12.13 hrs HW=311.85' (Free Discharge)↑ **1=Culvert** (Inlet Controls 0.56 cfs @ 2.01 fps)

Proposed Conditions

Type III 24-hr 10-year Rainfall=5.02"

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 32

Summary for Pond 2P: CB_3-4

Inflow Area = 0.503 ac, 50.95% Impervious, Inflow Depth > 3.09" for 10-year event
 Inflow = 1.71 cfs @ 12.03 hrs, Volume= 0.129 af
 Outflow = 1.71 cfs @ 12.03 hrs, Volume= 0.129 af, Atten= 0%, Lag= 0.0 min
 Primary = 1.71 cfs @ 12.03 hrs, Volume= 0.129 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 299.49' @ 12.03 hrs

Flood Elev= 303.30'

Device	Routing	Invert	Outlet Devices
#1	Primary	298.85'	15.0" Round Culvert L= 131.1' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 298.85' / 286.60' S= 0.0934 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf

Primary OutFlow Max=1.67 cfs @ 12.03 hrs HW=299.48' (Free Discharge)↑**1=Culvert** (Inlet Controls 1.67 cfs @ 2.70 fps)**Summary for Pond 3P: CB_5-6**

Inflow Area = 1.070 ac, 42.21% Impervious, Inflow Depth > 2.62" for 10-year event
 Inflow = 3.10 cfs @ 12.06 hrs, Volume= 0.234 af
 Outflow = 3.10 cfs @ 12.06 hrs, Volume= 0.234 af, Atten= 0%, Lag= 0.0 min
 Primary = 3.10 cfs @ 12.06 hrs, Volume= 0.234 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 287.41' @ 12.06 hrs

Flood Elev= 291.00'

Device	Routing	Invert	Outlet Devices
#1	Primary	286.50'	15.0" Round Culvert L= 168.9' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 286.50' / 272.60' S= 0.0823 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf

Primary OutFlow Max=3.04 cfs @ 12.06 hrs HW=287.40' (Free Discharge)↑**1=Culvert** (Inlet Controls 3.04 cfs @ 3.23 fps)**Summary for Pond 4P: CB_7-8**

Inflow Area = 2.671 ac, 42.88% Impervious, Inflow Depth > 2.42" for 10-year event
 Inflow = 8.12 cfs @ 12.04 hrs, Volume= 0.539 af
 Outflow = 8.12 cfs @ 12.04 hrs, Volume= 0.539 af, Atten= 0%, Lag= 0.0 min
 Primary = 8.12 cfs @ 12.04 hrs, Volume= 0.539 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Proposed Conditions

Type III 24-hr 10-year Rainfall=5.02"

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 33

Peak Elev= 275.01' @ 12.04 hrs

Flood Elev= 277.00'

Device	Routing	Invert	Outlet Devices
#1	Primary	272.50'	15.0" Round Culvert L= 128.2' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 272.50' / 263.70' S= 0.0686 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf

Primary OutFlow Max=7.98 cfs @ 12.04 hrs HW=274.95' (Free Discharge)↑**1=Culvert** (Inlet Controls 7.98 cfs @ 6.50 fps)**Summary for Pond 5P: CB-9**

Inflow Area = 3.304 ac, 44.00% Impervious, Inflow Depth > 2.46" for 10-year event
Inflow = 10.35 cfs @ 12.04 hrs, Volume= 0.678 af
Outflow = 10.35 cfs @ 12.04 hrs, Volume= 0.678 af, Atten= 0%, Lag= 0.0 min
Primary = 10.35 cfs @ 12.04 hrs, Volume= 0.678 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 267.28' @ 12.04 hrs

Flood Elev= 267.30'

Device	Routing	Invert	Outlet Devices
#1	Primary	263.60'	15.0" Round Culvert L= 100.6' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 263.60' / 253.10' S= 0.1044 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf

Primary OutFlow Max=10.08 cfs @ 12.04 hrs HW=267.13' (Free Discharge)↑**1=Culvert** (Inlet Controls 10.08 cfs @ 8.21 fps)**Summary for Pond 6P: CB_10-11**

Inflow Area = 4.390 ac, 44.11% Impervious, Inflow Depth > 2.46" for 10-year event
Inflow = 13.80 cfs @ 12.05 hrs, Volume= 0.901 af
Outflow = 13.80 cfs @ 12.05 hrs, Volume= 0.901 af, Atten= 0%, Lag= 0.0 min
Primary = 13.80 cfs @ 12.05 hrs, Volume= 0.901 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 256.38' @ 12.05 hrs

Flood Elev= 259.50'

Device	Routing	Invert	Outlet Devices
#1	Primary	253.00'	18.0" Round Culvert L= 172.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 253.00' / 245.10' S= 0.0459 '/' Cc= 0.900 n= 0.012, Flow Area= 1.77 sf

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 10-year Rainfall=5.02"
Printed 2/4/2021
Page 34

Primary OutFlow Max=13.63 cfs @ 12.05 hrs HW=256.31' (Free Discharge)

↑**1=Culvert** (Inlet Controls 13.63 cfs @ 7.71 fps)

Summary for Pond 7P: CB_12-13

Inflow Area = 4.689 ac, 47.32% Impervious, Inflow Depth > 2.58" for 10-year event
Inflow = 15.29 cfs @ 12.04 hrs, Volume= 1.009 af
Outflow = 15.29 cfs @ 12.04 hrs, Volume= 1.009 af, Atten= 0%, Lag= 0.0 min
Primary = 15.29 cfs @ 12.04 hrs, Volume= 1.009 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 248.97' @ 12.04 hrs

Flood Elev= 249.60'

Device	Routing	Invert	Outlet Devices
#1	Primary	245.00'	18.0" Round Culvert L= 36.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 245.00' / 244.00' S= 0.0278 '/' Cc= 0.900 n= 0.012, Flow Area= 1.77 sf

Primary OutFlow Max=14.99 cfs @ 12.04 hrs HW=248.85' (Free Discharge)

↑**1=Culvert** (Inlet Controls 14.99 cfs @ 8.48 fps)

Summary for Pond 10P: Stormwater Basin

Inflow Area = 5.461 ac, 40.63% Impervious, Inflow Depth > 2.37" for 10-year event
Inflow = 15.46 cfs @ 12.04 hrs, Volume= 1.077 af
Outflow = 3.98 cfs @ 12.46 hrs, Volume= 0.989 af, Atten= 74%, Lag= 24.9 min
Discarded = 0.82 cfs @ 12.46 hrs, Volume= 0.547 af
Primary = 3.17 cfs @ 12.46 hrs, Volume= 0.441 af
Secondary = 0.00 cfs @ 5.00 hrs, Volume= 0.000 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 244.81' @ 12.46 hrs Surf.Area= 7,835 sf Storage= 17,356 cf

Plug-Flow detention time= 95.5 min calculated for 0.989 af (92% of inflow)

Center-of-Mass det. time= 67.3 min (854.9 - 787.6)

Volume	Invert	Avail.Storage	Storage Description
#1	242.00'	46,796 cf	Custom Stage Data (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
242.00	4,270	0	0
244.00	7,051	11,321	11,321
246.00	8,985	16,036	27,357
248.00	10,454	19,439	46,796

Proposed Conditions

Type III 24-hr 10-year Rainfall=5.02"

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 35

Device	Routing	Invert	Outlet Devices
#1	Primary	242.50'	15.0" Round Culvert L= 100.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 242.50' / 242.00' S= 0.0050 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf
#2	Device 1	243.00'	4.0" Vert. Orifice/Grate C= 0.600
#3	Device 1	243.50'	6.0" Vert. Orifice/Grate C= 0.600
#4	Device 1	244.00'	10.0" Vert. Orifice/Grate C= 0.600
#5	Device 1	246.50'	36.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#6	Secondary	247.00'	18.0' long x 2.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 Coef. (English) 2.54 2.61 2.61 2.60 2.66 2.70 2.77 2.89 2.88 2.85 3.07 3.20 3.32
#7	Discarded	242.00'	4.500 in/hr Exfiltration over Horizontal area

Discarded OutFlow Max=0.82 cfs @ 12.46 hrs HW=244.81' (Free Discharge)↑ **7=Exfiltration** (Exfiltration Controls 0.82 cfs)**Primary OutFlow** Max=3.17 cfs @ 12.46 hrs HW=244.81' (Free Discharge)
↑ **1=Culvert** (Passes 3.17 cfs of 6.59 cfs potential flow)
↑ **2=Orifice/Grate** (Orifice Controls 0.54 cfs @ 6.17 fps)
↑ **3=Orifice/Grate** (Orifice Controls 0.97 cfs @ 4.96 fps)
↑ **4=Orifice/Grate** (Orifice Controls 1.66 cfs @ 3.06 fps)
↑ **5=Orifice/Grate** (Controls 0.00 cfs)
Secondary OutFlow Max=0.00 cfs @ 5.00 hrs HW=242.00' (Free Discharge)↑ **6=Broad-Crested Rectangular Weir** (Controls 0.00 cfs)**Summary for Link 1L: Wetlands Drainage**
Inflow Area = 5.540 ac, 1.13% Impervious, Inflow Depth > 1.50" for 10-year event
Inflow = 6.89 cfs @ 12.44 hrs, Volume= 0.691 af
Primary = 6.89 cfs @ 12.44 hrs, Volume= 0.691 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

10-year Outflow Imported from Proposed Wetlands Drainage~Reach 2R.hce

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 25-year Rainfall=6.05"
Printed 2/4/2021
Page 36

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Drainage Area 1 Runoff Area=8,570 sf 48.07% Impervious Runoff Depth>3.48"
Flow Length=111' Slope=0.0710 '/' Tc=9.1 min CN=79 Runoff=0.76 cfs 0.057 af

Subcatchment 2S: Drainage Area 2 Runoff Area=13,320 sf 52.80% Impervious Runoff Depth>4.32"
Flow Length=125' Slope=0.0100 '/' Tc=1.0 min CN=87 Runoff=1.77 cfs 0.110 af

Subcatchment 3S: Drainage Area 3 Runoff Area=24,738 sf 34.48% Impervious Runoff Depth>3.00"
Flow Length=265' Tc=5.7 min CN=74 Runoff=2.12 cfs 0.142 af

Subcatchment 4S: Drainage Area 4 Runoff Area=69,700 sf 43.33% Impervious Runoff Depth>3.10"
Flow Length=130' Slope=0.0100 '/' Tc=1.9 min CN=75 Runoff=6.84 cfs 0.414 af

Subcatchment 5S: Drainage Area 5 Runoff Area=27,597 sf 48.74% Impervious Runoff Depth>3.49"
Flow Length=180' Slope=0.0500 '/' Tc=1.3 min CN=79 Runoff=3.03 cfs 0.184 af

Subcatchment 6S: Drainage Area 6 Runoff Area=47,315 sf 44.44% Impervious Runoff Depth>3.29"
Flow Length=180' Slope=0.0500 '/' Tc=3.9 min CN=77 Runoff=4.73 cfs 0.298 af

Subcatchment 7S: Drainage Area 7 Runoff Area=13,011 sf 94.50% Impervious Runoff Depth>5.30"
Flow Length=175' Slope=0.0580 '/' Tc=1.2 min CN=97 Runoff=1.95 cfs 0.132 af

Subcatchment 8S: Overland to Swales Runoff Area=33,644 sf 0.00% Impervious Runoff Depth>1.62"
Flow Length=130' Slope=0.1240 '/' Tc=8.3 min CN=58 Runoff=1.35 cfs 0.104 af

Reach 3R: Riprap Swale Avg. Flow Depth=0.13' Max Vel=2.47 fps Inflow=1.35 cfs 0.104 af
n=0.045 L=210.0' S=0.0952 '/' Capacity=48.58 cfs Outflow=1.30 cfs 0.104 af

Reach 4R: Grass swale to basin Avg. Flow Depth=0.14' Max Vel=2.23 fps Inflow=1.30 cfs 0.104 af
n=0.035 L=205.0' S=0.0439 '/' Capacity=42.41 cfs Outflow=1.26 cfs 0.104 af

Reach 9R: Peak off Site Inflow=15.11 cfs 1.731 af
Outflow=15.11 cfs 1.731 af

Pond 1P: CB_1-2 Peak Elev=311.91' Inflow=0.76 cfs 0.057 af
15.0" Round Culvert n=0.012 L=128.7' S=0.0975 '/' Outflow=0.76 cfs 0.057 af

Pond 2P: CB_3-4 Peak Elev=299.58' Inflow=2.19 cfs 0.167 af
15.0" Round Culvert n=0.012 L=131.1' S=0.0934 '/' Outflow=2.19 cfs 0.167 af

Pond 3P: CB_5-6 Peak Elev=287.60' Inflow=4.09 cfs 0.309 af
15.0" Round Culvert n=0.012 L=168.9' S=0.0823 '/' Outflow=4.09 cfs 0.309 af

Pond 4P: CB_7-8 Peak Elev=276.49' Inflow=10.85 cfs 0.723 af
15.0" Round Culvert n=0.012 L=128.2' S=0.0686 '/' Outflow=10.85 cfs 0.723 af

Pond 5P: CB-9 Peak Elev=269.65' Inflow=13.79 cfs 0.908 af
15.0" Round Culvert n=0.012 L=100.6' S=0.1044 '/' Outflow=13.79 cfs 0.908 af

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 25-year Rainfall=6.05"

Printed 2/4/2021

Page 37

Pond 6P: CB_10-11

Peak Elev=258.42' Inflow=18.39 cfs 1.206 af
18.0" Round Culvert n=0.012 L=172.0' S=0.0459 ' / ' Outflow=18.39 cfs 1.206 af

Pond 7P: CB_12-13

Peak Elev=251.37' Inflow=20.20 cfs 1.338 af
18.0" Round Culvert n=0.012 L=36.0' S=0.0278 ' / ' Outflow=20.20 cfs 1.338 af

Pond 10P: Stormwater Basin

Peak Elev=245.52' Storage=23,126 cf Inflow=20.63 cfs 1.441 af
Discarded=0.89 cfs 0.597 af Primary=4.65 cfs 0.731 af Secondary=0.00 cfs 0.000 af Outflow=5.54 cfs 1.328 af

Link 1L:

25-year Outflow Imported from Proposed Wetlands Drainage~Reach 2R.hce Inflow=10.47 cfs 1.000 af
Area= 5.540 ac 1.13% Imperv. Primary=10.47 cfs 1.000 af

Total Runoff Area = 5.461 ac Runoff Volume = 1.442 af Average Runoff Depth = 3.17"
59.37% Pervious = 3.242 ac 40.63% Impervious = 2.219 ac

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC
 HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 25-year Rainfall=6.05"
 Printed 2/4/2021
 Page 38

Summary for Subcatchment 1S: Drainage Area 1

Runoff = 0.76 cfs @ 12.13 hrs, Volume= 0.057 af, Depth> 3.48"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 25-year Rainfall=6.05"

Area (sf)	CN	Description
4,120	98	Paved parking, HSG B
4,450	61	>75% Grass cover, Good, HSG B
8,570	79	Weighted Average
4,450		51.93% Pervious Area
4,120		48.07% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.1	111	0.0710	0.20		Sheet Flow, Tc-1 Grass: Dense n= 0.240 P2= 3.37"

Summary for Subcatchment 2S: Drainage Area 2

Runoff = 1.77 cfs @ 12.01 hrs, Volume= 0.110 af, Depth> 4.32"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 25-year Rainfall=6.05"

Area (sf)	CN	Description
* 6,287	74	>75% Grass cover, Good, HSG B/D
* 7,033	98	Roof/pavement
13,320	87	Weighted Average
6,287		47.20% Pervious Area
7,033		52.80% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.0	125	0.0100	2.03		Shallow Concentrated Flow, Tc-2 Paved Kv= 20.3 fps

Summary for Subcatchment 3S: Drainage Area 3

Runoff = 2.12 cfs @ 12.09 hrs, Volume= 0.142 af, Depth> 3.00"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 25-year Rainfall=6.05"

Proposed Conditions

Type III 24-hr 25-year Rainfall=6.05"

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 39

Area (sf)	CN	Description
* 8,529	98	Paved parking/roof
16,209	61	>75% Grass cover, Good, HSG B
24,738	74	Weighted Average
16,209		65.52% Pervious Area
8,529		34.48% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0	105	0.1100	0.35		Sheet Flow, Tc-4a Grass: Short n= 0.150 P2= 3.37"
0.7	160	0.0310	3.57		Shallow Concentrated Flow, Tc-4b Paved Kv= 20.3 fps
5.7	265	Total			

Summary for Subcatchment 4S: Drainage Area 4

Runoff = 6.84 cfs @ 12.04 hrs, Volume= 0.414 af, Depth> 3.10"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Type III 24-hr 25-year Rainfall=6.05"

Area (sf)	CN	Description
* 30,200	98	Paved parking & roof HSG A
20,000	61	>75% Grass cover, Good, HSG B
19,500	55	Woods, Good, HSG B
69,700	75	Weighted Average
39,500		56.67% Pervious Area
30,200		43.33% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.9	130	0.0100	1.13		Sheet Flow, Tc-3 Smooth surfaces n= 0.011 P2= 3.37"

Summary for Subcatchment 5S: Drainage Area 5

Runoff = 3.03 cfs @ 12.02 hrs, Volume= 0.184 af, Depth> 3.49"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Type III 24-hr 25-year Rainfall=6.05"

Area (sf)	CN	Description
* 13,450	98	Paved surfaces & roof
14,147	61	>75% Grass cover, Good, HSG B
27,597	79	Weighted Average
14,147		51.26% Pervious Area
13,450		48.74% Impervious Area

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC
 HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
 Type III 24-hr 25-year Rainfall=6.05"
 Printed 2/4/2021
 Page 40

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.3	180	0.0500	2.29		Sheet Flow, Tc-5 Smooth surfaces n= 0.011 P2= 3.37"

Summary for Subcatchment 6S: Drainage Area 6

Runoff = 4.73 cfs @ 12.06 hrs, Volume= 0.298 af, Depth> 3.29"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 25-year Rainfall=6.05"

Area (sf)	CN	Description
* 21,025	98	Pavement/Roofs, HSG B
22,990	61	>75% Grass cover, Good, HSG B
3,300	55	Woods, Good, HSG B
47,315	77	Weighted Average
26,290		55.56% Pervious Area
21,025		44.44% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.9	180	0.0500	0.76		Lag/CN Method, Tc-6

Summary for Subcatchment 7S: Drainage Area 7

Runoff = 1.95 cfs @ 12.02 hrs, Volume= 0.132 af, Depth> 5.30"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 25-year Rainfall=6.05"

Area (sf)	CN	Description
* 12,295	98	Roof & Pavement
* 716	74	>75% Grass cover, Good, HSG B/D
13,011	97	Weighted Average
716		5.50% Pervious Area
12,295		94.50% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.2	175	0.0580	2.42		Sheet Flow, Tc-7 Smooth surfaces n= 0.011 P2= 3.37"

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 25-year Rainfall=6.05"
Printed 2/4/2021
Page 41

Summary for Subcatchment 8S: Overland to Swales

Runoff = 1.35 cfs @ 12.13 hrs, Volume= 0.104 af, Depth> 1.62"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 25-year Rainfall=6.05"

Area (sf)	CN	Description
* 33,644	58	>75% Grass cover, Good, HSG B
33,644		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.3	130	0.1240	0.26		Sheet Flow, Tc=8 Grass: Dense n= 0.240 P2= 3.37"

Summary for Reach 3R: Riprap Swale

Inflow Area = 0.772 ac, 0.00% Impervious, Inflow Depth > 1.62" for 25-year event
Inflow = 1.35 cfs @ 12.13 hrs, Volume= 0.104 af
Outflow = 1.30 cfs @ 12.18 hrs, Volume= 0.104 af, Atten= 4%, Lag= 2.6 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Max. Velocity= 2.47 fps, Min. Travel Time= 1.4 min
Avg. Velocity= 0.92 fps, Avg. Travel Time= 3.8 min

Peak Storage= 115 cf @ 12.15 hrs
Average Depth at Peak Storage= 0.13'
Bank-Full Depth= 1.00' Flow Area= 6.0 sf, Capacity= 48.58 cfs

4.00' x 1.00' deep channel, n= 0.045
Side Slope Z-value= 2.0 '/' Top Width= 8.00'
Length= 210.0' Slope= 0.0952 '/'
Inlet Invert= 276.00', Outlet Invert= 256.00'



Summary for Reach 4R: Grass swale to basin

Inflow Area = 0.772 ac, 0.00% Impervious, Inflow Depth > 1.62" for 25-year event
Inflow = 1.30 cfs @ 12.18 hrs, Volume= 0.104 af
Outflow = 1.26 cfs @ 12.22 hrs, Volume= 0.104 af, Atten= 3%, Lag= 2.9 min

Proposed Conditions

Type III 24-hr 25-year Rainfall=6.05"

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 42

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Max. Velocity= 2.23 fps, Min. Travel Time= 1.5 min

Avg. Velocity = 0.84 fps, Avg. Travel Time= 4.1 min

Peak Storage= 119 cf @ 12.20 hrs

Average Depth at Peak Storage= 0.14'

Bank-Full Depth= 1.00' Flow Area= 6.0 sf, Capacity= 42.41 cfs

4.00' x 1.00' deep channel, n= 0.035

Side Slope Z-value= 2.0 ' / ' Top Width= 8.00'

Length= 205.0' Slope= 0.0439 ' / '

Inlet Invert= 256.00', Outlet Invert= 247.00'

**Summary for Reach 9R: Peak off Site**

Inflow Area = 11.002 ac, 20.74% Impervious, Inflow Depth > 1.89" for 25-year event

Inflow = 15.11 cfs @ 12.41 hrs, Volume= 1.731 af

Outflow = 15.11 cfs @ 12.41 hrs, Volume= 1.731 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Summary for Pond 1P: CB_1-2

Inflow Area = 0.197 ac, 48.07% Impervious, Inflow Depth > 3.48" for 25-year event

Inflow = 0.76 cfs @ 12.13 hrs, Volume= 0.057 af

Outflow = 0.76 cfs @ 12.13 hrs, Volume= 0.057 af, Atten= 0%, Lag= 0.0 min

Primary = 0.76 cfs @ 12.13 hrs, Volume= 0.057 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 311.91' @ 12.13 hrs

Flood Elev= 316.00'

Device	Routing	Invert	Outlet Devices
#1	Primary	311.50'	15.0" Round Culvert L= 128.7' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 311.50' / 298.95' S= 0.0975 ' / ' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf

Primary OutFlow Max=0.74 cfs @ 12.13 hrs HW=311.90' (Free Discharge)↑ **1=Culvert** (Inlet Controls 0.74 cfs @ 2.16 fps)

Proposed Conditions

Type III 24-hr 25-year Rainfall=6.05"

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 43

Summary for Pond 2P: CB_3-4

Inflow Area = 0.503 ac, 50.95% Impervious, Inflow Depth > 3.99" for 25-year event
 Inflow = 2.19 cfs @ 12.03 hrs, Volume= 0.167 af
 Outflow = 2.19 cfs @ 12.03 hrs, Volume= 0.167 af, Atten= 0%, Lag= 0.0 min
 Primary = 2.19 cfs @ 12.03 hrs, Volume= 0.167 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 299.58' @ 12.03 hrs

Flood Elev= 303.30'

Device	Routing	Invert	Outlet Devices
#1	Primary	298.85'	15.0" Round Culvert L= 131.1' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 298.85' / 286.60' S= 0.0934 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf

Primary OutFlow Max=2.13 cfs @ 12.03 hrs HW=299.57' (Free Discharge)↑**1=Culvert** (Inlet Controls 2.13 cfs @ 2.90 fps)**Summary for Pond 3P: CB_5-6**

Inflow Area = 1.070 ac, 42.21% Impervious, Inflow Depth > 3.47" for 25-year event
 Inflow = 4.09 cfs @ 12.06 hrs, Volume= 0.309 af
 Outflow = 4.09 cfs @ 12.06 hrs, Volume= 0.309 af, Atten= 0%, Lag= 0.0 min
 Primary = 4.09 cfs @ 12.06 hrs, Volume= 0.309 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 287.60' @ 12.06 hrs

Flood Elev= 291.00'

Device	Routing	Invert	Outlet Devices
#1	Primary	286.50'	15.0" Round Culvert L= 168.9' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 286.50' / 272.60' S= 0.0823 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf

Primary OutFlow Max=4.02 cfs @ 12.06 hrs HW=287.59' (Free Discharge)↑**1=Culvert** (Inlet Controls 4.02 cfs @ 3.55 fps)**Summary for Pond 4P: CB_7-8**

Inflow Area = 2.671 ac, 42.88% Impervious, Inflow Depth > 3.25" for 25-year event
 Inflow = 10.85 cfs @ 12.04 hrs, Volume= 0.723 af
 Outflow = 10.85 cfs @ 12.04 hrs, Volume= 0.723 af, Atten= 0%, Lag= 0.0 min
 Primary = 10.85 cfs @ 12.04 hrs, Volume= 0.723 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Proposed Conditions

Type III 24-hr 25-year Rainfall=6.05"

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 44

Peak Elev= 276.49' @ 12.04 hrs

Flood Elev= 277.00'

Device	Routing	Invert	Outlet Devices
#1	Primary	272.50'	15.0" Round Culvert L= 128.2' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 272.50' / 263.70' S= 0.0686 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf

Primary OutFlow Max=10.64 cfs @ 12.04 hrs HW=276.37' (Free Discharge)↑**1=Culvert** (Inlet Controls 10.64 cfs @ 8.67 fps)**Summary for Pond 5P: CB-9**

Inflow Area = 3.304 ac, 44.00% Impervious, Inflow Depth > 3.30" for 25-year event
Inflow = 13.79 cfs @ 12.04 hrs, Volume= 0.908 af
Outflow = 13.79 cfs @ 12.04 hrs, Volume= 0.908 af, Atten= 0%, Lag= 0.0 min
Primary = 13.79 cfs @ 12.04 hrs, Volume= 0.908 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 269.65' @ 12.04 hrs

Flood Elev= 267.30'

Device	Routing	Invert	Outlet Devices
#1	Primary	263.60'	15.0" Round Culvert L= 100.6' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 263.60' / 253.10' S= 0.1044 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf

Primary OutFlow Max=13.40 cfs @ 12.04 hrs HW=269.37' (Free Discharge)↑**1=Culvert** (Inlet Controls 13.40 cfs @ 10.92 fps)**Summary for Pond 6P: CB_10-11**

Inflow Area = 4.390 ac, 44.11% Impervious, Inflow Depth > 3.30" for 25-year event
Inflow = 18.39 cfs @ 12.04 hrs, Volume= 1.206 af
Outflow = 18.39 cfs @ 12.04 hrs, Volume= 1.206 af, Atten= 0%, Lag= 0.0 min
Primary = 18.39 cfs @ 12.04 hrs, Volume= 1.206 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 258.42' @ 12.05 hrs

Flood Elev= 259.50'

Device	Routing	Invert	Outlet Devices
#1	Primary	253.00'	18.0" Round Culvert L= 172.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 253.00' / 245.10' S= 0.0459 '/' Cc= 0.900 n= 0.012, Flow Area= 1.77 sf

Proposed Conditions

Type III 24-hr 25-year Rainfall=6.05"

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 45

Primary OutFlow Max=18.11 cfs @ 12.04 hrs HW=258.28' (Free Discharge)↑**1=Culvert** (Inlet Controls 18.11 cfs @ 10.25 fps)**Summary for Pond 7P: CB_12-13**

Inflow Area = 4.689 ac, 47.32% Impervious, Inflow Depth > 3.42" for 25-year event
 Inflow = 20.20 cfs @ 12.04 hrs, Volume= 1.338 af
 Outflow = 20.20 cfs @ 12.04 hrs, Volume= 1.338 af, Atten= 0%, Lag= 0.0 min
 Primary = 20.20 cfs @ 12.04 hrs, Volume= 1.338 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 251.37' @ 12.04 hrs

Flood Elev= 249.60'

Device	Routing	Invert	Outlet Devices
#1	Primary	245.00'	18.0" Round Culvert L= 36.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 245.00' / 244.00' S= 0.0278 '/' Cc= 0.900 n= 0.012, Flow Area= 1.77 sf

Primary OutFlow Max=19.77 cfs @ 12.04 hrs HW=251.15' (Free Discharge)↑**1=Culvert** (Inlet Controls 19.77 cfs @ 11.19 fps)**Summary for Pond 10P: Stormwater Basin**

Inflow Area = 5.461 ac, 40.63% Impervious, Inflow Depth > 3.17" for 25-year event
 Inflow = 20.63 cfs @ 12.04 hrs, Volume= 1.441 af
 Outflow = 5.54 cfs @ 12.44 hrs, Volume= 1.328 af, Atten= 73%, Lag= 23.9 min
 Discarded = 0.89 cfs @ 12.44 hrs, Volume= 0.597 af
 Primary = 4.65 cfs @ 12.44 hrs, Volume= 0.731 af
 Secondary = 0.00 cfs @ 5.00 hrs, Volume= 0.000 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 245.52' @ 12.44 hrs Surf.Area= 8,518 sf Storage= 23,126 cf

Plug-Flow detention time= 85.6 min calculated for 1.324 af (92% of inflow)

Center-of-Mass det. time= 58.6 min (840.7 - 782.1)

Volume	Invert	Avail.Storage	Storage Description
#1	242.00'	46,796 cf	Custom Stage Data (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
242.00	4,270	0	0
244.00	7,051	11,321	11,321
246.00	8,985	16,036	27,357
248.00	10,454	19,439	46,796

Proposed Conditions

Type III 24-hr 25-year Rainfall=6.05"

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 46

Device	Routing	Invert	Outlet Devices
#1	Primary	242.50'	15.0" Round Culvert L= 100.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 242.50' / 242.00' S= 0.0050 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf
#2	Device 1	243.00'	4.0" Vert. Orifice/Grate C= 0.600
#3	Device 1	243.50'	6.0" Vert. Orifice/Grate C= 0.600
#4	Device 1	244.00'	10.0" Vert. Orifice/Grate C= 0.600
#5	Device 1	246.50'	36.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#6	Secondary	247.00'	18.0' long x 2.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 Coef. (English) 2.54 2.61 2.61 2.60 2.66 2.70 2.77 2.89 2.88 2.85 3.07 3.20 3.32
#7	Discarded	242.00'	4.500 in/hr Exfiltration over Horizontal area

Discarded OutFlow Max=0.89 cfs @ 12.44 hrs HW=245.52' (Free Discharge)↑ **7=Exfiltration** (Exfiltration Controls 0.89 cfs)**Primary OutFlow** Max=4.65 cfs @ 12.44 hrs HW=245.52' (Free Discharge)
↑ **1=Culvert** (Passes 4.65 cfs of 7.94 cfs potential flow)
↑ **2=Orifice/Grate** (Orifice Controls 0.64 cfs @ 7.38 fps)
↑ **3=Orifice/Grate** (Orifice Controls 1.26 cfs @ 6.40 fps)
↑ **4=Orifice/Grate** (Orifice Controls 2.75 cfs @ 5.05 fps)
↑ **5=Orifice/Grate** (Controls 0.00 cfs)
Secondary OutFlow Max=0.00 cfs @ 5.00 hrs HW=242.00' (Free Discharge)↑ **6=Broad-Crested Rectangular Weir** (Controls 0.00 cfs)**Summary for Link 1L: Wetlands Drainage**
Inflow Area = 5.540 ac, 1.13% Impervious, Inflow Depth > 2.17" for 25-year event
Inflow = 10.47 cfs @ 12.40 hrs, Volume= 1.000 af
Primary = 10.47 cfs @ 12.40 hrs, Volume= 1.000 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

25-year Outflow Imported from Proposed Wetlands Drainage~Reach 2R.hce

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 50-year Rainfall=6.85"
Printed 2/4/2021
Page 47

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Drainage Area 1 Runoff Area=8,570 sf 48.07% Impervious Runoff Depth>4.17"
Flow Length=111' Slope=0.0710 '/' Tc=9.1 min CN=79 Runoff=0.90 cfs 0.068 af

Subcatchment 2S: Drainage Area 2 Runoff Area=13,320 sf 52.80% Impervious Runoff Depth>5.05"
Flow Length=125' Slope=0.0100 '/' Tc=1.0 min CN=87 Runoff=2.05 cfs 0.129 af

Subcatchment 3S: Drainage Area 3 Runoff Area=24,738 sf 34.48% Impervious Runoff Depth>3.65"
Flow Length=265' Tc=5.7 min CN=74 Runoff=2.57 cfs 0.173 af

Subcatchment 4S: Drainage Area 4 Runoff Area=69,700 sf 43.33% Impervious Runoff Depth>3.76"
Flow Length=130' Slope=0.0100 '/' Tc=1.9 min CN=75 Runoff=8.25 cfs 0.501 af

Subcatchment 5S: Drainage Area 5 Runoff Area=27,597 sf 48.74% Impervious Runoff Depth>4.18"
Flow Length=180' Slope=0.0500 '/' Tc=1.3 min CN=79 Runoff=3.61 cfs 0.221 af

Subcatchment 6S: Drainage Area 6 Runoff Area=47,315 sf 44.44% Impervious Runoff Depth>3.97"
Flow Length=180' Slope=0.0500 '/' Tc=3.9 min CN=77 Runoff=5.67 cfs 0.359 af

Subcatchment 7S: Drainage Area 7 Runoff Area=13,011 sf 94.50% Impervious Runoff Depth>6.03"
Flow Length=175' Slope=0.0580 '/' Tc=1.2 min CN=97 Runoff=2.21 cfs 0.150 af

Subcatchment 8S: Overland to Swales Runoff Area=33,644 sf 0.00% Impervious Runoff Depth>2.11"
Flow Length=130' Slope=0.1240 '/' Tc=8.3 min CN=58 Runoff=1.79 cfs 0.136 af

Reach 3R: Riprap Swale Avg. Flow Depth=0.15' Max Vel=2.75 fps Inflow=1.79 cfs 0.136 af
n=0.045 L=210.0' S=0.0952 '/' Capacity=48.58 cfs Outflow=1.74 cfs 0.135 af

Reach 4R: Grass swale to basin Avg. Flow Depth=0.16' Max Vel=2.47 fps Inflow=1.74 cfs 0.135 af
n=0.035 L=205.0' S=0.0439 '/' Capacity=42.41 cfs Outflow=1.69 cfs 0.135 af

Reach 9R: Peak off Site Inflow=18.90 cfs 2.232 af
Outflow=18.90 cfs 2.232 af

Pond 1P: CB_1-2 Peak Elev=311.95' Inflow=0.90 cfs 0.068 af
15.0" Round Culvert n=0.012 L=128.7' S=0.0975 '/' Outflow=0.90 cfs 0.068 af

Pond 2P: CB_3-4 Peak Elev=299.66' Inflow=2.55 cfs 0.197 af
15.0" Round Culvert n=0.012 L=131.1' S=0.0934 '/' Outflow=2.55 cfs 0.197 af

Pond 3P: CB_5-6 Peak Elev=287.80' Inflow=4.88 cfs 0.370 af
15.0" Round Culvert n=0.012 L=168.9' S=0.0823 '/' Outflow=4.88 cfs 0.370 af

Pond 4P: CB_7-8 Peak Elev=277.97' Inflow=13.02 cfs 0.871 af
15.0" Round Culvert n=0.012 L=128.2' S=0.0686 '/' Outflow=13.02 cfs 0.871 af

Pond 5P: CB-9 Peak Elev=272.00' Inflow=16.51 cfs 1.092 af
15.0" Round Culvert n=0.012 L=100.6' S=0.1044 '/' Outflow=16.51 cfs 1.092 af

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 50-year Rainfall=6.85"

Printed 2/4/2021

Page 48

Pond 6P: CB_10-11

Peak Elev=260.44' Inflow=22.02 cfs 1.451 af
18.0" Round Culvert n=0.012 L=172.0' S=0.0459 '/ Outflow=22.02 cfs 1.451 af

Pond 7P: CB_12-13

Peak Elev=253.74' Inflow=24.08 cfs 1.601 af
18.0" Round Culvert n=0.012 L=36.0' S=0.0278 '/ Outflow=24.08 cfs 1.601 af

Pond 10P: Stormwater Basin

Peak Elev=246.10' Storage=28,287 cf Inflow=24.74 cfs 1.736 af
Discarded=0.94 cfs 0.633 af Primary=5.58 cfs 0.974 af Secondary=0.00 cfs 0.000 af Outflow=6.52 cfs 1.608 af

Link 1L:

50-year Outflow Imported from Proposed Wetlands Drainage~Reach 2R.hce Inflow=13.34 cfs 1.257 af
Area= 5.540 ac 1.13% Imperv. Primary=13.34 cfs 1.257 af

Total Runoff Area = 5.461 ac Runoff Volume = 1.737 af Average Runoff Depth = 3.82"
59.37% Pervious = 3.242 ac 40.63% Impervious = 2.219 ac

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC
 HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
 Type III 24-hr 50-year Rainfall=6.85"
 Printed 2/4/2021
 Page 49

Summary for Subcatchment 1S: Drainage Area 1

Runoff = 0.90 cfs @ 12.13 hrs, Volume= 0.068 af, Depth> 4.17"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 50-year Rainfall=6.85"

Area (sf)	CN	Description
4,120	98	Paved parking, HSG B
4,450	61	>75% Grass cover, Good, HSG B
8,570	79	Weighted Average
4,450		51.93% Pervious Area
4,120		48.07% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.1	111	0.0710	0.20		Sheet Flow, Tc-1 Grass: Dense n= 0.240 P2= 3.37"

Summary for Subcatchment 2S: Drainage Area 2

Runoff = 2.05 cfs @ 12.01 hrs, Volume= 0.129 af, Depth> 5.05"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 50-year Rainfall=6.85"

Area (sf)	CN	Description
* 6,287	74	>75% Grass cover, Good, HSG B/D
* 7,033	98	Roof/pavement
13,320	87	Weighted Average
6,287		47.20% Pervious Area
7,033		52.80% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.0	125	0.0100	2.03		Shallow Concentrated Flow, Tc-2 Paved Kv= 20.3 fps

Summary for Subcatchment 3S: Drainage Area 3

Runoff = 2.57 cfs @ 12.09 hrs, Volume= 0.173 af, Depth> 3.65"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 50-year Rainfall=6.85"

Proposed Conditions

Type III 24-hr 50-year Rainfall=6.85"

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 50

Area (sf)	CN	Description
* 8,529	98	Paved parking/roof
16,209	61	>75% Grass cover, Good, HSG B
24,738	74	Weighted Average
16,209		65.52% Pervious Area
8,529		34.48% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0	105	0.1100	0.35		Sheet Flow, Tc-4a Grass: Short n= 0.150 P2= 3.37"
0.7	160	0.0310	3.57		Shallow Concentrated Flow, Tc-4b Paved Kv= 20.3 fps
5.7	265	Total			

Summary for Subcatchment 4S: Drainage Area 4

Runoff = 8.25 cfs @ 12.04 hrs, Volume= 0.501 af, Depth> 3.76"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Type III 24-hr 50-year Rainfall=6.85"

Area (sf)	CN	Description
* 30,200	98	Paved parking & roof HSG A
20,000	61	>75% Grass cover, Good, HSG B
19,500	55	Woods, Good, HSG B
69,700	75	Weighted Average
39,500		56.67% Pervious Area
30,200		43.33% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.9	130	0.0100	1.13		Sheet Flow, Tc-3 Smooth surfaces n= 0.011 P2= 3.37"

Summary for Subcatchment 5S: Drainage Area 5

Runoff = 3.61 cfs @ 12.02 hrs, Volume= 0.221 af, Depth> 4.18"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Type III 24-hr 50-year Rainfall=6.85"

Area (sf)	CN	Description
* 13,450	98	Paved surfaces & roof
14,147	61	>75% Grass cover, Good, HSG B
27,597	79	Weighted Average
14,147		51.26% Pervious Area
13,450		48.74% Impervious Area

Proposed Conditions

Type III 24-hr 50-year Rainfall=6.85"

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 51

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.3	180	0.0500	2.29		Sheet Flow, Tc-5 Smooth surfaces n= 0.011 P2= 3.37"

Summary for Subcatchment 6S: Drainage Area 6

Runoff = 5.67 cfs @ 12.06 hrs, Volume= 0.359 af, Depth> 3.97"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 50-year Rainfall=6.85"

Area (sf)	CN	Description
* 21,025	98	Pavement/Roofs, HSG B
22,990	61	>75% Grass cover, Good, HSG B
3,300	55	Woods, Good, HSG B
47,315	77	Weighted Average
26,290		55.56% Pervious Area
21,025		44.44% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.9	180	0.0500	0.76		Lag/CN Method, Tc-6

Summary for Subcatchment 7S: Drainage Area 7

Runoff = 2.21 cfs @ 12.02 hrs, Volume= 0.150 af, Depth> 6.03"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 50-year Rainfall=6.85"

Area (sf)	CN	Description
* 12,295	98	Roof & Pavement
* 716	74	>75% Grass cover, Good, HSG B/D
13,011	97	Weighted Average
716		5.50% Pervious Area
12,295		94.50% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.2	175	0.0580	2.42		Sheet Flow, Tc-7 Smooth surfaces n= 0.011 P2= 3.37"

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 50-year Rainfall=6.85"
Printed 2/4/2021
Page 52

Summary for Subcatchment 8S: Overland to Swales

Runoff = 1.79 cfs @ 12.13 hrs, Volume= 0.136 af, Depth> 2.11"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 50-year Rainfall=6.85"

Area (sf)	CN	Description
* 33,644	58	>75% Grass cover, Good, HSG B
33,644		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.3	130	0.1240	0.26		Sheet Flow, Tc=8 Grass: Dense n= 0.240 P2= 3.37"

Summary for Reach 3R: Riprap Swale

Inflow Area = 0.772 ac, 0.00% Impervious, Inflow Depth > 2.11" for 50-year event
Inflow = 1.79 cfs @ 12.13 hrs, Volume= 0.136 af
Outflow = 1.74 cfs @ 12.17 hrs, Volume= 0.135 af, Atten= 3%, Lag= 2.4 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Max. Velocity= 2.75 fps, Min. Travel Time= 1.3 min
Avg. Velocity= 0.98 fps, Avg. Travel Time= 3.6 min

Peak Storage= 137 cf @ 12.15 hrs
Average Depth at Peak Storage= 0.15'
Bank-Full Depth= 1.00' Flow Area= 6.0 sf, Capacity= 48.58 cfs

4.00' x 1.00' deep channel, n= 0.045
Side Slope Z-value= 2.0 '/' Top Width= 8.00'
Length= 210.0' Slope= 0.0952 '/'
Inlet Invert= 276.00', Outlet Invert= 256.00'



Summary for Reach 4R: Grass swale to basin

Inflow Area = 0.772 ac, 0.00% Impervious, Inflow Depth > 2.10" for 50-year event
Inflow = 1.74 cfs @ 12.17 hrs, Volume= 0.135 af
Outflow = 1.69 cfs @ 12.21 hrs, Volume= 0.135 af, Atten= 3%, Lag= 2.6 min

Proposed Conditions

Type III 24-hr 50-year Rainfall=6.85"

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 53

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Max. Velocity= 2.47 fps, Min. Travel Time= 1.4 min

Avg. Velocity = 0.90 fps, Avg. Travel Time= 3.8 min

Peak Storage= 142 cf @ 12.19 hrs

Average Depth at Peak Storage= 0.16'

Bank-Full Depth= 1.00' Flow Area= 6.0 sf, Capacity= 42.41 cfs

4.00' x 1.00' deep channel, n= 0.035

Side Slope Z-value= 2.0 ' / ' Top Width= 8.00'

Length= 205.0' Slope= 0.0439 ' / '

Inlet Invert= 256.00', Outlet Invert= 247.00'

**Summary for Reach 9R: Peak off Site**

Inflow Area = 11.002 ac, 20.74% Impervious, Inflow Depth > 2.43" for 50-year event

Inflow = 18.90 cfs @ 12.39 hrs, Volume= 2.232 af

Outflow = 18.90 cfs @ 12.39 hrs, Volume= 2.232 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Summary for Pond 1P: CB_1-2

Inflow Area = 0.197 ac, 48.07% Impervious, Inflow Depth > 4.17" for 50-year event

Inflow = 0.90 cfs @ 12.13 hrs, Volume= 0.068 af

Outflow = 0.90 cfs @ 12.13 hrs, Volume= 0.068 af, Atten= 0%, Lag= 0.0 min

Primary = 0.90 cfs @ 12.13 hrs, Volume= 0.068 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 311.95' @ 12.13 hrs

Flood Elev= 316.00'

Device	Routing	Invert	Outlet Devices
#1	Primary	311.50'	15.0" Round Culvert L= 128.7' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 311.50' / 298.95' S= 0.0975 ' / ' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf

Primary OutFlow Max=0.88 cfs @ 12.13 hrs HW=311.94' (Free Discharge)↑ **1=Culvert** (Inlet Controls 0.88 cfs @ 2.26 fps)

Proposed Conditions

Type III 24-hr 50-year Rainfall=6.85"

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 54

Summary for Pond 2P: CB_3-4

Inflow Area = 0.503 ac, 50.95% Impervious, Inflow Depth > 4.70" for 50-year event
 Inflow = 2.55 cfs @ 12.03 hrs, Volume= 0.197 af
 Outflow = 2.55 cfs @ 12.03 hrs, Volume= 0.197 af, Atten= 0%, Lag= 0.0 min
 Primary = 2.55 cfs @ 12.03 hrs, Volume= 0.197 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 299.66' @ 12.03 hrs

Flood Elev= 303.30'

Device	Routing	Invert	Outlet Devices
#1	Primary	298.85'	15.0" Round Culvert L= 131.1' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 298.85' / 286.60' S= 0.0934 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf

Primary OutFlow Max=2.49 cfs @ 12.03 hrs HW=299.64' (Free Discharge)↑**1=Culvert** (Inlet Controls 2.49 cfs @ 3.03 fps)**Summary for Pond 3P: CB_5-6**

Inflow Area = 1.070 ac, 42.21% Impervious, Inflow Depth > 4.15" for 50-year event
 Inflow = 4.88 cfs @ 12.06 hrs, Volume= 0.370 af
 Outflow = 4.88 cfs @ 12.06 hrs, Volume= 0.370 af, Atten= 0%, Lag= 0.0 min
 Primary = 4.88 cfs @ 12.06 hrs, Volume= 0.370 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 287.80' @ 12.06 hrs

Flood Elev= 291.00'

Device	Routing	Invert	Outlet Devices
#1	Primary	286.50'	15.0" Round Culvert L= 168.9' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 286.50' / 272.60' S= 0.0823 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf

Primary OutFlow Max=4.78 cfs @ 12.06 hrs HW=287.78' (Free Discharge)↑**1=Culvert** (Inlet Controls 4.78 cfs @ 3.89 fps)**Summary for Pond 4P: CB_7-8**

Inflow Area = 2.671 ac, 42.88% Impervious, Inflow Depth > 3.91" for 50-year event
 Inflow = 13.02 cfs @ 12.04 hrs, Volume= 0.871 af
 Outflow = 13.02 cfs @ 12.04 hrs, Volume= 0.871 af, Atten= 0%, Lag= 0.0 min
 Primary = 13.02 cfs @ 12.04 hrs, Volume= 0.871 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Proposed Conditions

Type III 24-hr 50-year Rainfall=6.85"

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 55

Peak Elev= 277.97' @ 12.04 hrs

Flood Elev= 277.00'

Device	Routing	Invert	Outlet Devices
#1	Primary	272.50'	15.0" Round Culvert L= 128.2' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 272.50' / 263.70' S= 0.0686 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf

Primary OutFlow Max=12.75 cfs @ 12.04 hrs HW=277.78' (Free Discharge)↑**1=Culvert** (Inlet Controls 12.75 cfs @ 10.39 fps)**Summary for Pond 5P: CB-9**

Inflow Area = 3.304 ac, 44.00% Impervious, Inflow Depth > 3.97" for 50-year event
Inflow = 16.51 cfs @ 12.04 hrs, Volume= 1.092 af
Outflow = 16.51 cfs @ 12.04 hrs, Volume= 1.092 af, Atten= 0%, Lag= 0.0 min
Primary = 16.51 cfs @ 12.04 hrs, Volume= 1.092 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 272.00' @ 12.04 hrs

Flood Elev= 267.30'

Device	Routing	Invert	Outlet Devices
#1	Primary	263.60'	15.0" Round Culvert L= 100.6' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 263.60' / 253.10' S= 0.1044 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf

Primary OutFlow Max=16.03 cfs @ 12.04 hrs HW=271.58' (Free Discharge)↑**1=Culvert** (Inlet Controls 16.03 cfs @ 13.06 fps)**Summary for Pond 6P: CB_10-11**

Inflow Area = 4.390 ac, 44.11% Impervious, Inflow Depth > 3.97" for 50-year event
Inflow = 22.02 cfs @ 12.04 hrs, Volume= 1.451 af
Outflow = 22.02 cfs @ 12.04 hrs, Volume= 1.451 af, Atten= 0%, Lag= 0.0 min
Primary = 22.02 cfs @ 12.04 hrs, Volume= 1.451 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 260.44' @ 12.04 hrs

Flood Elev= 259.50'

Device	Routing	Invert	Outlet Devices
#1	Primary	253.00'	18.0" Round Culvert L= 172.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 253.00' / 245.10' S= 0.0459 '/' Cc= 0.900 n= 0.012, Flow Area= 1.77 sf

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 50-year Rainfall=6.85"
Printed 2/4/2021
Page 56

Primary OutFlow Max=21.66 cfs @ 12.04 hrs HW=260.23' (Free Discharge)

↑**1=Culvert** (Inlet Controls 21.66 cfs @ 12.26 fps)

Summary for Pond 7P: CB_12-13

Inflow Area = 4.689 ac, 47.32% Impervious, Inflow Depth > 4.10" for 50-year event
Inflow = 24.08 cfs @ 12.04 hrs, Volume= 1.601 af
Outflow = 24.08 cfs @ 12.04 hrs, Volume= 1.601 af, Atten= 0%, Lag= 0.0 min
Primary = 24.08 cfs @ 12.04 hrs, Volume= 1.601 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 253.74' @ 12.04 hrs

Flood Elev= 249.60'

Device	Routing	Invert	Outlet Devices
#1	Primary	245.00'	18.0" Round Culvert L= 36.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 245.00' / 244.00' S= 0.0278 '/' Cc= 0.900 n= 0.012, Flow Area= 1.77 sf

Primary OutFlow Max=23.55 cfs @ 12.04 hrs HW=253.41' (Free Discharge)

↑**1=Culvert** (Inlet Controls 23.55 cfs @ 13.33 fps)

Summary for Pond 10P: Stormwater Basin

Inflow Area = 5.461 ac, 40.63% Impervious, Inflow Depth > 3.81" for 50-year event
Inflow = 24.74 cfs @ 12.04 hrs, Volume= 1.736 af
Outflow = 6.52 cfs @ 12.44 hrs, Volume= 1.608 af, Atten= 74%, Lag= 24.1 min
Discarded = 0.94 cfs @ 12.44 hrs, Volume= 0.633 af
Primary = 5.58 cfs @ 12.44 hrs, Volume= 0.974 af
Secondary = 0.00 cfs @ 5.00 hrs, Volume= 0.000 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 246.10' @ 12.44 hrs Surf.Area= 9,061 sf Storage= 28,287 cf

Plug-Flow detention time= 82.4 min calculated for 1.608 af (93% of inflow)

Center-of-Mass det. time= 56.5 min (835.0 - 778.6)

Volume	Invert	Avail.Storage	Storage Description
#1	242.00'	46,796 cf	Custom Stage Data (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
242.00	4,270	0	0
244.00	7,051	11,321	11,321
246.00	8,985	16,036	27,357
248.00	10,454	19,439	46,796

Proposed Conditions

Type III 24-hr 50-year Rainfall=6.85"

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 57

Device	Routing	Invert	Outlet Devices
#1	Primary	242.50'	15.0" Round Culvert L= 100.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 242.50' / 242.00' S= 0.0050 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf
#2	Device 1	243.00'	4.0" Vert. Orifice/Grate C= 0.600
#3	Device 1	243.50'	6.0" Vert. Orifice/Grate C= 0.600
#4	Device 1	244.00'	10.0" Vert. Orifice/Grate C= 0.600
#5	Device 1	246.50'	36.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#6	Secondary	247.00'	18.0' long x 2.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 Coef. (English) 2.54 2.61 2.61 2.60 2.66 2.70 2.77 2.89 2.88 2.85 3.07 3.20 3.32
#7	Discarded	242.00'	4.500 in/hr Exfiltration over Horizontal area

Discarded OutFlow Max=0.94 cfs @ 12.44 hrs HW=246.10' (Free Discharge)↑ **7=Exfiltration** (Exfiltration Controls 0.94 cfs)**Primary OutFlow** Max=5.58 cfs @ 12.44 hrs HW=246.10' (Free Discharge)
↑ **1=Culvert** (Passes 5.58 cfs of 8.91 cfs potential flow)
↑ **2=Orifice/Grate** (Orifice Controls 0.72 cfs @ 8.25 fps)
↑ **3=Orifice/Grate** (Orifice Controls 1.45 cfs @ 7.38 fps)
↑ **4=Orifice/Grate** (Orifice Controls 3.41 cfs @ 6.25 fps)
↑ **5=Orifice/Grate** (Controls 0.00 cfs)
Secondary OutFlow Max=0.00 cfs @ 5.00 hrs HW=242.00' (Free Discharge)↑ **6=Broad-Crested Rectangular Weir** (Controls 0.00 cfs)**Summary for Link 1L: Wetlands Drainage**
Inflow Area = 5.540 ac, 1.13% Impervious, Inflow Depth > 2.72" for 50-year event
Inflow = 13.34 cfs @ 12.39 hrs, Volume= 1.257 af
Primary = 13.34 cfs @ 12.39 hrs, Volume= 1.257 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

50-year Outflow Imported from Proposed Wetlands Drainage~Reach 2R.hce

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 100-year Rainfall=7.64"

Printed 2/4/2021

Page 58

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points

Runoff by SCS TR-20 method, UH=SCS

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Drainage Area 1 Runoff Area=8,570 sf 48.07% Impervious Runoff Depth>4.86"
Flow Length=111' Slope=0.0710 '/' Tc=9.1 min CN=79 Runoff=1.04 cfs 0.080 af

Subcatchment 2S: Drainage Area 2 Runoff Area=13,320 sf 52.80% Impervious Runoff Depth>5.77"
Flow Length=125' Slope=0.0100 '/' Tc=1.0 min CN=87 Runoff=2.33 cfs 0.147 af

Subcatchment 3S: Drainage Area 3 Runoff Area=24,738 sf 34.48% Impervious Runoff Depth>4.31"
Flow Length=265' Tc=5.7 min CN=74 Runoff=3.02 cfs 0.204 af

Subcatchment 4S: Drainage Area 4 Runoff Area=69,700 sf 43.33% Impervious Runoff Depth>4.42"
Flow Length=130' Slope=0.0100 '/' Tc=1.9 min CN=75 Runoff=9.65 cfs 0.590 af

Subcatchment 5S: Drainage Area 5 Runoff Area=27,597 sf 48.74% Impervious Runoff Depth>4.87"
Flow Length=180' Slope=0.0500 '/' Tc=1.3 min CN=79 Runoff=4.18 cfs 0.257 af

Subcatchment 6S: Drainage Area 6 Runoff Area=47,315 sf 44.44% Impervious Runoff Depth>4.64"
Flow Length=180' Slope=0.0500 '/' Tc=3.9 min CN=77 Runoff=6.60 cfs 0.420 af

Subcatchment 7S: Drainage Area 7 Runoff Area=13,011 sf 94.50% Impervious Runoff Depth>6.75"
Flow Length=175' Slope=0.0580 '/' Tc=1.2 min CN=97 Runoff=2.47 cfs 0.168 af

Subcatchment 8S: Overland to Swales Runoff Area=33,644 sf 0.00% Impervious Runoff Depth>2.62"
Flow Length=130' Slope=0.1240 '/' Tc=8.3 min CN=58 Runoff=2.26 cfs 0.168 af

Reach 3R: Riprap Swale Avg. Flow Depth=0.17' Max Vel=2.98 fps Inflow=2.26 cfs 0.168 af
n=0.045 L=210.0' S=0.0952 '/' Capacity=48.58 cfs Outflow=2.20 cfs 0.168 af

Reach 4R: Grass swale to basin Avg. Flow Depth=0.18' Max Vel=2.68 fps Inflow=2.20 cfs 0.168 af
n=0.035 L=205.0' S=0.0439 '/' Capacity=42.41 cfs Outflow=2.13 cfs 0.167 af

Reach 9R: Peak off Site Inflow=24.03 cfs 2.750 af
Outflow=24.03 cfs 2.750 af

Pond 1P: CB_1-2 Peak Elev=311.98' Inflow=1.04 cfs 0.080 af
15.0" Round Culvert n=0.012 L=128.7' S=0.0975 '/' Outflow=1.04 cfs 0.080 af

Pond 2P: CB_3-4 Peak Elev=299.72' Inflow=2.91 cfs 0.227 af
15.0" Round Culvert n=0.012 L=131.1' S=0.0934 '/' Outflow=2.91 cfs 0.227 af

Pond 3P: CB_5-6 Peak Elev=288.04' Inflow=5.66 cfs 0.431 af
15.0" Round Culvert n=0.012 L=168.9' S=0.0823 '/' Outflow=5.66 cfs 0.431 af

Pond 4P: CB_7-8 Peak Elev=279.71' Inflow=15.18 cfs 1.021 af
15.0" Round Culvert n=0.012 L=128.2' S=0.0686 '/' Outflow=15.18 cfs 1.021 af

Pond 5P: CB-9 Peak Elev=274.76' Inflow=19.22 cfs 1.278 af
15.0" Round Culvert n=0.012 L=100.6' S=0.1044 '/' Outflow=19.22 cfs 1.278 af

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 100-year Rainfall=7.64"

Printed 2/4/2021

Page 59

Pond 6P: CB_10-11

Peak Elev=262.82' Inflow=25.64 cfs 1.698 af
18.0" Round Culvert n=0.012 L=172.0' S=0.0459 '/ Outflow=25.64 cfs 1.698 af

Pond 7P: CB_12-13

Peak Elev=256.51' Inflow=27.94 cfs 1.866 af
18.0" Round Culvert n=0.012 L=36.0' S=0.0278 '/ Outflow=27.94 cfs 1.866 af

Pond 10P: Stormwater Basin

Peak Elev=246.63' Storage=33,197 cf Inflow=28.85 cfs 2.034 af
Discarded=0.98 cfs 0.667 af Primary=7.82 cfs 1.226 af Secondary=0.00 cfs 0.000 af Outflow=8.81 cfs 1.893 af

Link 1L:

100-year Outflow Imported from Proposed Wetlands Drainage~Reach 2R.hce Inflow=16.37 cfs 1.524 af
Area= 5.540 ac 1.13% Imperv. Primary=16.37 cfs 1.524 af

Total Runoff Area = 5.461 ac Runoff Volume = 2.035 af Average Runoff Depth = 4.47"
59.37% Pervious = 3.242 ac 40.63% Impervious = 2.219 ac

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC
 HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
 Type III 24-hr 100-year Rainfall=7.64"
 Printed 2/4/2021
 Page 60

Summary for Subcatchment 1S: Drainage Area 1

Runoff = 1.04 cfs @ 12.13 hrs, Volume= 0.080 af, Depth> 4.86"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 100-year Rainfall=7.64"

Area (sf)	CN	Description
4,120	98	Paved parking, HSG B
4,450	61	>75% Grass cover, Good, HSG B
8,570	79	Weighted Average
4,450		51.93% Pervious Area
4,120		48.07% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.1	111	0.0710	0.20		Sheet Flow, Tc-1 Grass: Dense n= 0.240 P2= 3.37"

Summary for Subcatchment 2S: Drainage Area 2

Runoff = 2.33 cfs @ 12.01 hrs, Volume= 0.147 af, Depth> 5.77"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 100-year Rainfall=7.64"

Area (sf)	CN	Description
* 6,287	74	>75% Grass cover, Good, HSG B/D
* 7,033	98	Roof/pavement
13,320	87	Weighted Average
6,287		47.20% Pervious Area
7,033		52.80% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.0	125	0.0100	2.03		Shallow Concentrated Flow, Tc-2 Paved Kv= 20.3 fps

Summary for Subcatchment 3S: Drainage Area 3

Runoff = 3.02 cfs @ 12.09 hrs, Volume= 0.204 af, Depth> 4.31"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 100-year Rainfall=7.64"

Proposed Conditions

Type III 24-hr 100-year Rainfall=7.64"

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 61

	Area (sf)	CN	Description
*	8,529	98	Paved parking/roof
	16,209	61	>75% Grass cover, Good, HSG B
	24,738	74	Weighted Average
	16,209		65.52% Pervious Area
	8,529		34.48% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0	105	0.1100	0.35		Sheet Flow, Tc-4a Grass: Short n= 0.150 P2= 3.37"
0.7	160	0.0310	3.57		Shallow Concentrated Flow, Tc-4b Paved Kv= 20.3 fps
5.7	265	Total			

Summary for Subcatchment 4S: Drainage Area 4

Runoff = 9.65 cfs @ 12.04 hrs, Volume= 0.590 af, Depth> 4.42"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Type III 24-hr 100-year Rainfall=7.64"

	Area (sf)	CN	Description
*	30,200	98	Paved parking & roof HSG A
	20,000	61	>75% Grass cover, Good, HSG B
	19,500	55	Woods, Good, HSG B
	69,700	75	Weighted Average
	39,500		56.67% Pervious Area
	30,200		43.33% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.9	130	0.0100	1.13		Sheet Flow, Tc-3 Smooth surfaces n= 0.011 P2= 3.37"

Summary for Subcatchment 5S: Drainage Area 5

Runoff = 4.18 cfs @ 12.02 hrs, Volume= 0.257 af, Depth> 4.87"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Type III 24-hr 100-year Rainfall=7.64"

	Area (sf)	CN	Description
*	13,450	98	Paved surfaces & roof
	14,147	61	>75% Grass cover, Good, HSG B
	27,597	79	Weighted Average
	14,147		51.26% Pervious Area
	13,450		48.74% Impervious Area

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC
 HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
 Type III 24-hr 100-year Rainfall=7.64"
 Printed 2/4/2021
 Page 62

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.3	180	0.0500	2.29		Sheet Flow, Tc-5 Smooth surfaces n= 0.011 P2= 3.37"

Summary for Subcatchment 6S: Drainage Area 6

Runoff = 6.60 cfs @ 12.06 hrs, Volume= 0.420 af, Depth> 4.64"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 100-year Rainfall=7.64"

Area (sf)	CN	Description
* 21,025	98	Pavement/Roofs, HSG B
22,990	61	>75% Grass cover, Good, HSG B
3,300	55	Woods, Good, HSG B
47,315	77	Weighted Average
26,290		55.56% Pervious Area
21,025		44.44% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.9	180	0.0500	0.76		Lag/CN Method, Tc-6

Summary for Subcatchment 7S: Drainage Area 7

Runoff = 2.47 cfs @ 12.02 hrs, Volume= 0.168 af, Depth> 6.75"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 100-year Rainfall=7.64"

Area (sf)	CN	Description
* 12,295	98	Roof & Pavement
* 716	74	>75% Grass cover, Good, HSG B/D
13,011	97	Weighted Average
716		5.50% Pervious Area
12,295		94.50% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.2	175	0.0580	2.42		Sheet Flow, Tc-7 Smooth surfaces n= 0.011 P2= 3.37"

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 100-year Rainfall=7.64"
Printed 2/4/2021
Page 63

Summary for Subcatchment 8S: Overland to Swales

Runoff = 2.26 cfs @ 12.13 hrs, Volume= 0.168 af, Depth> 2.62"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 100-year Rainfall=7.64"

Area (sf)	CN	Description
* 33,644	58	>75% Grass cover, Good, HSG B
33,644		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.3	130	0.1240	0.26		Sheet Flow, Tc=8 Grass: Dense n= 0.240 P2= 3.37"

Summary for Reach 3R: Riprap Swale

Inflow Area = 0.772 ac, 0.00% Impervious, Inflow Depth > 2.62" for 100-year event
Inflow = 2.26 cfs @ 12.13 hrs, Volume= 0.168 af
Outflow = 2.20 cfs @ 12.16 hrs, Volume= 0.168 af, Atten= 3%, Lag= 2.2 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Max. Velocity= 2.98 fps, Min. Travel Time= 1.2 min
Avg. Velocity= 1.04 fps, Avg. Travel Time= 3.4 min

Peak Storage= 159 cf @ 12.14 hrs
Average Depth at Peak Storage= 0.17'
Bank-Full Depth= 1.00' Flow Area= 6.0 sf, Capacity= 48.58 cfs

4.00' x 1.00' deep channel, n= 0.045
Side Slope Z-value= 2.0 '/' Top Width= 8.00'
Length= 210.0' Slope= 0.0952 '/'
Inlet Invert= 276.00', Outlet Invert= 256.00'



Summary for Reach 4R: Grass swale to basin

Inflow Area = 0.772 ac, 0.00% Impervious, Inflow Depth > 2.61" for 100-year event
Inflow = 2.20 cfs @ 12.16 hrs, Volume= 0.168 af
Outflow = 2.13 cfs @ 12.20 hrs, Volume= 0.167 af, Atten= 3%, Lag= 2.5 min

Proposed Conditions

Type III 24-hr 100-year Rainfall=7.64"

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 64

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Max. Velocity= 2.68 fps, Min. Travel Time= 1.3 min

Avg. Velocity = 0.96 fps, Avg. Travel Time= 3.6 min

Peak Storage= 165 cf @ 12.18 hrs

Average Depth at Peak Storage= 0.18'

Bank-Full Depth= 1.00' Flow Area= 6.0 sf, Capacity= 42.41 cfs

4.00' x 1.00' deep channel, n= 0.035

Side Slope Z-value= 2.0 '/' Top Width= 8.00'

Length= 205.0' Slope= 0.0439 '/'

Inlet Invert= 256.00', Outlet Invert= 247.00'

**Summary for Reach 9R: Peak off Site**

Inflow Area = 11.002 ac, 20.74% Impervious, Inflow Depth > 3.00" for 100-year event

Inflow = 24.03 cfs @ 12.38 hrs, Volume= 2.750 af

Outflow = 24.03 cfs @ 12.38 hrs, Volume= 2.750 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Summary for Pond 1P: CB_1-2

Inflow Area = 0.197 ac, 48.07% Impervious, Inflow Depth > 4.86" for 100-year event

Inflow = 1.04 cfs @ 12.13 hrs, Volume= 0.080 af

Outflow = 1.04 cfs @ 12.13 hrs, Volume= 0.080 af, Atten= 0%, Lag= 0.0 min

Primary = 1.04 cfs @ 12.13 hrs, Volume= 0.080 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 311.98' @ 12.13 hrs

Flood Elev= 316.00'

Device	Routing	Invert	Outlet Devices
#1	Primary	311.50'	15.0" Round Culvert L= 128.7' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 311.50' / 298.95' S= 0.0975 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf

Primary OutFlow Max=1.02 cfs @ 12.13 hrs HW=311.98' (Free Discharge)↑ **1=Culvert** (Inlet Controls 1.02 cfs @ 2.36 fps)

Proposed Conditions

Type III 24-hr 100-year Rainfall=7.64"

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 65

Summary for Pond 2P: CB_3-4

Inflow Area = 0.503 ac, 50.95% Impervious, Inflow Depth > 5.41" for 100-year event
 Inflow = 2.91 cfs @ 12.03 hrs, Volume= 0.227 af
 Outflow = 2.91 cfs @ 12.03 hrs, Volume= 0.227 af, Atten= 0%, Lag= 0.0 min
 Primary = 2.91 cfs @ 12.03 hrs, Volume= 0.227 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 299.72' @ 12.03 hrs

Flood Elev= 303.30'

Device	Routing	Invert	Outlet Devices
#1	Primary	298.85'	15.0" Round Culvert L= 131.1' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 298.85' / 286.60' S= 0.0934 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf

Primary OutFlow Max=2.85 cfs @ 12.03 hrs HW=299.71' (Free Discharge)↑**1=Culvert** (Inlet Controls 2.85 cfs @ 3.16 fps)**Summary for Pond 3P: CB_5-6**

Inflow Area = 1.070 ac, 42.21% Impervious, Inflow Depth > 4.83" for 100-year event
 Inflow = 5.66 cfs @ 12.06 hrs, Volume= 0.431 af
 Outflow = 5.66 cfs @ 12.06 hrs, Volume= 0.431 af, Atten= 0%, Lag= 0.0 min
 Primary = 5.66 cfs @ 12.06 hrs, Volume= 0.431 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 288.04' @ 12.06 hrs

Flood Elev= 291.00'

Device	Routing	Invert	Outlet Devices
#1	Primary	286.50'	15.0" Round Culvert L= 168.9' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 286.50' / 272.60' S= 0.0823 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf

Primary OutFlow Max=5.55 cfs @ 12.06 hrs HW=288.01' (Free Discharge)↑**1=Culvert** (Inlet Controls 5.55 cfs @ 4.52 fps)**Summary for Pond 4P: CB_7-8**

Inflow Area = 2.671 ac, 42.88% Impervious, Inflow Depth > 4.59" for 100-year event
 Inflow = 15.18 cfs @ 12.04 hrs, Volume= 1.021 af
 Outflow = 15.18 cfs @ 12.04 hrs, Volume= 1.021 af, Atten= 0%, Lag= 0.0 min
 Primary = 15.18 cfs @ 12.04 hrs, Volume= 1.021 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Proposed Conditions

Type III 24-hr 100-year Rainfall=7.64"

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 66

Peak Elev= 279.71' @ 12.04 hrs

Flood Elev= 277.00'

Device	Routing	Invert	Outlet Devices
#1	Primary	272.50'	15.0" Round Culvert L= 128.2' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 272.50' / 263.70' S= 0.0686 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf

Primary OutFlow Max=14.86 cfs @ 12.04 hrs HW=279.45' (Free Discharge)↑**1=Culvert** (Inlet Controls 14.86 cfs @ 12.11 fps)**Summary for Pond 5P: CB-9**

Inflow Area = 3.304 ac, 44.00% Impervious, Inflow Depth > 4.64" for 100-year event
Inflow = 19.22 cfs @ 12.04 hrs, Volume= 1.278 af
Outflow = 19.22 cfs @ 12.04 hrs, Volume= 1.278 af, Atten= 0%, Lag= 0.0 min
Primary = 19.22 cfs @ 12.04 hrs, Volume= 1.278 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 274.76' @ 12.04 hrs

Flood Elev= 267.30'

Device	Routing	Invert	Outlet Devices
#1	Primary	263.60'	15.0" Round Culvert L= 100.6' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 263.60' / 253.10' S= 0.1044 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf

Primary OutFlow Max=18.65 cfs @ 12.04 hrs HW=274.19' (Free Discharge)↑**1=Culvert** (Inlet Controls 18.65 cfs @ 15.20 fps)**Summary for Pond 6P: CB_10-11**

Inflow Area = 4.390 ac, 44.11% Impervious, Inflow Depth > 4.64" for 100-year event
Inflow = 25.64 cfs @ 12.04 hrs, Volume= 1.698 af
Outflow = 25.64 cfs @ 12.04 hrs, Volume= 1.698 af, Atten= 0%, Lag= 0.0 min
Primary = 25.64 cfs @ 12.04 hrs, Volume= 1.698 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 262.82' @ 12.04 hrs

Flood Elev= 259.50'

Device	Routing	Invert	Outlet Devices
#1	Primary	253.00'	18.0" Round Culvert L= 172.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 253.00' / 245.10' S= 0.0459 '/' Cc= 0.900 n= 0.012, Flow Area= 1.77 sf

Proposed Conditions

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock
Type III 24-hr 100-year Rainfall=7.64"
Printed 2/4/2021
Page 67

Primary OutFlow Max=25.20 cfs @ 12.04 hrs HW=262.52' (Free Discharge)

↑**1=Culvert** (Inlet Controls 25.20 cfs @ 14.26 fps)

Summary for Pond 7P: CB_12-13

Inflow Area = 4.689 ac, 47.32% Impervious, Inflow Depth > 4.78" for 100-year event
Inflow = 27.94 cfs @ 12.04 hrs, Volume= 1.866 af
Outflow = 27.94 cfs @ 12.04 hrs, Volume= 1.866 af, Atten= 0%, Lag= 0.0 min
Primary = 27.94 cfs @ 12.04 hrs, Volume= 1.866 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 256.51' @ 12.04 hrs

Flood Elev= 249.60'

Device	Routing	Invert	Outlet Devices
#1	Primary	245.00'	18.0" Round Culvert L= 36.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 245.00' / 244.00' S= 0.0278 '/' Cc= 0.900 n= 0.012, Flow Area= 1.77 sf

Primary OutFlow Max=27.31 cfs @ 12.04 hrs HW=256.05' (Free Discharge)

↑**1=Culvert** (Inlet Controls 27.31 cfs @ 15.45 fps)

Summary for Pond 10P: Stormwater Basin

Inflow Area = 5.461 ac, 40.63% Impervious, Inflow Depth > 4.47" for 100-year event
Inflow = 28.85 cfs @ 12.04 hrs, Volume= 2.034 af
Outflow = 8.81 cfs @ 12.40 hrs, Volume= 1.893 af, Atten= 69%, Lag= 21.7 min
Discarded = 0.98 cfs @ 12.41 hrs, Volume= 0.667 af
Primary = 7.82 cfs @ 12.40 hrs, Volume= 1.226 af
Secondary = 0.00 cfs @ 5.00 hrs, Volume= 0.000 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 246.63' @ 12.41 hrs Surf.Area= 9,450 sf Storage= 33,197 cf

Plug-Flow detention time= 80.1 min calculated for 1.893 af (93% of inflow)

Center-of-Mass det. time= 55.4 min (830.9 - 775.4)

Volume	Invert	Avail.Storage	Storage Description
#1	242.00'	46,796 cf	Custom Stage Data (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
242.00	4,270	0	0
244.00	7,051	11,321	11,321
246.00	8,985	16,036	27,357
248.00	10,454	19,439	46,796

Proposed Conditions

Type III 24-hr 100-year Rainfall=7.64"

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 68


Device	Routing	Invert	Outlet Devices
#1	Primary	242.50'	15.0" Round Culvert L= 100.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 242.50' / 242.00' S= 0.0050 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf
#2	Device 1	243.00'	4.0" Vert. Orifice/Grate C= 0.600
#3	Device 1	243.50'	6.0" Vert. Orifice/Grate C= 0.600
#4	Device 1	244.00'	10.0" Vert. Orifice/Grate C= 0.600
#5	Device 1	246.50'	36.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#6	Secondary	247.00'	18.0' long x 2.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 Coef. (English) 2.54 2.61 2.61 2.60 2.66 2.70 2.77 2.89 2.88 2.85 3.07 3.20 3.32
#7	Discarded	242.00'	4.500 in/hr Exfiltration over Horizontal area

Discarded OutFlow Max=0.98 cfs @ 12.41 hrs HW=246.63' (Free Discharge)↑ **7=Exfiltration** (Exfiltration Controls 0.98 cfs)**Primary OutFlow** Max=7.78 cfs @ 12.40 hrs HW=246.63' (Free Discharge)
 ↑ **1=Culvert** (Passes 7.78 cfs of 9.70 cfs potential flow)
 ↑ **2=Orifice/Grate** (Orifice Controls 0.78 cfs @ 8.96 fps)
 ↑ **3=Orifice/Grate** (Orifice Controls 1.61 cfs @ 8.17 fps)
 ↑ **4=Orifice/Grate** (Orifice Controls 3.91 cfs @ 7.17 fps)
 ↑ **5=Orifice/Grate** (Weir Controls 1.48 cfs @ 1.19 fps)
Secondary OutFlow Max=0.00 cfs @ 5.00 hrs HW=242.00' (Free Discharge)↑ **6=Broad-Crested Rectangular Weir** (Controls 0.00 cfs)**Summary for Link 1L: Wetlands Drainage**


Inflow Area = 5.540 ac, 1.13% Impervious, Inflow Depth > 3.30" for 100-year event
 Inflow = 16.37 cfs @ 12.37 hrs, Volume= 1.524 af
 Primary = 16.37 cfs @ 12.37 hrs, Volume= 1.524 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs


100-year Outflow Imported from Proposed Wetlands Drainage~Reach 2R.hce




Overland to Wetlands





Wetland Swale



Overland to Wetlands



Wetland Swale



Proposed Wetlands Drainage

Prepared by Killingly Engineering Associates, LLC

Printed 2/4/2021

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Page 2

Area Listing (all nodes)

Area (acres)	CN	Description (subcatchment-numbers)
2.735	55	Woods, Good, HSG B (2S', 8S)
0.441	58	>75% Grass cover, Good, HSG B (2S')
1.423	77	Woods, Good, HSG D (8S)
0.880	77	Woods, Good, HSG D - Wetlands (2S')
0.063	98	Roofs, HSG B (2S')
5.540	65	TOTAL AREA

Proposed Wetlands Drainage

Prepared by Killingly Engineering Associates, LLC

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock - Wetlands Drainage Link
Type III 24-hr 2-year Rainfall=3.37"

Printed 2/4/2021

Page 3

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points

Runoff by SCS TR-20 method, UH=SCS

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 2S': Overland to Wetlands

Runoff Area=81,744 sf 3.33% Impervious Runoff Depth>0.70"
Flow Length=200' Slope=0.1100 '/' Tc=12.2 min CN=67 Runoff=1.18 cfs 0.109 af

Subcatchment 8S: Overland to Wetlands

Runoff Area=159,593 sf 0.00% Impervious Runoff Depth>0.57"
Flow Length=152' Slope=0.1240 '/' Tc=14.1 min CN=64 Runoff=1.64 cfs 0.173 af

Reach 1R: Wetland Swale

Avg. Flow Depth=0.08' Max Vel=1.21 fps Inflow=1.18 cfs 0.109 af
n=0.050 L=290.0' S=0.0759 '/' Capacity=1,056.58 cfs Outflow=1.10 cfs 0.108 af

Reach 2R: Wetland Swale

Avg. Flow Depth=0.13' Max Vel=1.25 fps Inflow=2.64 cfs 0.281 af
n=0.050 L=712.0' S=0.0478 '/' Capacity=890.78 cfs Outflow=2.24 cfs 0.276 af

Total Runoff Area = 5.540 ac Runoff Volume = 0.282 af Average Runoff Depth = 0.61"
98.87% Pervious = 5.478 ac 1.13% Impervious = 0.063 ac

Proposed Wetlands Drainage

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock - Wetlands Drainage Link
Type III 24-hr 2-year Rainfall=3.37"
Printed 2/4/2021
Page 4

Summary for Subcatchment 2S': Overland to Wetlands

Runoff = 1.18 cfs @ 12.20 hrs, Volume= 0.109 af, Depth> 0.70"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 2-year Rainfall=3.37"

	Area (sf)	CN	Description
*	38,320	77	Woods, Good, HSG D - Wetlands
	21,500	55	Woods, Good, HSG B
	2,724	98	Roofs, HSG B
*	19,200	58	>75% Grass cover, Good, HSG B
	81,744	67	Weighted Average
	79,020		96.67% Pervious Area
	2,724		3.33% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
12.2	200	0.1100	0.27		Sheet Flow, Tc-2s Grass: Dense n= 0.240 P2= 3.37"

Summary for Subcatchment 8S: Overland to Wetlands

Runoff = 1.64 cfs @ 12.24 hrs, Volume= 0.173 af, Depth> 0.57"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 2-year Rainfall=3.37"

	Area (sf)	CN	Description
	97,618	55	Woods, Good, HSG B
	61,975	77	Woods, Good, HSG D
	159,593	64	Weighted Average
	159,593		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
14.1	152	0.1240	0.18		Sheet Flow, Tc-8 Woods: Light underbrush n= 0.400 P2= 3.37"

Summary for Reach 1R: Wetland Swale

Inflow Area = 1.877 ac, 3.33% Impervious, Inflow Depth > 0.70" for 2-year event
Inflow = 1.18 cfs @ 12.20 hrs, Volume= 0.109 af
Outflow = 1.10 cfs @ 12.32 hrs, Volume= 0.108 af, Atten= 7%, Lag= 7.5 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Max. Velocity= 1.21 fps, Min. Travel Time= 4.0 min
Avg. Velocity= 0.62 fps, Avg. Travel Time= 7.8 min

Proposed Wetlands Drainage

Prepared by Killingly Engineering Associates, LLC

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock - Wetlands Drainage Link
Type III 24-hr 2-year Rainfall=3.37"

Printed 2/4/2021

Page 5

Peak Storage= 267 cf @ 12.26 hrs

Average Depth at Peak Storage= 0.08'

Bank-Full Depth= 2.00' Flow Area= 106.7 sf, Capacity= 1,056.58 cfs

80.00' x 2.00' deep Parabolic Channel, n= 0.050 Scattered brush, heavy weeds

Length= 290.0' Slope= 0.0759 '/'

Inlet Invert= 294.00', Outlet Invert= 272.00'



Summary for Reach 2R: Wetland Swale

Inflow Area = 5.540 ac, 1.13% Impervious, Inflow Depth > 0.61" for 2-year event

Inflow = 2.64 cfs @ 12.29 hrs, Volume= 0.281 af

Outflow = 2.24 cfs @ 12.59 hrs, Volume= 0.276 af, Atten= 15%, Lag= 18.2 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Max. Velocity= 1.25 fps, Min. Travel Time= 9.5 min

Avg. Velocity= 0.69 fps, Avg. Travel Time= 17.3 min

Peak Storage= 1,280 cf @ 12.43 hrs


Average Depth at Peak Storage= 0.13'

Bank-Full Depth= 2.00' Flow Area= 113.3 sf, Capacity= 890.78 cfs

85.00' x 2.00' deep Parabolic Channel, n= 0.050 Scattered brush, heavy weeds

Length= 712.0' Slope= 0.0478 '/'

Inlet Invert= 272.00', Outlet Invert= 238.00'



Proposed Wetlands Drainage

Prepared by Killingly Engineering Associates, LLC

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock - Wetlands Drainage Link
Type III 24-hr 5-year Rainfall=4.27"

Printed 2/4/2021

Page 6

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points

Runoff by SCS TR-20 method, UH=SCS

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 2S': Overland to Wetlands

Runoff Area=81,744 sf 3.33% Impervious Runoff Depth>1.19"
Flow Length=200' Slope=0.1100 '/' Tc=12.2 min CN=67 Runoff=2.17 cfs 0.186 af

Subcatchment 8S: Overland to Wetlands

Runoff Area=159,593 sf 0.00% Impervious Runoff Depth>1.02"
Flow Length=152' Slope=0.1240 '/' Tc=14.1 min CN=64 Runoff=3.33 cfs 0.310 af

Reach 1R: Wetland Swale

Avg. Flow Depth=0.11' Max Vel=1.46 fps Inflow=2.17 cfs 0.186 af
n=0.050 L=290.0' S=0.0759 '/' Capacity=1,056.58 cfs Outflow=2.06 cfs 0.185 af

Reach 2R: Wetland Swale

Avg. Flow Depth=0.18' Max Vel=1.56 fps Inflow=5.26 cfs 0.495 af
n=0.050 L=712.0' S=0.0478 '/' Capacity=890.78 cfs Outflow=4.58 cfs 0.488 af

Total Runoff Area = 5.540 ac Runoff Volume = 0.496 af Average Runoff Depth = 1.08"
98.87% Pervious = 5.478 ac 1.13% Impervious = 0.063 ac

Proposed Wetlands Drainage

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock - Wetlands Drainage Link
Type III 24-hr 5-year Rainfall=4.27"
Printed 2/4/2021
Page 7

Summary for Subcatchment 2S': Overland to Wetlands

Runoff = 2.17 cfs @ 12.19 hrs, Volume= 0.186 af, Depth> 1.19"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 5-year Rainfall=4.27"

	Area (sf)	CN	Description
*	38,320	77	Woods, Good, HSG D - Wetlands
	21,500	55	Woods, Good, HSG B
	2,724	98	Roofs, HSG B
*	19,200	58	>75% Grass cover, Good, HSG B
	81,744	67	Weighted Average
	79,020		96.67% Pervious Area
	2,724		3.33% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
12.2	200	0.1100	0.27		Sheet Flow, Tc-2s Grass: Dense n= 0.240 P2= 3.37"

Summary for Subcatchment 8S: Overland to Wetlands

Runoff = 3.33 cfs @ 12.22 hrs, Volume= 0.310 af, Depth> 1.02"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 5-year Rainfall=4.27"

	Area (sf)	CN	Description
	97,618	55	Woods, Good, HSG B
	61,975	77	Woods, Good, HSG D
	159,593	64	Weighted Average
	159,593		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
14.1	152	0.1240	0.18		Sheet Flow, Tc-8 Woods: Light underbrush n= 0.400 P2= 3.37"

Summary for Reach 1R: Wetland Swale

Inflow Area = 1.877 ac, 3.33% Impervious, Inflow Depth > 1.19" for 5-year event
Inflow = 2.17 cfs @ 12.19 hrs, Volume= 0.186 af
Outflow = 2.06 cfs @ 12.29 hrs, Volume= 0.185 af, Atten= 5%, Lag= 6.1 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Max. Velocity= 1.46 fps, Min. Travel Time= 3.3 min
Avg. Velocity = 0.70 fps, Avg. Travel Time= 6.9 min

Proposed Wetlands Drainage

Prepared by Killingly Engineering Associates, LLC

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock - Wetlands Drainage Link
Type III 24-hr 5-year Rainfall=4.27"

Printed 2/4/2021

Page 8

Peak Storage= 411 cf @ 12.23 hrs

Average Depth at Peak Storage= 0.11'

Bank-Full Depth= 2.00' Flow Area= 106.7 sf, Capacity= 1,056.58 cfs

80.00' x 2.00' deep Parabolic Channel, n= 0.050 Scattered brush, heavy weeds

Length= 290.0' Slope= 0.0759 '/'

Inlet Invert= 294.00', Outlet Invert= 272.00'



Summary for Reach 2R: Wetland Swale

Inflow Area = 5.540 ac, 1.13% Impervious, Inflow Depth > 1.07" for 5-year event

Inflow = 5.26 cfs @ 12.25 hrs, Volume= 0.495 af

Outflow = 4.58 cfs @ 12.49 hrs, Volume= 0.488 af, Atten= 13%, Lag= 14.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Max. Velocity= 1.56 fps, Min. Travel Time= 7.6 min

Avg. Velocity= 0.77 fps, Avg. Travel Time= 15.5 min

Peak Storage= 2,108 cf @ 12.36 hrs

Average Depth at Peak Storage= 0.18'

Bank-Full Depth= 2.00' Flow Area= 113.3 sf, Capacity= 890.78 cfs

85.00' x 2.00' deep Parabolic Channel, n= 0.050 Scattered brush, heavy weeds

Length= 712.0' Slope= 0.0478 '/'

Inlet Invert= 272.00', Outlet Invert= 238.00'



Proposed Wetlands Drainage

Prepared by Killingly Engineering Associates, LLC

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock - Wetlands Drainage Link
Type III 24-hr 10-year Rainfall=5.02"

Printed 2/4/2021

Page 9

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points

Runoff by SCS TR-20 method, UH=SCS

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 2S': Overland to Wetlands

Runoff Area=81,744 sf 3.33% Impervious Runoff Depth>1.66"
Flow Length=200' Slope=0.1100 '/' Tc=12.2 min CN=67 Runoff=3.10 cfs 0.260 af

Subcatchment 8S: Overland to Wetlands

Runoff Area=159,593 sf 0.00% Impervious Runoff Depth>1.45"
Flow Length=152' Slope=0.1240 '/' Tc=14.1 min CN=64 Runoff=4.94 cfs 0.442 af

Reach 1R: Wetland Swale

Avg. Flow Depth=0.13' Max Vel=1.63 fps Inflow=3.10 cfs 0.260 af
n=0.050 L=290.0' S=0.0759 '/' Capacity=1,056.58 cfs Outflow=3.01 cfs 0.258 af

Reach 2R: Wetland Swale

Avg. Flow Depth=0.21' Max Vel=1.76 fps Inflow=7.75 cfs 0.700 af
n=0.050 L=712.0' S=0.0478 '/' Capacity=890.78 cfs Outflow=6.89 cfs 0.691 af

Total Runoff Area = 5.540 ac Runoff Volume = 0.701 af Average Runoff Depth = 1.52"
98.87% Pervious = 5.478 ac 1.13% Impervious = 0.063 ac

Proposed Wetlands Drainage

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock - Wetlands Drainage Link
Type III 24-hr 10-year Rainfall=5.02"
Printed 2/4/2021
Page 10

Summary for Subcatchment 2S': Overland to Wetlands

Runoff = 3.10 cfs @ 12.18 hrs, Volume= 0.260 af, Depth> 1.66"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 10-year Rainfall=5.02"

	Area (sf)	CN	Description
*	38,320	77	Woods, Good, HSG D - Wetlands
	21,500	55	Woods, Good, HSG B
	2,724	98	Roofs, HSG B
*	19,200	58	>75% Grass cover, Good, HSG B
	81,744	67	Weighted Average
	79,020		96.67% Pervious Area
	2,724		3.33% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
12.2	200	0.1100	0.27		Sheet Flow, Tc-2s Grass: Dense n= 0.240 P2= 3.37"

Summary for Subcatchment 8S: Overland to Wetlands

Runoff = 4.94 cfs @ 12.21 hrs, Volume= 0.442 af, Depth> 1.45"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 10-year Rainfall=5.02"

	Area (sf)	CN	Description
	97,618	55	Woods, Good, HSG B
	61,975	77	Woods, Good, HSG D
	159,593	64	Weighted Average
	159,593		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
14.1	152	0.1240	0.18		Sheet Flow, Tc-8 Woods: Light underbrush n= 0.400 P2= 3.37"

Summary for Reach 1R: Wetland Swale

Inflow Area = 1.877 ac, 3.33% Impervious, Inflow Depth > 1.66" for 10-year event
Inflow = 3.10 cfs @ 12.18 hrs, Volume= 0.260 af
Outflow = 3.01 cfs @ 12.27 hrs, Volume= 0.258 af, Atten= 3%, Lag= 5.3 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Max. Velocity= 1.63 fps, Min. Travel Time= 3.0 min
Avg. Velocity = 0.75 fps, Avg. Travel Time= 6.5 min

Proposed Wetlands Drainage

Prepared by Killingly Engineering Associates, LLC

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock - Wetlands Drainage Link
Type III 24-hr 10-year Rainfall=5.02"

Printed 2/4/2021

Page 11

Peak Storage= 533 cf @ 12.22 hrs


Average Depth at Peak Storage= 0.13'

Bank-Full Depth= 2.00' Flow Area= 106.7 sf, Capacity= 1,056.58 cfs

80.00' x 2.00' deep Parabolic Channel, n= 0.050 Scattered brush, heavy weeds

Length= 290.0' Slope= 0.0759 '/'

Inlet Invert= 294.00', Outlet Invert= 272.00'



Summary for Reach 2R: Wetland Swale

Inflow Area = 5.540 ac, 1.13% Impervious, Inflow Depth > 1.52" for 10-year event

Inflow = 7.75 cfs @ 12.24 hrs, Volume= 0.700 af

Outflow = 6.89 cfs @ 12.44 hrs, Volume= 0.691 af, Atten= 11%, Lag= 12.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Max. Velocity= 1.76 fps, Min. Travel Time= 6.7 min

Avg. Velocity= 0.82 fps, Avg. Travel Time= 14.5 min

Peak Storage= 2,801 cf @ 12.32 hrs

Average Depth at Peak Storage= 0.21'

Bank-Full Depth= 2.00' Flow Area= 113.3 sf, Capacity= 890.78 cfs

85.00' x 2.00' deep Parabolic Channel, n= 0.050 Scattered brush, heavy weeds

Length= 712.0' Slope= 0.0478 '/'

Inlet Invert= 272.00', Outlet Invert= 238.00'



Proposed Wetlands Drainage

Prepared by Killingly Engineering Associates, LLC

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock - Wetlands Drainage Link
Type III 24-hr 25-year Rainfall=6.05"

Printed 2/4/2021

Page 12

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points

Runoff by SCS TR-20 method, UH=SCS

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 2S': Overland to Wetlands

Runoff Area=81,744 sf 3.33% Impervious Runoff Depth>2.36"
Flow Length=200' Slope=0.1100 '/' Tc=12.2 min CN=67 Runoff=4.48 cfs 0.370 af

Subcatchment 8S: Overland to Wetlands

Runoff Area=159,593 sf 0.00% Impervious Runoff Depth>2.10"
Flow Length=152' Slope=0.1240 '/' Tc=14.1 min CN=64 Runoff=7.37 cfs 0.642 af

Reach 1R: Wetland Swale

Avg. Flow Depth=0.16' Max Vel=1.83 fps Inflow=4.48 cfs 0.370 af
n=0.050 L=290.0' S=0.0759 '/' Capacity=1,056.58 cfs Outflow=4.34 cfs 0.368 af

Reach 2R: Wetland Swale

Avg. Flow Depth=0.26' Max Vel=2.01 fps Inflow=11.46 cfs 1.010 af
n=0.050 L=712.0' S=0.0478 '/' Capacity=890.78 cfs Outflow=10.47 cfs 1.000 af

Total Runoff Area = 5.540 ac Runoff Volume = 1.012 af Average Runoff Depth = 2.19"
98.87% Pervious = 5.478 ac 1.13% Impervious = 0.063 ac

Proposed Wetlands Drainage

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock - Wetlands Drainage Link
Type III 24-hr 25-year Rainfall=6.05"
Printed 2/4/2021
Page 13

Summary for Subcatchment 2S': Overland to Wetlands

Runoff = 4.48 cfs @ 12.18 hrs, Volume= 0.370 af, Depth> 2.36"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 25-year Rainfall=6.05"

	Area (sf)	CN	Description
*	38,320	77	Woods, Good, HSG D - Wetlands
	21,500	55	Woods, Good, HSG B
	2,724	98	Roofs, HSG B
*	19,200	58	>75% Grass cover, Good, HSG B
	81,744	67	Weighted Average
	79,020		96.67% Pervious Area
	2,724		3.33% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
12.2	200	0.1100	0.27		Sheet Flow, Tc-2s Grass: Dense n= 0.240 P2= 3.37"

Summary for Subcatchment 8S: Overland to Wetlands

Runoff = 7.37 cfs @ 12.21 hrs, Volume= 0.642 af, Depth> 2.10"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 25-year Rainfall=6.05"

	Area (sf)	CN	Description
	97,618	55	Woods, Good, HSG B
	61,975	77	Woods, Good, HSG D
	159,593	64	Weighted Average
	159,593		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
14.1	152	0.1240	0.18		Sheet Flow, Tc-8 Woods: Light underbrush n= 0.400 P2= 3.37"

Summary for Reach 1R: Wetland Swale

Inflow Area = 1.877 ac, 3.33% Impervious, Inflow Depth > 2.36" for 25-year event
Inflow = 4.48 cfs @ 12.18 hrs, Volume= 0.370 af
Outflow = 4.34 cfs @ 12.26 hrs, Volume= 0.368 af, Atten= 3%, Lag= 5.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Max. Velocity= 1.83 fps, Min. Travel Time= 2.6 min
Avg. Velocity= 0.80 fps, Avg. Travel Time= 6.1 min

Proposed Wetlands Drainage

Prepared by Killingly Engineering Associates, LLC

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock - Wetlands Drainage Link
Type III 24-hr 25-year Rainfall=6.05"

Printed 2/4/2021

Page 14

Peak Storage= 692 cf @ 12.21 hrs


Average Depth at Peak Storage= 0.16'

Bank-Full Depth= 2.00' Flow Area= 106.7 sf, Capacity= 1,056.58 cfs

80.00' x 2.00' deep Parabolic Channel, n= 0.050 Scattered brush, heavy weeds

Length= 290.0' Slope= 0.0759 '/'

Inlet Invert= 294.00', Outlet Invert= 272.00'



Summary for Reach 2R: Wetland Swale

Inflow Area = 5.540 ac, 1.13% Impervious, Inflow Depth > 2.19" for 25-year event

Inflow = 11.46 cfs @ 12.23 hrs, Volume= 1.010 af

Outflow = 10.47 cfs @ 12.40 hrs, Volume= 1.000 af, Atten= 9%, Lag= 10.5 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Max. Velocity= 2.01 fps, Min. Travel Time= 5.9 min

Avg. Velocity= 0.88 fps, Avg. Travel Time= 13.4 min

Peak Storage= 3,721 cf @ 12.31 hrs

Average Depth at Peak Storage= 0.26'

Bank-Full Depth= 2.00' Flow Area= 113.3 sf, Capacity= 890.78 cfs

85.00' x 2.00' deep Parabolic Channel, n= 0.050 Scattered brush, heavy weeds

Length= 712.0' Slope= 0.0478 '/'

Inlet Invert= 272.00', Outlet Invert= 238.00'



Proposed Wetlands Drainage

Prepared by Killingly Engineering Associates, LLC

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock - Wetlands Drainage Link
Type III 24-hr 50-year Rainfall=6.85"

Printed 2/4/2021

Page 15

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points

Runoff by SCS TR-20 method, UH=SCS

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 2S': Overland to Wetlands

Runoff Area=81,744 sf 3.33% Impervious Runoff Depth>2.94"
Flow Length=200' Slope=0.1100 '/' Tc=12.2 min CN=67 Runoff=5.65 cfs 0.461 af

Subcatchment 8S: Overland to Wetlands

Runoff Area=159,593 sf 0.00% Impervious Runoff Depth>2.65"
Flow Length=152' Slope=0.1240 '/' Tc=14.1 min CN=64 Runoff=9.39 cfs 0.810 af

Reach 1R: Wetland Swale

Avg. Flow Depth=0.18' Max Vel=1.97 fps Inflow=5.65 cfs 0.461 af
n=0.050 L=290.0' S=0.0759 '/' Capacity=1,056.58 cfs Outflow=5.44 cfs 0.459 af

Reach 2R: Wetland Swale

Avg. Flow Depth=0.29' Max Vel=2.16 fps Inflow=14.62 cfs 1.269 af
n=0.050 L=712.0' S=0.0478 '/' Capacity=890.78 cfs Outflow=13.34 cfs 1.257 af

Total Runoff Area = 5.540 ac Runoff Volume = 1.271 af Average Runoff Depth = 2.75"
98.87% Pervious = 5.478 ac 1.13% Impervious = 0.063 ac

Proposed Wetlands Drainage

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock - Wetlands Drainage Link
Type III 24-hr 50-year Rainfall=6.85"
Printed 2/4/2021
Page 16

Summary for Subcatchment 2S': Overland to Wetlands

Runoff = 5.65 cfs @ 12.17 hrs, Volume= 0.461 af, Depth> 2.94"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 50-year Rainfall=6.85"

	Area (sf)	CN	Description
*	38,320	77	Woods, Good, HSG D - Wetlands
	21,500	55	Woods, Good, HSG B
	2,724	98	Roofs, HSG B
*	19,200	58	>75% Grass cover, Good, HSG B
	81,744	67	Weighted Average
	79,020		96.67% Pervious Area
	2,724		3.33% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
12.2	200	0.1100	0.27		Sheet Flow, Tc-2s Grass: Dense n= 0.240 P2= 3.37"

Summary for Subcatchment 8S: Overland to Wetlands

Runoff = 9.39 cfs @ 12.20 hrs, Volume= 0.810 af, Depth> 2.65"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 50-year Rainfall=6.85"

	Area (sf)	CN	Description
	97,618	55	Woods, Good, HSG B
	61,975	77	Woods, Good, HSG D
	159,593	64	Weighted Average
	159,593		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
14.1	152	0.1240	0.18		Sheet Flow, Tc-8 Woods: Light underbrush n= 0.400 P2= 3.37"

Summary for Reach 1R: Wetland Swale

Inflow Area = 1.877 ac, 3.33% Impervious, Inflow Depth > 2.94" for 50-year event
Inflow = 5.65 cfs @ 12.17 hrs, Volume= 0.461 af
Outflow = 5.44 cfs @ 12.25 hrs, Volume= 0.459 af, Atten= 4%, Lag= 4.7 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Max. Velocity= 1.97 fps, Min. Travel Time= 2.5 min
Avg. Velocity= 0.83 fps, Avg. Travel Time= 5.8 min

Proposed Wetlands Drainage

Prepared by Killingly Engineering Associates, LLC

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock - Wetlands Drainage Link
Type III 24-hr 50-year Rainfall=6.85"

Printed 2/4/2021

Page 17

Peak Storage= 810 cf @ 12.21 hrs


Average Depth at Peak Storage= 0.18'

Bank-Full Depth= 2.00' Flow Area= 106.7 sf, Capacity= 1,056.58 cfs

80.00' x 2.00' deep Parabolic Channel, n= 0.050 Scattered brush, heavy weeds

Length= 290.0' Slope= 0.0759 '/'

Inlet Invert= 294.00', Outlet Invert= 272.00'



Summary for Reach 2R: Wetland Swale

Inflow Area = 5.540 ac, 1.13% Impervious, Inflow Depth > 2.75" for 50-year event

Inflow = 14.62 cfs @ 12.22 hrs, Volume= 1.269 af

Outflow = 13.34 cfs @ 12.39 hrs, Volume= 1.257 af, Atten= 9%, Lag= 9.8 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Max. Velocity= 2.16 fps, Min. Travel Time= 5.5 min

Avg. Velocity= 0.92 fps, Avg. Travel Time= 12.8 min

Peak Storage= 4,416 cf @ 12.29 hrs

Average Depth at Peak Storage= 0.29'

Bank-Full Depth= 2.00' Flow Area= 113.3 sf, Capacity= 890.78 cfs

85.00' x 2.00' deep Parabolic Channel, n= 0.050 Scattered brush, heavy weeds

Length= 712.0' Slope= 0.0478 '/'

Inlet Invert= 272.00', Outlet Invert= 238.00'



Proposed Wetlands Drainage

Prepared by Killingly Engineering Associates, LLC

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock - Wetlands Drainage Link
Type III 24-hr 100-year Rainfall=7.64"

Printed 2/4/2021

Page 18

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points

Runoff by SCS TR-20 method, UH=SCS

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 2S': Overland to Wetlands

Runoff Area=81,744 sf 3.33% Impervious Runoff Depth>3.54"
Flow Length=200' Slope=0.1100 '/' Tc=12.2 min CN=67 Runoff=6.81 cfs 0.554 af

Subcatchment 8S: Overland to Wetlands

Runoff Area=159,593 sf 0.00% Impervious Runoff Depth>3.23"
Flow Length=152' Slope=0.1240 '/' Tc=14.1 min CN=64 Runoff=11.46 cfs 0.985 af

Reach 1R: Wetland Swale

Avg. Flow Depth=0.19' Max Vel=2.09 fps Inflow=6.81 cfs 0.554 af
n=0.050 L=290.0' S=0.0759 '/' Capacity=1,056.58 cfs Outflow=6.56 cfs 0.552 af

Reach 2R: Wetland Swale

Avg. Flow Depth=0.32' Max Vel=2.30 fps Inflow=17.81 cfs 1.537 af
n=0.050 L=712.0' S=0.0478 '/' Capacity=890.78 cfs Outflow=16.37 cfs 1.524 af

Total Runoff Area = 5.540 ac Runoff Volume = 1.539 af Average Runoff Depth = 3.33"
98.87% Pervious = 5.478 ac 1.13% Impervious = 0.063 ac

Proposed Wetlands Drainage

Prepared by Killingly Engineering Associates, LLC
HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock - Wetlands Drainage Link
Type III 24-hr 100-year Rainfall=7.64"
Printed 2/4/2021
Page 19

Summary for Subcatchment 2S': Overland to Wetlands

Runoff = 6.81 cfs @ 12.17 hrs, Volume= 0.554 af, Depth> 3.54"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 100-year Rainfall=7.64"

	Area (sf)	CN	Description
*	38,320	77	Woods, Good, HSG D - Wetlands
	21,500	55	Woods, Good, HSG B
	2,724	98	Roofs, HSG B
*	19,200	58	>75% Grass cover, Good, HSG B
	81,744	67	Weighted Average
	79,020		96.67% Pervious Area
	2,724		3.33% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
12.2	200	0.1100	0.27		Sheet Flow, Tc-2s Grass: Dense n= 0.240 P2= 3.37"

Summary for Subcatchment 8S: Overland to Wetlands

Runoff = 11.46 cfs @ 12.20 hrs, Volume= 0.985 af, Depth> 3.23"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 100-year Rainfall=7.64"

	Area (sf)	CN	Description
	97,618	55	Woods, Good, HSG B
	61,975	77	Woods, Good, HSG D
	159,593	64	Weighted Average
	159,593		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
14.1	152	0.1240	0.18		Sheet Flow, Tc-8 Woods: Light underbrush n= 0.400 P2= 3.37"

Summary for Reach 1R: Wetland Swale

Inflow Area = 1.877 ac, 3.33% Impervious, Inflow Depth > 3.54" for 100-year event
Inflow = 6.81 cfs @ 12.17 hrs, Volume= 0.554 af
Outflow = 6.56 cfs @ 12.25 hrs, Volume= 0.552 af, Atten= 4%, Lag= 4.5 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Max. Velocity= 2.09 fps, Min. Travel Time= 2.3 min
Avg. Velocity = 0.86 fps, Avg. Travel Time= 5.6 min

Proposed Wetlands Drainage

Prepared by Killingly Engineering Associates, LLC

HydroCAD® 10.00 s/n 07240 © 2011 HydroCAD Software Solutions LLC

Pollock - Wetlands Drainage Link
Type III 24-hr 100-year Rainfall=7.64"

Printed 2/4/2021

Page 20

Peak Storage= 924 cf @ 12.21 hrs


Average Depth at Peak Storage= 0.19'

Bank-Full Depth= 2.00' Flow Area= 106.7 sf, Capacity= 1,056.58 cfs

80.00' x 2.00' deep Parabolic Channel, n= 0.050 Scattered brush, heavy weeds

Length= 290.0' Slope= 0.0759 '/'

Inlet Invert= 294.00', Outlet Invert= 272.00'



Summary for Reach 2R: Wetland Swale

Inflow Area = 5.540 ac, 1.13% Impervious, Inflow Depth > 3.33" for 100-year event

Inflow = 17.81 cfs @ 12.22 hrs, Volume= 1.537 af

Outflow = 16.37 cfs @ 12.37 hrs, Volume= 1.524 af, Atten= 8%, Lag= 9.1 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Max. Velocity= 2.30 fps, Min. Travel Time= 5.2 min

Avg. Velocity= 0.96 fps, Avg. Travel Time= 12.3 min

Peak Storage= 5,084 cf @ 12.28 hrs


Average Depth at Peak Storage= 0.32'

Bank-Full Depth= 2.00' Flow Area= 113.3 sf, Capacity= 890.78 cfs

85.00' x 2.00' deep Parabolic Channel, n= 0.050 Scattered brush, heavy weeds

Length= 712.0' Slope= 0.0478 '/'

Inlet Invert= 272.00', Outlet Invert= 238.00'



SUPPORTING DOCUMENTATION

NOAA Point Precipitation Estimates Web Soil Survey



NOAA Atlas 14, Volume 10, Version 3
Location name: Brooklyn, Connecticut, USA*
Latitude: 41.7827°, Longitude: -71.9363°
Elevation: 329.49 ft**

* source: ESRI Maps

** source: USGS



POINT PRECIPITATION FREQUENCY ESTIMATES

Sanja Perica, Sandra Pavlovic, Michael St. Laurent, Carl Trypaluk, Dale Unruh, Orlan Wilhite

NOAA, National Weather Service, Silver Spring, Maryland

PF_tabular | PF_graphical | Maps_&_aerials

PF tabular

PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches)¹										
Duration	Average recurrence interval (years)									
	1	2	5	10	25	50	100	200	500	1000
5-min	0.337 (0.256-0.442)	0.400 (0.304-0.525)	0.503 (0.381-0.662)	0.587 (0.443-0.777)	0.704 (0.515-0.965)	0.793 (0.569-1.11)	0.884 (0.618-1.27)	0.982 (0.658-1.45)	1.12 (0.723-1.70)	1.23 (0.775-1.89)
10-min	0.477 (0.363-0.626)	0.566 (0.430-0.743)	0.711 (0.539-0.937)	0.831 (0.627-1.10)	0.997 (0.730-1.37)	1.12 (0.807-1.57)	1.25 (0.876-1.80)	1.39 (0.932-2.05)	1.58 (1.02-2.40)	1.74 (1.10-2.68)
15-min	0.562 (0.427-0.737)	0.666 (0.506-0.875)	0.836 (0.634-1.10)	0.978 (0.738-1.30)	1.17 (0.859-1.61)	1.32 (0.949-1.84)	1.47 (1.03-2.12)	1.64 (1.10-2.41)	1.86 (1.21-2.83)	2.04 (1.29-3.15)
30-min	0.775 (0.590-1.02)	0.919 (0.699-1.21)	1.16 (0.875-1.52)	1.35 (1.02-1.79)	1.62 (1.19-2.22)	1.82 (1.31-2.54)	2.03 (1.42-2.92)	2.26 (1.51-3.33)	2.57 (1.66-3.90)	2.82 (1.78-4.35)
60-min	0.988 (0.752-1.30)	1.17 (0.891-1.54)	1.47 (1.12-1.94)	1.72 (1.30-2.28)	2.07 (1.51-2.83)	2.33 (1.67-3.25)	2.59 (1.81-3.73)	2.88 (1.93-4.24)	3.28 (2.12-4.97)	3.59 (2.28-5.55)
2-hr	1.26 (0.966-1.65)	1.50 (1.15-1.96)	1.89 (1.44-2.47)	2.21 (1.67-2.91)	2.65 (1.95-3.62)	2.98 (2.15-4.15)	3.32 (2.35-4.78)	3.72 (2.49-5.44)	4.28 (2.78-6.45)	4.74 (3.01-7.28)
3-hr	1.46 (1.12-1.90)	1.73 (1.33-2.26)	2.18 (1.66-2.85)	2.55 (1.93-3.35)	3.06 (2.26-4.17)	3.44 (2.50-4.78)	3.84 (2.72-5.52)	4.31 (2.90-6.28)	4.99 (3.24-7.49)	5.55 (3.53-8.49)
6-hr	1.87 (1.44-2.42)	2.22 (1.70-2.88)	2.79 (2.13-3.63)	3.26 (2.49-4.26)	3.91 (2.90-5.32)	4.40 (3.21-6.10)	4.92 (3.51-7.05)	5.53 (3.73-8.02)	6.43 (4.19-9.60)	7.19 (4.58-10.9)
12-hr	2.36 (1.82-3.05)	2.81 (2.17-3.63)	3.53 (2.72-4.58)	4.14 (3.17-5.39)	4.97 (3.70-6.72)	5.59 (4.09-7.71)	6.25 (4.47-8.91)	7.03 (4.76-10.1)	8.17 (5.34-12.1)	9.14 (5.85-13.8)
24-hr	2.82 (2.19-3.62)	3.37 (2.61-4.34)	4.28 (3.30-5.52)	5.03 (3.87-6.52)	6.06 (4.54-8.16)	6.84 (5.03-9.38)	7.66 (5.50-10.9)	8.62 (5.86-12.4)	10.1 (6.59-14.8)	11.3 (7.22-16.9)
2-day	3.17 (2.47-4.06)	3.84 (2.99-4.92)	4.92 (3.82-6.33)	5.83 (4.50-7.52)	7.07 (5.31-9.48)	7.99 (5.90-10.9)	8.98 (6.48-12.7)	10.2 (6.92-14.5)	11.9 (7.83-17.4)	13.4 (8.62-19.9)
3-day	3.44 (2.68-4.39)	4.16 (3.25-5.32)	5.35 (4.16-6.85)	6.33 (4.90-8.14)	7.68 (5.79-10.3)	8.69 (6.44-11.8)	9.77 (7.08-13.8)	11.1 (7.55-15.7)	13.0 (8.58-19.0)	14.7 (9.48-21.8)
4-day	3.67 (2.88-4.68)	4.45 (3.47-5.67)	5.71 (4.45-7.30)	6.75 (5.23-8.67)	8.19 (6.18-10.9)	9.25 (6.87-12.6)	10.4 (7.56-14.7)	11.8 (8.06-16.7)	13.9 (9.17-20.2)	15.7 (10.1-23.2)
7-day	4.34	5.21	6.63	7.81	9.43	10.6	11.9	13.5	15.9	18.0

	(3.41-5.52)	(4.09-6.62)	(5.19-8.45)	(6.08-9.99)	(7.15-12.5)	(7.92-14.4)	(8.70-16.7)	(9.26-19.0)	(10.5-23.0)	(11.6-26.4)
10-day	5.02 (3.95-6.36)	5.95 (4.68-7.54)	7.46 (5.84-9.48)	8.71 (6.79-11.1)	10.4 (7.92-13.8)	11.7 (8.74-15.8)	13.1 (9.54-18.3)	14.7 (10.1-20.7)	17.2 (11.4-24.8)	19.3 (12.5-28.3)
20-day	7.17 (5.67-9.05)	8.16 (6.45-10.3)	9.78 (7.70-12.4)	11.1 (8.71-14.1)	13.0 (9.85-17.0)	14.4 (10.7-19.1)	15.8 (11.4-21.6)	17.4 (12.0-24.2)	19.6 (13.0-28.0)	21.3 (13.9-31.0)
30-day	8.99 (7.12-11.3)	10.0 (7.92-12.6)	11.7 (9.20-14.7)	13.0 (10.2-16.5)	14.9 (11.3-19.4)	16.4 (12.2-21.6)	17.8 (12.8-24.1)	19.3 (13.4-26.8)	21.2 (14.2-30.2)	22.6 (14.7-32.8)
45-day	11.2 (8.93-14.1)	12.3 (9.74-15.4)	14.0 (11.1-17.6)	15.4 (12.1-19.5)	17.3 (13.2-22.4)	18.9 (14.0-24.7)	20.3 (14.6-27.1)	21.7 (15.1-29.9)	23.3 (15.6-33.0)	24.3 (15.9-35.1)
60-day	13.1 (10.4-16.4)	14.2 (11.3-17.8)	15.9 (12.6-20.0)	17.4 (13.7-21.9)	19.4 (14.7-24.9)	21.0 (15.6-27.3)	22.4 (16.1-29.8)	23.7 (16.5-32.6)	25.1 (16.9-35.5)	26.0 (17.0-37.4)

¹ Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS).

Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values.


Please refer to NOAA Atlas 14 document for more information.


[Back to Top](#)

PF graphical

PDS-based depth-duration-frequency (DDF) curves

Latitude: 41.7827°, Longitude: -71.9363°







NOAA Atlas 14, Volume 10, Version 3


Created (GMT): Tue Dec 8 14:02:09 2020

[Back to Top](#)


Maps & aeriels

Small scale terrain

**Large scale terrain****Large scale map**



Large scale aerial

[Back to Top](#)

US Department of Commerce
National Oceanic and Atmospheric Administration
[National Weather Service](#)
[National Water Center](#)
1325 East West Highway
Silver Spring, MD 20910
Questions?: HDSC.Questions@noaa.gov


[Disclaimer](#)

Hydrologic Soil Group—State of Connecticut (Louise Berry Drive)



MAP LEGEND

Area of Interest (AOI)









 Area of Interest (AOI)

Soils

Soil Rating Polygons





 A
 A/D
 B
 B/D
 C
 C/D
 D
 Not rated or not available

Soil Rating Lines


 A
 A/D
 B
 B/D
 C
 C/D
 D
 Not rated or not available

Soil Rating Points




 A
 A/D
 B
 B/D

 C
 C/D
 D
 Not rated or not available

Water Features

 Streams and Canals

Transportation

 Rails
 Interstate Highways
 US Routes
 Major Roads
 Local Roads

Background

 Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:12,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
Web Soil Survey URL:
Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: State of Connecticut
Survey Area Data: Version 20, Jun 9, 2020

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Apr 14, 2011—Aug 27, 2016

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
3	Ridgebury, Leicester, and Whitman soils, 0 to 8 percent slopes, extremely stony	D	3.1	27.8%
34B	Merrimac fine sandy loam, 3 to 8 percent slopes	A	0.0	0.4%
60B	Canton and Charlton fine sandy loams, 3 to 8 percent slopes	B	4.7	42.9%
61C	Canton and Charlton fine sandy loams, 8 to 15 percent slopes, very stony	B	2.9	26.0%
62D	Canton and Charlton fine sandy loams, 15 to 35 percent slopes, extremely stony	B	0.1	0.7%
701B	Ninigret fine sandy loam, 3 to 8 percent slopes	C	0.2	2.2%
Totals for Area of Interest			11.0	100.0%

Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

Rating Options

Aggregation Method: Dominant Condition

Component Percent Cutoff: None Specified

Tie-break Rule: Higher

DRAINAGE AREA PLANS

n/f
Pierce Baptist Home, Inc.
Map 19, Block 24, Lot 148

SEWER EASEMENT IN FAVOR OF
THE TOWN OF BROOKLYN
VOL. 617, PG. 278

ACCESS RIGHT OF WAY
OVER LANEWAY IN FAVOR OF
THE TOWN OF BROOKLYN
VOL. 31, PG. 130

n/f
Carl R. Baker
&
Darlene A. Baker
Map 19, Block 24, Lot 158

30' WIDE ACCESS EASEMENT IN
FAVOR OF THE TOWN OF BROOKLYN
AS SHOWN ON MAP REFERENCE #??
STATUS UNKNOWN - NO RECORDED DEED FOUND

n/f
Town of Brooklyn
Map 19, Block 33, Lot 21

50 25 0 50
GRAPHIC SCALE IN FEET

LINE TABLE		
LINE	BEARING	DISTANCE
L1	N 11°34'49" E	8.88'
L2	N 09°28'18" E	25.48'
L3	S 89°46'21" E	25.92'
L4	N 00°34'43" W	23.50'
L5	N 08°18'28" E	23.74'

n/f
Curt R. Hostman
Map 19, Block 33, Lot 20.1

n/f
Curt R. Hostman
Map 19, Block 33, Lot 20.2

n/f
William J. Purcell, Jr.
Map 19, Block 33, Lot 20.3

n/f
Stephanie A. Hynes
&
Brennan D. Hynes
Map 19, Block 33, Lot 16

n/f
Richard E. Bein
Map 19, Block 33, Lot 17

n/f
Linda Atsales
Map 19, Block 33, Lot 15

n/f
Mark S. Benard
Map 19, Block 33, Lot 14

n/f
Sean P. Mahan
Map 19, Block 33, Lot 13

n/f
Sally A. Wood
Map 19, Block 33, Lot 10A

LEGEND

- IRON PIN TO BE SET
- IRON PIN FOUND
- DH DRILL HOLE FOUND
- UTILITY POLE
- CB CATCH BASIN
- SMH SANITARY MANHOLE
- 260--- EXISTING CONTOURS
- #--- INLAND WETLANDS FLAG
- ○ ○ ○ ○ STONE WALL
- ○ ○ ○ ○ STONE WALL REMAINS

20.11'
S 86°16'31" E

199.57'
N 86°16'31" W

262.34'
N 89°56'57" W

222.52'
N 89°46'21" W

106.33'
N 89°46'09" W

127.58'
S 11°20'42" W

74.68'
S 11°57'36" W

88.34'
S 09°28'18" W

88.34'
S 09°28'18" W

88.34'
S 09°28'18" W

88.34'
S 09°28'18" W

88.34'
S 09°28'18" W

88.34'
S 09°28'18" W

88.34'
S 09°28'18" W

88.34'
S 09°28'18" W

88.34'
S 09°28'18" W

88.34'
S 09°28'18" W


DATE	PER TOWN REVIEW
08/24/2020	DESCRIPTION
DATE	REVISIONS

EXISTING DRAINAGE AREAS

PREPARED FOR

SHANE POLLOCK

LOUISE BERRY DRIVE
BROOKLYN, CONNECTICUT





Killingly Engineering Associates
Civil Engineering & Surveying

114 Westcott Road
P.O. Box 421
Killingly, Connecticut 06241
(860) 779-7299
www.killinglyengineering.com

DATE: 4/23/2020	DRAWN: NET
SCALE: 1" = 50'	DESIGN: NET
SHEET: 1 OF 2	CHK BY: ---
DWG. No: CLIENT FILE	JOB No: 20014

K:\2014\Drawings\2-DRAINAGE.dwg Dec 08, 2020 9:28 AM



DATE	DESCRIPTION
	REVISIONS

PROPOSED DRAINAGE AREAS

PREPARED FOR

SHANE POLLOCK

LOUISE BERRY DRIVE
BROOKLYN, CONNECTICUT

Killingly Engineering Associates
Civil Engineering & Surveying

114 Westcott Road
P.O. Box 421
Killingly, Connecticut 06241
(860) 779-7299
www.killinglyengineering.com

DATE: 4/23/2020	DRAWN: DNE
SCALE: 1" = 40'	DESIGN: NET
SHEET: 5 OF 9	CHK BY: ---
DWG. No: CLIENT FILE	JOB No: 20014

NORMAND E. THIBEAULT, JR., P.E. LIC #PEN 0022834	DATE
---	------