CLA Engineers, Inc.

Civil • Structural • Survey

317 MAIN STREET

NORWICH, CT 06360

(860) 886-1966

(860) 886-9165 FAX

November 23, 2020

Margaret Washburn ZEO/WEO/Blight Enforcement Officer Town of Brooklyn 69 South Main Street Suite 22 Brooklyn, CT 06234

RE: Proposed 4 Lot Subdivision – Square 1 Building Associates

Tripp Hollow Road Brooklyn, CT Beecher Rd CLA 6503

Dear Margaret:

Attached are revised plans addressing engineering comments dated 9/5/20. Please note the following:

Sheet 2 of 8

- 1) Signatures provided
- 2) Corrected
- 3) Corrected
- 4) Corrected
- 5) Corrected
- 6) Provided
- 7) Provided

Sheet 3 of 8

- 1) Addressed previously
- 2) Corrected
- 3) The land surveyor has stated that the Town did not require this for the recent adjacent subdivision to the North on the same unimproved Town Road. Town to clarify the need for this as it relates to consistency with the adjacent property.
- 4) Addressed previously

Sheet 4 of 8

- 1) Hay Bale check dams have been added to plan in lieu of additional silt fence.
- 2) A pipe has been added under the driveway to lot 12-9.

Sheet 5 of 8

- 1) The area of wetland disturbed has been added to the plan.
- 2) Corrected

- 3) Hay bale check dams have been added to plan in lieu of additional silt fence. In addition, silt fence has been extended from wetland crossing to station 3+00 along shared driveway.
- 4) A pipe has been added under the driveway to lot 12-10.
- 5) Additional information has been added related to removing existing organic material and providing appropriate pipe bedding and backfill.
- 6) Per our Soil Scientist, unlike a larger culvert crossing (box culverts or 5'-6' diameter pipes) on a heavily traveled road, the increased height (due to the proposed 15" pipe) of a single driveway will not impede wildlife passage. Therefore, we feel gravel pipe bottoms are unnecessary and would potentially be a future maintenance concern with pipes of this size.
- 7) There was no evidence of channelized drainage flow near the crossing. In addition, multiple pipes and porous backfill material are proposed to spread out the flow. Multiple pipe crossings were a request of the Commission after the wetland walk. Therefore, we feel the need for flared end sections is unnecessary.
- 8) This comment is no longer applicable due to the redesign of the crossing.
- 9) Underground utilities have been relocated around pipe crossings.

Sheet 6 of 8

- 1) Corrected
- 2) Corrected

Drainage Calculations

Calculations have been revised to account for 25-year storm.

Please contact me if you have any questions.

Sincerely,

Robert A. DeLuca, P.E.

DRAINAGE NARRATI'VE

4-Lot Subdivision
Tripp Hollow Road, Brooklyn, CT
Prepared for
Square 1 Building Associates, LLC



The existing site consists of approximately 23.3 acres of undeveloped woodlands located to the west of Tripp Hollow Road in Brooklyn Connecticut. There are inland wetlands running in a north/south direction through the center of the site.

The proposed subdivision consists of 4 residential building lots served by approximately 1,000 L.F. of new shared driveway access form Tripp Hollow Road. Presently, storm water in the proposed development area drains west and north, exiting the site via the wetlands and eventually discharging to Tatnic Brook.

The driveway for the western most building lot is required to cross the wetland. The crossing location has been determined to minimize impact to the wetland (see CLA Wetland Letter to Inland Wetlands Commission 09/03/20). The crossing length is approximately 100 feet.

The following determines the size of the drainage culvert required to pass the 25-year storm event with inlet control, without submerging the culvert.

Methodology:

In accordance with the Town of Brooklyn's Public Improvement Specifications, the site's watershed was analyzed using the Rational method for the 25-year storm. The Rational method predicts the peak runoff according to the formula: Q=CiA, where C is a runoff coefficient, i is the rainfall intensity, and A is the sub-catchment area.

Rainfall intensities used in the calculations were taken from the Brooklyn (06-0918) weather station readings accessed via the NOAA Atlas 14 Point Precipitation Frequency website.

The proposed watershed contributing to the driveway crossing was determined to be 5.77 acres using local DEEP watershed basin boundaries and Connecticut Elevation (Lidar) Data (See Fig. 1).


The site consists primarily undeveloped woodlands. A run-off coefficient (C) of 0.2 (Unimproved Surface) was utilized. The Time of Concentration was determined as approximately 10 minutes using the TR-55 method.

The peak discharge (Q) for the 25-year storm event was calculated as follows:

Peak Volume (Q) = CiA = 0.2×6.11 in/hr x 5.77 acres = 7.05 c.f.s. (See Appendix 1)

Analysis of the culvert crossing was performed using Hydraflow Express culvert modeler (used in HDS-5 Hydraulic Design of Highway Culverts).

The resultant analysis determined that three 15" diameter pipes, installed at a grade consistent with the existing wetland, are able to convey approximately 12 c.f.s without submerging the pipes (See Appendix 2).



CLA Engineers, Inc. CIVIL · STRUCTURAL · SURVEYING

317 Main Street Norwich, Connecticut (860) 886-1966 Fax (860) 886-9165 e-mail: cla@claengineers.com

PROPOSED WATERSHED

SQUARE 1 BUILDING ASSOCIATES, LLC DATE: 9/7/20 **4 LOT SUBDIVISION** TRIPP HOLLOW ROAD, BROOKLYN, CT

SCALE: 1:2,400 1

Hydrograph Report



Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2009 by Autodesk, Inc. v6.066

Sunday, Nov 22, 2020

Hyd. No. 1

Watershed 1


Hydrograph type = Rational Storm frequency = 25 yrs Time interval = 1 min Drainage area = 5.770 ac

Intensity = 6.111 in/hr

IDF Curve = 6503 Pollock.IDF Peak discharge = 7.052 cfsTime to peak = 10 min Hyd. volume = 0.097 acft Runoff coeff. = 0.2

Tc by TR55 $= 10.00 \, \text{min}$

Asc/Rec limb fact = 1/1



Culvert Report



Hydraflow Express Extension for AutoCAD® Civil 3D® 2009 by Autodesk, Inc.

Monday, Nov 23 2020

Wetland Crossing

Invert Elev Dn (ft) = 417.10Pipe Length (ft) = 24.00Slope (%) = 1.25Invert Elev Up (ft) = 417.40Rise (in) = 15.0Shape Cir 15.0 Span (in) No. Barrels = 3 n-Value = 0.012Inlet Edge = Projecting

Coeff. K,M,c,Y,k = 0.0045, 2, 0.0317, 0.69, 0.5

Embankment


Top Elevation (ft) = 419.90 Top Width (ft) = 10.00 Crest Width (ft) = 50.00 **Calculations**

Qmin (cfs) = 1.00Qmax (cfs) = 20.00Tailwater Elev (ft) = (dc+D)/2

Highlighted

Qtotal (cfs) = 12.00 Qpipe (cfs) = 12.00 Qovertop (cfs) = 0.00Veloc Dn (ft/s) = 3.69Veloc Up (ft/s) = 4.74HGL Dn (ft) = 418.13 HGL Up (ft) = 418.21 Hw Elev (ft) = 418.61 Hw/D (ft) = 0.97

Flow Regime = Inlet Control




SUBDIVISION APPLICATION

PROPOSED 4 LOT SUBDIVISION


TRIPP HOLLOW ROAD BROOKLYN, CONNECTICUT


PROPERTY OWNER/APPLICANT: SQUARE 1 BUILDING ASSOCIATES

September 1, 2020



PREPARED BY:





APPROVED BY THE BROOKLYN INLAND WETLANDS COMMISSION

CHAIRMAN DATE

Expiration date per section 22A-42A of the Connecticut

APPROVED BY THE BROOKLYN PLANNING AND ZONING COMMISSION


General Statutes.


CHAIRMAN DATE

Expiration date per section 8.26C of the Connecticut General Statutes. Date: ______

INDEX OF DRAWINGS

SHEET 1 OF 8 COVER SHEET EXISTING CONDITION PLAN SHEET 2 OF 8 SUBDIVISION SHEET 3 OF 8 SHEET 4 OF 8 SITE DEVELOPMENT PLAN 1 SITE DEVELOPMENT PLAN 2 SHEET 5 OF 8 DETAIL SHEET SHEET 6 OF 8 PARCEL HISTORY PLAN SHEET 7 OF 8 SITE ANALYSIS SHEET 8 OF 8





SELECT FILL SPECIFICATION

SELECT FILL PLACED WITHIN AND ADJACENT TO LEACHING SYSTEM AREAS SHALL BE COMPRISED OF CLEAN SAND, OR SAND AND GRAVEL, FREE FROM ORGANIC MATTER AND FOREIGN SUBSTANCES. THE SELECT FILL SHALL MEET THE FOLLOWING REQUIREMENTS PER THE CONNECTICUT PUBLIC HEALTH

- 1. THE SELECT FILL SHALL NOT CONTAIN ANY MATERIAL LARGER THAN THE THREE (3) INCH SLEEVE.
- 2. UP TO 45% OF THE DRY WEIGHT OF THE REPRESENTATIVE SAMPLE MAY BE RETAINED ON THE #4 SLEEVE (THIS IS THE GRAVEL PORTION OF THE
- 3. THE MATERIAL THAT PASSES THE #4 SIEVE IS THEN REWEIGHED AND THE SIEVE ANALYSIS STARTED, 4. THE REMAINING SAMPLE SHALL MEET THE FOLLOWING CRITERIA:

DRY SIEVE WET SIEVE 70-100 70-100 10-50* 10-75 0-20 0-5

* PERCENT PASSING THE #40 SIEVE CAN BE INCREASED TO NO GREATER THAN 75 IF THE PERCENT PASSING THE #100 SIEVE DOES NOT EXCEED 10 AND THE #200 SIEVE DOES NOT EXCEED 5.

SEPTIC NOTES

- PROPOSED SEPTIC SYSTEM TO BE STAKED IN THE FIELD BY A LAND SURVEYOR LICENSED IN THE STATE OF CONNECTICUT.
- 2. A BENCHMARK SHALL BE SET WITHIN 10'-15' OF THE PROPOSED SEPTIC SYSTEM PRIOR TO CONSTRUCTION.
- 3. ALL WORK AND MATERIAL (SEPTIC TANK, DISTRIBUTION BOX, PIPE) SHALL CONFORM TO THE CONNECTICUT PUBLIC HEALTH CODE REGULATIONS AND STANDARDS FOR SUBSURFACE SEWAGE DISPOSAL SYSTEM.
- 4. SEWER LINE FROM FOUNDATION WALL TO SEPTIC TANK SHALL BE 4" SCHEDULE 40 PVC ASTM D 1785 AND JOINTS PER HEALTH DEPT. CODE. PIPE FROM SEPTIC TANK TO DISTRIBUTION LINES SHALL BE 4" SOLID PVC CONFORMING TO STMD-3034 AND SDR-35.
- 5. SYSTEMS SHALL BE SET LEVEL FOR ENTIRE LENGTH AND HAVE A CENTER TO CENTER SPACING AS CALLED FOR IN THE CONNECTICUT PUBLIC HEALTH CODE. THERE ARE PRESENTLY NO KNOWN WATER WELLS WITHIN 75' OF THE PROPOSED SEPTIC SYSTEMS.
- 6. CLEAR AND GRUB THE AREA WHERE THE SEPTIC SYSTEMS AND HOUSES ARE TO BE CONSTRUCTED. ALL TOPSOIL IS TO BE STRIPPED AND
- ALL FILL MATERIAL SHALL BE CLEAN EARTH FREE OF STUMPS, ORGANICS, CONSTRUCTION DEBRIS AND TOPSOIL.
- 8. TOPSOIL SHALL BE RE-APPLIED OVER ALL FILL AREAS AND ALL DISTURBED AREAS TO PROVIDE A MINIMUM DEPTH OF FOUR INCHES IN ACCORDANCE WITH THE SLOPE STABILIZATION DETAILS..

CONCEPT SEPTIC SYSTEM DESIGN

LOT 12-8
PRIMARY LEACHING AREA
3 BEDROOM RESIDENCE

PERCOLATION RATE: 13.3 MIN./INCH (NDDH FILE #21000003) LEACHING AREA REQUIRED: <u>675 SF</u>

USE TRADITIONAL TRENCH

EFFECTIVE LEACHING AREA OF LEACHING TRENCH 3.0 SF/LF REQUIRED LENGTH = 675 SF / 3 SF/LF = 225 LF

MLSS CALCULATION
HYDRAULIC FACTORS

DEPTH TO RESTRICTIVE LAYER = 28"

SLOPE = 4.0%HYDRAULIC FACTOR (HF) = 34

FLOW FACTOR (FF) = 1.5PERCOLATION FACTOR (PF) = 1.25 (10.1 TO 20.0 MIN./INCH) MLSS REQUIRED: 34 x 1.5 x 1.25 $\stackrel{.}{=}$ 63.75 LF

PROPOSED SYSTEM
USE 3 ROWS OF 75 LF

LEACHING AREA PROVIDED = 675 SF

RESERVE LEACHING AREA
USE SAME AS PRIMARY SYSTEM

PERCOLATION RATE: 10 MIN./INCH (NDDH FILE #21000003) LEACHING AREA REQUIRED: 495 SF

USE TRADITIONAL TRENCH

EFFECTIVE LEACHING AREA OF LEACHING TRENCH 3.0 SF/LF REQUIRED LENGTH = 495 SF / 3 SF/LF = 165 LF

MLSS CALCULATION HYDRAULIC FACTORS

DEPTH TO RESTRICTIVE LAYER = 24"

SLOPE = 10.5%HYDRAULIC FACTOR (HF) = 26

FLOW FACTOR (FF) = 1.5PERCOLATION FACTOR (PF) = 1.00 (UP TO 10.0 MIN./INCH)

MLSS REQUIRED: $26 \times 1.5 \times 1.00 = 39 \text{ LF}$

PROPOSED SYSTEM
USE 3 ROWS OF 55 LF LEACHING AREA PROVIDED = $\underline{495}$ SF

RESERVE LEACHING AREA USE SAME AS PRIMARY SYSTEM

0-11" Topsoil

Soil Test Data (NDDH File #21000003)

Soil Testing Conducted on 8/26/20 by Sherry McGann, R.S. & Sherry Vallone, E.H.S.

0-8" Topsoil


Lot 12-8 Lot 12-9 TP 2-A Mottles: 24" Mottles: 28" Ground Water: N/O Ground Water: N/0 Roots: 28" Roots: 24" Ledge: N/0 Ledge: N/O


11-28" OB Very Fine Sandy Loam 8-24" OB Fine Sandy Loam 28-86" GR Mottled Sandy Loam Till 24-92" GR Mottled Sandy Loam Till

TP 1-B Mottles: 28" TP 2-B Mottles: 26" Ground Water: N/0 Ground Water: N/0 Roots: 28" Roots: 26" Ledge: N/0 Ledge: N/0 0-10" Topsoil 0-9" Topsoil


10-28" OB Very Fine Sandy Loam 9-26" OB Fine Sandy Loam 28-91" GR Mottled Sandy Loam Till 26-91" GR Mottled Sandy Loam Till

Perc 1A 10:36 3" Perc 2A 1 :38 2" 10:46 5" 1:48 5 1/4" 10:56 7 ½" 1:58 71/4" 11:05 8 3/4" 2:08 9" 11: 15 9 ½" <u>2:18 10"</u> <u>11:25 10¼"</u> 10.0 minutes/inch 13.33 minutes/inch





UTILITY POLE



			CLA Engineers, Inc	
3	11/23/20	NCCG COMMENTS ADDRESSED	CIVIE - STREETERAL - SCRVETING	
2	09/28/20	WETLAND FLAGS CALLOUTS ADDED		
1	09/20/20	VARIOUS MODIFICATIONS	317 Main Street Norwich, CT 06360	
No.	DATE	REVISION	(860) 886-1966 Fax (860) 886-9165	
			Project No.	

Inc.

CLA - 6503


Proj. Engineer

D.H.

08/24/20 Sheet No.

4 of 8

Date:



CLA

SELECT FILL SPECIFICATION

SELECT FILL PLACED WITHIN AND ADJACENT TO LEACHING SYSTEM AREAS SHALL BE COMPRISED OF CLEAN SAND, OR SAND AND GRAVEL, FREE FROM ORGANIC MATTER AND FOREIGN SUBSTANCES. THE SELECT FILL SHALL MEET THE FOLLOWING REQUIREMENTS PER THE CONNECTICUT PUBLIC HEALTH CODE FOR USE WITHIN THE LEACHING AREA:

- 1. THE SELECT FILL SHALL NOT CONTAIN ANY MATERIAL LARGER THAN THE THREE (3) INCH SLEEVE.
 2. UP TO 45% OF THE DRY WEIGHT OF THE REPRESENTATIVE SAMPLE MAY BE RETAINED ON THE #4 SLEEVE (THIS IS THE GRAVEL PORTION OF THE
- 3. THE MATERIAL THAT PASSES THE #4 SIEVE IS THEN REWEIGHED AND THE SIEVE ANALYSIS STARTED, 4. THE REMAINING SAMPLE SHALL MEET THE FOLLOWING CRITERIA:

0-5

0-2.5

PERCENT PASSING
SIEVE SIZE WET SIEVE DRY SIEVE
#4 100 100
#10 70-100 70-100
#40 10-50* 10-75

0-20

* PERCENT PASSING THE #40 SIEVE CAN BE INCREASED TO NO GREATER THAN 75 IF THE PERCENT PASSING THE #100 SIEVE DOES NOT EXCEED 10 AND THE #200 SIEVE DOES NOT EXCEED 5.

SEPTIC NOTES

- I. PROPOSED SEPTIC SYSTEM TO BE STAKED IN THE FIELD BY A LAND SURVEYOR LICENSED IN THE STATE OF CONNECTICUT.
- A BENCHMARK SHALL BE SET WITHIN 10'-15' OF THE PROPOSED SEPTIC SYSTEM PRIOR TO CONSTRUCTION.
 ALL WORK AND MATERIAL (SEPTIC TANK, DISTRIBUTION BOX, PIPE) SHALL CONFORM TO THE CONNECTICUT PUBLIC HEALTH CODE REGULATIONS AND STANDARDS FOR SUBSURFACE SEWAGE DISPOSAL SYSTEM.
- 4. SEWER LINE FROM FOUNDATION WALL TO SEPTIC TANK SHALL BE 4" SCHEDULE 40 PVC ASTM D 1785 AND JOINTS PER HEALTH DEPT. CODE. PIPE FROM SEPTIC TANK TO DISTRIBUTION LINES SHALL BE 4" SOLID PVC CONFORMING TO STMD—3034 AND SDR—35.

 5. SYSTEMS SHALL BE SET LEVEL FOR ENTIRE LENGTH AND HAVE A CENTER TO CENTER SPACING AS CALLED FOR IN THE CONNECTICUT PUBLIC
- HEALTH CODE. THERE ARE PRESENTLY NO KNOWN WATER WELLS WITHIN 75' OF THE PROPOSED SEPTIC SYSTEMS.
- 6. CLEAR AND GRUB THE AREA WHERE THE SEPTIC SYSTEMS AND HOUSES ARE TO BE CONSTRUCTED. ALL TOPSOIL IS TO BE STRIPPED AND
- 7. ALL FILL MATERIAL SHALL BE CLEAN EARTH FREE OF STUMPS, ORGANICS, CONSTRUCTION DEBRIS AND TOPSOIL.

 8. TOPSOIL SHALL BE RE—APPLIED OVER ALL FILL AREAS AND ALL DISTURBED AREAS TO PROVIDE A MINIMUM DEPTH OF FOUR INCHES IN ACCORDANCE WITH THE SLOPE STABILIZATION DETAILS..

CONCEPT SEPTIC SYSTEM DESIGN

LOT 12-1
PRIMARY LEACHING AREA
3 BEDROOM RESIDENCE

PERCOLATION RATE: 5.7 MIN./INCH (NDDH FILE #21000003)
LEACHING AREA REQUIRED: 495 SF

USE TRADITIONAL TRENCH
EFFECTIVE LEACHING AREA OF LEACHING TRENCH 3.0 SF/LF
REQUIRED LENGTH = 495 SF / 3 SF/LF = 165 LF

MLSS CALCULATION HYDRAULIC FACTORS

DEPTH TO RESTRICTIVE LAYER = 24" (POSSIBLE LEDGE)
SLOPE = 2.7%
HYDRAULIC FACTOR (HF) = 48

FLOW FACTOR (FF) = 1.5
PERCOLATION FACTOR (PF) = 1.00 (UP TO 10.0 MIN./INCH)
MLSS REQUIRED: 48 x 1.5 x 1.00 = 72 LF

PROPOSED SYSTEM

USE 2ROWS OF 84 LF

LEACHING AREA PROVIDED = 504 SF

RESERVE LEACHING AREA USE SAME AS PRIMARY SYSTEM LOT 12-10
PRIMARY LEACHING AREA

3 BEDROOM RESIDENCE
PERCOLATION RATE: 10.0 MIN./INCH (NDDH FILE #21000003)
LEACHING AREA REQUIRED: 495 SF

USE TRADITIONAL TRENCH
EFFECTIVE LEACHING AREA OF LEACHING TRENCH 3.0 SF/LF
REQUIRED LENGTH = 495 SF / 3 SF/LF = 165 LF


MLSS CALCULATION HYDRAULIC FACTORS DEPTH TO RESTRICTIVE LAYER = 24" (MOTTLES) SLOPE = 5.5%


HYDRAULIC FACTOR (HF) = 34

FLOW FACTOR (FF) = 1.5 PERCOLATION FACTOR (PF) = 1.0 (UP TO 10.0 MIN./INCH) MLSS REQUIRED: $34 \times 1.5 \times 1.0 = 51.0 \text{ LF}$


PROPOSED SYSTEM
USE 3 ROWS OF 55 LF
LEACHING AREA PROVIDED = 495 SF


RESERVE LEACHING AREA
USE SAME AS PRIMARY SYSTEM






Driveway - Cross Section at Wetland Crossing (Typical)







			LOLA Engineens Inc	
			CLA Engineers, Inc.	
			Civil • Structural • Surveying	
3	11/23/20	NCCG COMMENTS ADDRESSED	OIVIE SINGOIGNIE SONVEINA	
2	09/28/20	WETLAND FLAGS CALLOUTS ADDED		
1	09/20/20	VARIOUS MODIFICATIONS	317 Main Street Norwich, CT 06360 (860) 886-1966 Fax (860) 886-9165	
Nο	ከለጥፑ	PEVISION		

SQUARE 1 BUILDING ASSOCIATES, LLC

4-LOT SUBDIVISION
BROOKLYN, CT

GRADING & CONCEPT SITE DESIGN

5 of 8

Project No.

CLA-6503

Proj. Engineer

D.H.

08/24/20

Date:

EROSION & SEDIMENTATION CONTROL NARRATIVE


- 1. THE EROSION & SEDIMENTATION CONTROL PLAN AND DETAILS HAVE BEEN DEVELOPED AS A STRATEGY TO CONTROL SOIL EROSION AND SEDIMENTATION DURING AND AFTER CONSTRUCTION. THIS PLAN IS BASED ON THE "2002 CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL" BY THE CONNECTICUT COUNCIL ON SOIL AND WATER CONSERVATION IN COOPERATION WITH THE
- CONNECTICUT DEP.


 2. THE PROPOSED LOCATIONS OF SILTATION AND EROSION CONTROL MEASURES ARE SHOWN ON THE PLANS. THE CONTRACTOR SHALL PROVIDED SILT FENCE, STONE CHECK DAMS AND/OR OTHER EROSION CONTROL MEASURES AS NEEDED OR DIRECTED BY THE ENGINEER OR TOWN STAFF TO ADEQUATELY PREVENT SEDIMENT TRANSPORT.
- 3. EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO SITE DISTURBANCE.
- 4. THE CONTRACTOR SHALL INSPECT, REPAIR AND/OR REPLACE EROSION CONTROL MEASURES EVERY 7 DAYS AND IMMEDIATELY FOLLOWING ANY SIGNIFICANT RAINFALL OR SNOW MELT. SEDIMENT DEPOSITS MUST BE REMOVED WHEN WHEN DEPOSITS REACH APPROXIMATELY ONE HALF THE HEIGHT OF THE BARRIER. SEDIMENT CONTROL DEVICES SHALL REMAIN IN PLACE AND BE MAINTAINED BY THE
- CONTRACTOR UNTIL AREAS UPSLOPE ARE PERMANENTLY STABILIZED.

 5. STAKED HAY BALE SILT BARRIERS OR SILT FENCE SHALL BE INSTALLED AROUND ANY TEMPORARY STOCKPILE AREAS. TEMPORARY VEGETATIVE COVER MAY BE REQUIRED (SEE NOTE).
- 6. INLET SEDIMENTATION CONTROL DEVICES SHALL BE INSTALLED UNDER THE GRATES OF ALL NEW CATCH BASINS AT THE TIME OF INSTALLATION, AND UNDER THE GRATES OF EXISTING CATCH BASINS
- IN THE CONSTRUCTION AREA.

 7. CONTINUOUS DUST CONTROL USING WATER, CALCIUM CHLORIDE OR APPROVED EQUAL SHALL BE PROVIDED FOR ALL EARTH STOCKPILES, EARTH PILED ALONG EXCAVATIONS, SURFACES OF BACKFILLED TRENCHES AND GRAVELED ROADWAY SURFACES.
- 8. IF DEWATERING IS NECESSARY DURING ANY TIME OF CONSTRUCTION A CLEAR WATER DISCHARGE SHALL BE PROVIDED AS SHOWN IN THE HAY—BALE BARRIER DEWATERING DETAIL OR ALTERNATE METHOD PROPOSED BY THE CONTRACTOR AND APPROVED BY THE ENGINEER.
- 9. ALL DISTURBED AREAS SHALL BE RESTORED PER THE SLOPE STABILIZATION AND PERMANENT VEGETATION DETAILS. ALL DISTURBED AREAS THAT ARE SLOPED LESS THAN THREE HORIZONTAL TO ONE VERTICAL (3:1) SLOPE SHALL BE LOAMED, SEEDED, FERTILIZED AND MULCHED PER THE PERMANENT VEGETATIVE COVER SPECIFICATIONS. EROSION CONTROL MATTING SHALL BE PROVIDED ON ALL DISTURBED AREAS IS NOT TO BE COMPLETED REFORE OCTOBER 15. THE
- 10. IF FINAL SEEDING OF DISTURBED AREAS IS NOT TO BE COMPLETED BEFORE OCTOBER 15, THE CONTRACTOR SHALL PROVIDE TEMPORARY MULCHING (DORMANT SEEDING MAY BE ATTEMPTED AS WELL) TO PROTECT THE SITE AND DELAY PERMANENT SEEDING.
- 11. WHEN FEASIBLE, TEMPORARY SEEDING OF DISTURBED AREAS THAT HAVE NOT BEEN FINISHED GRADED SHALL BE COMPLETED PRIOR TO OCTOBER 15.
- 12. ANY EROSION WHICH OCCURS WITHIN THE DISTURBED AREAS SHALL BE IMMEDIATELY REPAIRED AND STABILIZED. DURING THE CONSTRUCTION PHASE, INTERCEPTED SEDIMENT SHALL BE RETURNED TO THE SITE. POST SEEDING, INTERCEPTED SEDIMENT, IF ANY, SHALL BE DISPOSED OF IN A MANNER
- APPROVED BY THE TOWN AND ENGINEER.


 13. EROSION AND SEDIMENTATION CONTROL MEASURES SHALL REMAIN IN PLACE UNTIL VEGETATION IS RE-ESTABLISHED OR SLOPES ARE STABILIZED AND REMOVAL IS APPROVED BY THE TOWN.
- 14. UNFORESEEN PROBLEMS WHICH ARE ENCOUNTERED IN THE FIELD SHALL BE SOLVED ACCORDING TO THE "2002 CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL" BY THE CONNECTICUT COUNCIL ON SOIL AND WATER CONSERVATION IN COOPERATION WITH THE CONNECTICUT
- 15. THE CONTRACTOR SHALL PROVIDE THE NAME AND EMERGENCY CONTACT INFORMATION FOR THE PROJECT PERSONNEL RESPONSIBLE FOR EROSION AND SEDIMENTATION CONTROLS PRIOR TO THE START OF CONSTRUCTION.





TYPICAL GRAVEL DRIVEWAY CROSS SECTION

NOT TO SCALE



TEMPORARY VEGETATIVE COVER

A TEMPORARY SEEDING OF RYE GRASS WILL BE COMPLETED WITHIN 15 DAYS OF THE FORMATION OF STOCKPILES. IF THE SOIL IN THE STOCKPILES HAS BEEN COMPACTED BY CONSTRUCTION OPERATIONS IT SHALL BE LOOSENED TO A DEPTH OF 2 INCHES BEFORE THE FERTILIZER, LIME AND SEED IS APPLIED. 10–10–10 FERTILIZER AT A RATE OF 7.5 POUNDS PER 1000 S.F. LIMESTONE AT A RATE OF 90 LBS. PER 1000 S.F. SHALL BE USED. RYE GRASS APPLIED AT A RATE OF 1 LB. PER 1000 S.F. SHALL PROVIDE THE TEMPORARY VEGETATIVE COVER. STRAW FREE FROM WEEDS AND COARSE MATTER SHALL BE USED AT A RATE OF 70–90 LBS. PER 1000 S.F. AS A TEMPORARY MULCH. APPLY MULCH AND DRIVE TRACKED EQUIPMENT UP AND DOWN SLOPE OVER ENTIRE SURFACE SO CLEAT MARKS ARE PARALLEL TO THE CONTOURS.

PERMANENT VEGETATIVE COVER


TOPSOIL WILL BE REPLACED ONCE THE EXCAVATIONS HAVE BEEN COMPLETED AND THE SLOPES ARE GRADED AS SHOWN ON THE PLANS. PROVIDE SLOPE PROTECTION AS CALLED FOR ON THE PLANS AND DETAILS. TOPSOIL SHALL BE SPREAD AT A MINIMUM COMPACTED DEPTH OF <u>4 INCHES</u>. ONCE THE TOPSOIL HAS BEEN SPREAD, ALL STONES TWO INCHES OR LARGER IN ANY DIMENSION WILL BE REMOVED AS WELL AS DEBRIS.

- APPLY AGRICULTURAL GROUND LIMESTONE AT THE RATE OF TWO TONS PER ACRE OR 100 LBS. PER 1000 S.F.
- APPLY 10-10-10 FERTILIZER OR EQUIVALENT AT A RATE OF 300 LBS. PER ACRE OR
- 7.5 LBS. PER 1000 S.F.

 WORK LIMESTONE AND FERTILIZER INTO THE SOIL TO A DEPTH OF 4 INCHES.
- INSPECT SEEDBED BEFORE SEEDING.
- IF TRAFFIC HAS COMPACTED THE SOIL, RETILL COMPACTED AREAS
 APPLY THE FOLLOWING GRASS SEED MIX:


TYPICAL SEED MIXTURE


1 1 3 1 1		
L DISTURBED AREAS	LBS./ACRE	LBS./1000 S.F.
ENTUCKY BLUEGRASS	20	0.45
REEPING RED FESCUE	20	0.45
ERENNIAL RYEGRASS	5	0.10
	45	1.00




TRENCH DETAIL: ELECTRICAL CONDUIT

NOT TO SCALE





NOT TO SCALE



NOT TO SCALE

PROVIDE 4" THICKNESS OF TOPSOIL OVER CLEAN FILL. PREPARE SOIL BEFORE INSTALLING BLANKETS, INCLUDING APPLICATION OF LIME,

BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE BLANKET IN 6" DEEP x 6" WIDE TRENCH, BACKFILL AND COMPACT THE TRENCH AFTER STAPLING.
 ROLL THE BLANKET (A) DOWN OR (B) HORIZONTALLY ACROSS THE SLOPE.
 THE EDGES OF PARALLEL BLANKETS MUST BE STAPLED WITH APPROXIMATELY 2" OVERLAP.
 WHEN BLANKETS MUST BE SPLICED DOWN THE SLOPE, PLACE BLANKETS END OVER

NOTE: ALL PERMANENT EROSION CONTROL BLANKETS ARE TO BE NORTH AMERICAN GREEN BIONET C125BN OR APPROVED EQUAL.

EROSION CONTROL MATTING DETAIL

(FOR 3:1 SLOPES OR GREATER)

TYPICAL LOAM & SEED SECTION DETAIL

(FOR ALL DISTURBED AREAS)

SLOPE STABILIZATION DETAILS

NOT TO SCALE

FOR AT THE UNIT PRICE FOR LOAM, SEED, FERTILIZE & MULCH)

AREA, APPROXIMATELÝ 12" APART.

UNDISTURBED AREA


4" CLEAN FILL


4" TOPSOIL PER PERMANENT VEGETATIVE


COVER NOTES

FERTILIZER, AND SEED MIX PER PERMANENT VEGETATIVE COVER NOTES. (SHALL BE PAID

END (SHINGLE STYLE) WITH APPROXIMATELY 4" OVERLAP. STAPLE THROUGH OVERLAPPED









NOT TO SCALE

1,000 GALLON SEPTIC TANK
NOT TO SCALE



NOT TO SCALE



DRAINAGE PIPE BEDDING DETAIL

NOT TO SCALE



