


LEGEND


| | |
|--|-------------------------|
| | PROPERTY LINE |
| | EASEMENT |
| | STONEWALL |
| | STONEWALL REMAINS |
| | EXISTING INDEX CONTOURS |
| | EXISTING CONTOURS |
| | WETLANDS FLAG |
| | BUILDING SETBACK |
| | IRON PIN |
| | DRILL HOLE |
| | MONUMENT |
| | PROPERTY POINT |
| | UTILITY POLE |



Location Map
SCALE
1" = 1000 FT

Map References

1. Town of Brooklyn, Plan showing land acquired from Annie Weldon by The State of Connecticut, Brooklyn - Pomfret Landing Rd, Scale: 1"=40', Date: September 1935
2. Plan of Brooklyn Manor, Darby Road and New Kimball Road, Brooklyn, Connecticut, Scale: 1"=40', Date: April 1980, Prepared by Kietlyka, Woodis & Pike
3. Subdivision Map "White Brook Estates" Prepared for Eric Lehto, Church Street, Brooklyn, Connecticut, Date: June 2004, Scale: 1"=50', Prepared by Provost and Rovero Inc.
4. Plat of Bounds on Pomfret-Brooklyn Town Line, as Found 1930 and 1931, Scale: 80 Rods (1320") to Inch, Prepared by G. Perry
5. Map Showing Subdivision For Leonard Bissonnette, Pomfret Landing Road, Brooklyn, Connecticut, Scale: 1"=40', Date: November 1973
6. Perimeter Survey Prepared for Jerry & Deb Sullivan, 28 Pomfret Land Road, Brooklyn, Connecticut, Date: September 2010, Scale: 1"=40', Prepared by Archer Surveying LLC
7. Property Survey - Boundary Line Modification, Prepared for A.Kausch and Sons LLC, Church Street/Pomfret Landing, Brooklyn, Connecticut, Date: April 2021, Scale: 1"=80', Prepared by Archer Surveying LLC



Notes

1. This survey has been prepared pursuant to the Regulations of Connecticut State Agencies Section 20-300b-20 and the "Standards for Surveys and Maps in State of Connecticut" as adopted by the Connecticut Association of Land Surveyors, Inc. on September 26, 1948
 - This Survey conforms to a Class "A-2" Horizontal Accuracy
 - Survey Type: Property Survey
 - Boundary Determination: Resurvey
 - Intent: Depict Existing Conditions with Respect to Property Lines
2. Parcels shown as lots 17, 20 and 21 on Assessors Tax Map 37 of the Brooklyn Assessors Office
3. Parcels shown as 7.00, Block D on Assessors Tax Map 47 of the Pomfret Assessors Office
4. Wetlands were flagged in the field by Robert Russo and field located by Archer Surveying LLC

To My Knowledge and Belief this Map is substantially Correct as noted hereon.


Property Survey
Prepared For:
A. Kausch & Sons LLC
Church Street & Pomfret Landing
Brooklyn, Connecticut

DRAWING SCALE: 1"=80'

ARCHER Surveying LLC
18 Providence Road, Brooklyn, CT
(860) 779-2240

Sheet No. 1 OF 4 Project No. 1895 Date: April 10, 2021



CONTINUE - SEE SHEET 3




PLAN




**Wetland Crossing (Typical)
Shared Driveway
Horiz. & Vert. Scale: 1" = 4'**



SHARED DRIVEWAY Wetland Crossing 1
STA 0+00 TO STA 1+00
Horiz. Scale= 1"= 40'
Vert. Scale= 1"= 10'



SHARED DRIVEWAY Wetland Crossing 2
STA 1+50 TO STA 3+00
Horiz. Scale= 1"= 40'
Vert. Scale= 1"= 10'



SHARED DRIVEWAY Wetland Crossing 3
STA 7+50 TO STA 9+00
Horiz. Scale= 1"= 40'
Vert. Scale= 1"= 10'

| | | | |
|---|--|--|--|
| <p>CLA Engineers, Inc. CIVIL • STRUCTURAL • SURVEYING</p> <p>317 Main Street Norwich, CT 06360 (860) 886-1966 Fax (860) 886-9165</p> | | | <p>Project No. CLA-6639</p> <p>Proj. Engineer R.A.D.</p> <p>Date: 04/30/21</p> <p>Sheet No. 2 of 4</p> |
| <p>No. DATE REVISION</p> | | <p>A. KAUSCH & SONS, LLC</p> <p>LOTS 019-37-17, 019-37-20 & 019-37-21 CHURCH ST. SITE DEVELOPMENT BROOKLYN, CT</p> <p>GRADING & SITE DESIGN</p> | |

SELECT FILL SPECIFICATION

SELECT FILL PLACED WITHIN AND ADJACENT TO LEACHING SYSTEM AREAS SHALL BE COMPRISED OF CLEAN SAND, OR SAND AND GRAVEL, FREE FROM ORGANIC MATTER AND FOREIGN SUBSTANCES. THE SELECT FILL SHALL MEET THE FOLLOWING REQUIREMENTS PER THE CONNECTICUT PUBLIC HEALTH CODE FOR USE WITHIN THE LEACHING AREA:

1. THE SELECT FILL SHALL NOT CONTAIN ANY MATERIAL LARGER THAN THE THREE (3) INCH SIEVE.
2. UP TO 45% OF THE DRY WEIGHT OF THE REPRESENTATIVE SAMPLE MAY BE RETAINED ON THE #4 SIEVE (THIS IS THE GRAVEL PORTION OF THE SAMPLE).
3. THE MATERIAL THAT PASSES THE #4 SIEVE IS THEN REWEIGHED AND THE SIEVE ANALYSIS STARTED.
4. THE REMAINING SAMPLE SHALL MEET THE FOLLOWING CRITERIA:

| SIEVE SIZE | PERCENT PASSING WET SIEVE | DRY SIEVE |
|------------|---------------------------|-----------|
| #4 | 100 | 100 |
| #10 | 70-100 | 70-100 |
| #40 | 10-50* | 10-75 |
| #100 | 0-20 | 0-5 |
| #200 | 0-5 | 0-2.5 |

* PERCENT PASSING THE #40 SIEVE CAN BE INCREASED TO NO GREATER THAN 75 IF THE PERCENT PASSING THE #100 SIEVE DOES NOT EXCEED 10 AND THE #200 SIEVE DOES NOT EXCEED 5.

SEPTIC NOTES

1. PROPOSED SEPTIC SYSTEM TO BE STAKED IN THE FIELD BY A LAND SURVEYOR LICENSED IN THE STATE OF CONNECTICUT.
2. A BENCHMARK SHALL BE SET WITHIN 10'-15' OF THE PROPOSED SEPTIC SYSTEM PRIOR TO CONSTRUCTION.
3. ALL WORK AND MATERIAL (SEPTIC TANK, DISTRIBUTION BOX, PIPE) SHALL CONFORM TO THE CONNECTICUT PUBLIC HEALTH CODE REGULATIONS AND STANDARDS FOR SUBSURFACE SEWAGE DISPOSAL SYSTEM.
4. SEWER LINE FROM FOUNDATION WALL TO SEPTIC TANK SHALL BE 4" SCHEDULE 40 PVC - ASTM D 1785 AND JOINTS PER HEALTH DEPT. CODE. PIPE FROM SEPTIC TANK TO DISTRIBUTION LINES SHALL BE 4" SOLID PVC CONFORMING TO STD-3034 AND SDR-35.
5. SYSTEMS SHALL BE SET LEVEL FOR ENTIRE LENGTH AND HAVE A CENTER TO CENTER SPACING AS CALLED FOR IN THE CONNECTICUT PUBLIC HEALTH CODE. THERE ARE PRESENTLY NO KNOWN WATER WELLS WITHIN 75' OF THE PROPOSED SEPTIC SYSTEMS.
6. CLEAR AND GRUB THE AREA WHERE THE SEPTIC SYSTEMS AND HOUSES ARE TO BE CONSTRUCTED. ALL TOPSOIL IS TO BE STRIPPED AND STOCKPILED FOR FUTURE USE.
7. ALL FILL MATERIAL SHALL BE CLEAN EARTH FREE OF STUMPS, ORGANICS, CONSTRUCTION DEBRIS AND TOPSOIL.
8. TOPSOIL SHALL BE RE-APPLIED OVER ALL FILL AREAS AND ALL DISTURBED AREAS TO PROVIDE A MINIMUM DEPTH OF FOUR INCHES IN ACCORDANCE WITH THE SLOPE STABILIZATION DETAILS.

DEEP TEST PIT DATA / SOIL DESCRIPTIONS

PERFORMED BY: Donovan Moe
 WITNESSED BY: NORTHEAST DISTRICT DEPARTMENT OF HEALTH DATE: 03/30/2021

| TEST PIT: 1 | TEST PIT: 2 |
|---------------------------------------|--------------------------------|
| 0" - 10" Topsoil / Organics | 0" - 10" Topsoil / Organics |
| 10" - 16" Orange Brown Fine Sand Loam | 10" - 27" Dark Brown Fine Sand |
| 16" - 34" Tan Compact Sand Loam | 27" - 48" Grey Compact Sand |
| 34" - 78" Grey Sand & Gravel | 48" - 70" Sand & Gravel |
| MOTTLES: 36" | MOTTLES: 32" |
| GROUNDWATER: 66" | GROUNDWATER: 62" |
| LEDGE: NO | LEDGE: NO |
| ROOTS: 46" | ROOTS: 32" |
| RESTRICTIVE: NO | RESTRICTIVE: NO |

| TEST PIT: 3 | TEST PIT: 4 |
|-------------------------------------|--|
| 0" - 12" Topsoil / Organics | 0" - 10" Topsoil / Organics |
| 12" - 30" Tan Orange Fine Sand Loam | 10" - 24" Tan Orange Fine Sand Loam |
| 30" - 48" Grey Sand Layer | 24" - 80" Saturated Grey Sand & Gravel |
| 48" - 72" Sand & Gravel | |
| MOTTLES: 30" | MOTTLES: 28" |
| GROUNDWATER: 65" | GROUNDWATER: 74" |
| LEDGE: NO | LEDGE: NO |
| ROOTS: NO | ROOTS: 30" |
| RESTRICTIVE: NO | RESTRICTIVE: NO |

PERCOLATION DATA

PERC 1 - DEPTH 23"

| TIME | DROP (INCHES) |
|-------|---------------|
| 11:10 | 6.0 |
| 11:12 | 7.0 |
| 11:14 | 8.0 |
| 11:16 | 8.5 |
| 11:18 | 9.25 |
| 11:20 | 9.5 |
| 11:22 | 10.0 |
| 11:25 | 11.0 |
| 11:28 | 11.5 |
| 11:31 | 12.0 |

PERCOLATION RATE > 6.0 MIN./IN.
 NOTES: PERCOLATION TEST PERFORMED ON 3/30/2021 PERFORMED BY Donovan Moe

PERCOLATION DATA

PERC 2 - DEPTH 17"

| TIME | DROP (INCHES) |
|-------|---------------|
| 11:04 | 6.25 |
| 11:10 | 8.25 |
| 11:16 | 9.75 |
| 11:22 | 10.625 |
| 11:34 | 12.125 |
| 11:46 | 13.125 |
| 11:58 | 14.625 |

PERCOLATION RATE > 8.0 MIN./IN.
 NOTES: PERCOLATION TEST PERFORMED ON 3/30/2021 PERFORMED BY Donovan Moe

CONCEPT SEPTIC SYSTEM DESIGN

PROPOSED LOT 1
 PRIMARY LEACHING AREA
 4 BEDROOM RESIDENCE
 PERCOLATION RATE: 6.0 MIN./INCH (NDDH FILE #21000307)
 LEACHING AREA REQUIRED: 557.5 SF

USE TRADITIONAL TRENCH
 EFFECTIVE LEACHING AREA OF LEACHING TRENCH 3.0 SF/LF
 REQUIRED LENGTH = 557.5 SF / 3 SF/LF = 186 LF

MLSS CALCULATION
 HYDRAULIC FACTORS
 DEPTH TO RESTRICTIVE LAYER = 32"
 SLOPE = 5.0%
 HYDRAULIC FACTOR (HF) = 32
 FLOW FACTOR (FF) = 1.0
 PERCOLATION FACTOR (PF) = 1.75 (LESS THAN 10.0 MIN./INCH)
 MLSS REQUIRED: 32 x 1.0 x 1.75 = 52.5 LF

PROPOSED SYSTEM
 USE 3 ROWS OF 65 LF
 LEACHING AREA PROVIDED = 585 SF

RESERVE LEACHING AREA
 USE SAME AS PRIMARY SYSTEM


PROPOSED LOT 2
 PRIMARY LEACHING AREA
 4 BEDROOM RESIDENCE
 PERCOLATION RATE: 8.0 MIN./INCH (NDDH FILE #21000307)
 LEACHING AREA REQUIRED: 557.5 SF

USE TRADITIONAL TRENCH
 EFFECTIVE LEACHING AREA OF LEACHING TRENCH 3.0 SF/LF
 REQUIRED LENGTH = 557.5 SF / 3 SF/LF = 186 LF

MLSS CALCULATION
 HYDRAULIC FACTORS
 DEPTH TO RESTRICTIVE LAYER = 28"
 SLOPE = 4.0%
 HYDRAULIC FACTOR (HF) = 34
 FLOW FACTOR (FF) = 1.0
 PERCOLATION FACTOR (PF) = 1.75 (LESS THAN 10.0 MIN./INCH)
 MLSS REQUIRED: 34 x 1.0 x 1.75 = 52.5 LF

PROPOSED SYSTEM
 USE 3 ROWS OF 65 LF
 LEACHING AREA PROVIDED = 585 SF

RESERVE LEACHING AREA
 USE SAME AS PRIMARY SYSTEM



CONTINUE - SEE SHEET 2

ARCHER Surveying LLC
 18 Providence Road, Brooklyn, CT
 (860) 779-2240

CLA Engineers, Inc.
 CIVIL • STRUCTURAL • SURVEYING
 317 Main Street Norwich, CT 06360
 (860) 886-1966 Fax (860) 886-9165

A. KAUSCH & SONS, LLC

LOTS 019-37-17, 019-37-20 & 019-37-21
CHURCH ST. SITE DEVELOPMENT
BROOKLYN, CT

GRADING & SITE DESIGN

Project No. CLA-6639
 Proj. Engineer R.A.D.
 Date: 04/30/21
 Sheet No. 3 of 4

EROSION & SEDIMENTATION CONTROL NARRATIVE

1. THE EROSION & SEDIMENTATION CONTROL PLAN AND DETAILS HAVE BEEN DEVELOPED AS A STRATEGY TO CONTROL SOIL EROSION AND SEDIMENTATION DURING AND AFTER CONSTRUCTION. THIS PLAN IS BASED ON THE "2002 CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL" BY THE CONNECTICUT COUNCIL ON SOIL AND WATER CONSERVATION IN COOPERATION WITH THE CONNECTICUT DEP.
2. THE PROPOSED LOCATIONS OF SILTATION AND EROSION CONTROL MEASURES ARE SHOWN ON THE PLANS. THE CONTRACTOR SHALL PROVIDED SILT FENCE, STONE CHECK DAMS AND/OR OTHER EROSION CONTROL MEASURES AS NEEDED OR DIRECTED BY THE ENGINEER OR TOWN STAFF TO ADEQUATELY PREVENT SEDIMENT TRANSPORT.
3. EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO SITE DISTURBANCE.
4. THE CONTRACTOR SHALL INSPECT, REPAIR AND/OR REPLACE EROSION CONTROL MEASURES EVERY 7 DAYS AND IMMEDIATELY FOLLOWING ANY SIGNIFICANT RAINFALL OR SNOW MELT. SEDIMENT DEPOSITS MUST BE REMOVED WHEN DEPOSITS REACH APPROXIMATELY ONE HALF THE HEIGHT OF THE BARRIER. SEDIMENT CONTROL DEVICES SHALL REMAIN IN PLACE AND BE MAINTAINED BY THE CONTRACTOR UNTIL AREAS UPSLOPE ARE PERMANENTLY STABILIZED.
5. STAKED HAY BALE SILT BARRIERS OR SILT FENCE SHALL BE INSTALLED AROUND ANY TEMPORARY STOCKPILE AREAS. TEMPORARY VEGETATIVE COVER MAY BE REQUIRED (SEE NOTE).
6. INLET SEDIMENTATION CONTROL DEVICES SHALL BE INSTALLED UNDER THE GRATES OF ALL NEW CATCH BASINS AT THE TIME OF INSTALLATION, AND UNDER THE GRATES OF EXISTING CATCH BASINS IN THE CONSTRUCTION AREA.
7. CONTINUOUS DUST CONTROL USING WATER, CALCIUM CHLORIDE OR APPROVED EQUAL SHALL BE PROVIDED FOR ALL EARTH STOCKPILES, EARTH PILED ALONG EXCAVATIONS, SURFACES OF BACKFILLED TRENCHES AND GRAVELED ROADWAY SURFACES.
8. IF DEWATERING IS NECESSARY DURING ANY TIME OF CONSTRUCTION A CLEAR WATER DISCHARGE SHALL BE PROVIDED AS SHOWN IN THE HAY-BALE BARRIER DEWATERING DETAIL OR ALTERNATE METHOD PROPOSED BY THE CONTRACTOR AND APPROVED BY THE ENGINEER.
9. ALL DISTURBED AREAS SHALL BE RESTORED PER THE SLOPE STABILIZATION AND PERMANENT VEGETATION DETAILS. ALL DISTURBED AREAS THAT ARE SLOPED LESS THAN THREE HORIZONTAL TO ONE VERTICAL (3:1) SLOPE SHALL BE LOAMED, SEED, FERTILIZED AND MULCHED PER THE PERMANENT VEGETATIVE COVER SPECIFICATIONS. EROSION CONTROL MATTING SHALL BE PROVIDED ON ALL DISTURBED AREAS THAT ARE SLOPED MORE THAN THREE HORIZONTAL TO ONE VERTICAL (3:1).
10. IF FINAL SEEDING OF DISTURBED AREAS IS NOT TO BE COMPLETED BEFORE OCTOBER 15, THE CONTRACTOR SHALL PROVIDE TEMPORARY MULCHING (DORMANT SEEDING MAY BE ATTEMPTED AS WELL) TO PROTECT THE SITE AND DELAY PERMANENT SEEDING.
11. WHEN FEASIBLE, TEMPORARY SEEDING OF DISTURBED AREAS THAT HAVE NOT BEEN FINISHED GRADED SHALL BE COMPLETED PRIOR TO OCTOBER 15.
12. ANY EROSION WHICH OCCURS WITHIN THE DISTURBED AREAS SHALL BE IMMEDIATELY REPAIRED AND STABILIZED. DURING THE CONSTRUCTION PHASE, INTERCEPTED SEDIMENT SHALL BE RETURNED TO THE SITE. POST SEEDING, INTERCEPTED SEDIMENT, IF ANY, SHALL BE DISPOSED OF IN A MANNER APPROVED BY THE TOWN AND ENGINEER.
13. EROSION AND SEDIMENTATION CONTROL MEASURES SHALL REMAIN IN PLACE UNTIL VEGETATION IS RE-ESTABLISHED OR SLOPES ARE STABILIZED AND REMOVAL IS APPROVED BY THE TOWN.
14. UNFORESEEN PROBLEMS WHICH ARE ENCOUNTERED IN THE FIELD SHALL BE SOLVED ACCORDING TO THE "2002 CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL" BY THE CONNECTICUT COUNCIL ON SOIL AND WATER CONSERVATION IN COOPERATION WITH THE CONNECTICUT DEP.
15. THE CONTRACTOR SHALL PROVIDE THE NAME AND EMERGENCY CONTACT INFORMATION FOR THE PROJECT PERSONNEL RESPONSIBLE FOR EROSION AND SEDIMENTATION CONTROLS PRIOR TO THE START OF CONSTRUCTION.

NOTE: THE CONTRACTOR SHALL CONTINUALLY STORE THE FOLLOWING MATERIALS ON SITE DURING CONSTRUCTION TO MEET UNEXPECTED EROSION NEEDS

- * 100 LF OF SILT FENCE
- * 10 HAY BALES
- * 10 CY OF WOOD CHIPS OR CRUSHED STONE

TEMPORARY VEGETATIVE COVER

A TEMPORARY SEEDING OF RYE GRASS WILL BE COMPLETED WITHIN 15 DAYS OF THE FORMATION OF STOCKPILES. IF THE SOIL IN THE STOCKPILES HAS BEEN COMPACTED BY CONSTRUCTION OPERATIONS IT SHALL BE LOOSENED TO A DEPTH OF 2 INCHES BEFORE THE FERTILIZER, LIME AND SEED IS APPLIED. 10-10-10 FERTILIZER AT A RATE OF 7.5 POUNDS PER 1000 S.F. LIMESTONE AT A RATE OF 90 LBS. PER 1000 S.F. SHALL BE USED. RYE GRASS APPLIED AT A RATE OF 1 LB. PER 1000 S.F. SHALL PROVIDE THE TEMPORARY VEGETATIVE COVER. STRAW FREE FROM WEEDS AND COARSE MATTER SHALL BE USED AT A RATE OF 70-90 LBS. PER 1000 S.F. AS A TEMPORARY MULCH. APPLY MULCH AND DRIVE TRACKED EQUIPMENT UP AND DOWN SLOPE OVER ENTIRE SURFACE SO GLEAT MARKS ARE PARALLEL TO THE CONTOURS.


PERMANENT VEGETATIVE COVER

TOPSOIL WILL BE REPLACED ONCE THE EXCAVATIONS HAVE BEEN COMPLETED AND THE SLOPES ARE GRADED AS SHOWN ON THE PLANS. PROVIDE SLOPE PROTECTION AS CALLED FOR ON THE PLANS AND DETAILS. TOPSOIL SHALL BE SPREAD AT A MINIMUM COMPACTED DEPTH OF 4 INCHES. ONCE THE TOPSOIL HAS BEEN SPREAD, ALL STONES TWO INCHES OR LARGER IN ANY DIMENSION WILL BE REMOVED AS WELL AS DEBRIS.


- APPLY AGRICULTURAL GROUND LIMESTONE AT THE RATE OF TWO TONS PER ACRE OR 100 LBS. PER 1000 S.F.
- APPLY 10-10-10 FERTILIZER OR EQUIVALENT AT A RATE OF 300 LBS. PER ACRE OR 7.5 LBS. PER 1000 S.F.
- WORK LIMESTONE AND FERTILIZER INTO THE SOIL TO A DEPTH OF 4 INCHES.
- INSPECT SEEDBED BEFORE SEEDING.
- IF TRAFFIC HAS COMPACTED THE SOIL, RETILL COMPACTED AREAS.
- APPLY THE FOLLOWING GRASS SEED MIX:

TYPICAL SEED MIXTURE


| ALL DISTURBED AREAS | LBS./ACRE | LBS./1000 S.F. |
|---------------------|-----------|----------------|
| KENTUCKY BLUEGRASS | 20 | 0.45 |
| CREeping RED FESCUE | 20 | 0.45 |
| PERENNIAL RYEGRASS | 5 | 0.10 |
| | 45 | 1.00 |




STANDARD D-BOX
NOT TO SCALE




1,250 GALLON SEPTIC TANK
NOT TO SCALE




12' x 48' LEACHING TRENCH
NOT TO SCALE




TRENCH DETAIL: ELECTRICAL CONDUIT
NOT TO SCALE




RIP-RAP SPLASH PAD DETAIL
NOT TO SCALE



SILT FENCE SECTION
NOT TO SCALE




TYPICAL DRIVEWAY CROSS SECTION
NOT TO SCALE




1. PROVIDE 4" THICKNESS OF TOPSOIL OVER CLEAN FILL. PREPARE SOIL BEFORE INSTALLING BLANKETS, INCLUDING APPLICATION OF LIME, FERTILIZER, AND SEED MIX PER PERMANENT VEGETATIVE COVER NOTES. (SHALL BE PAID FOR AT THE UNIT PRICE FOR LOAM, SEED, FERTILIZE & MULCH)
2. BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE BLANKET IN 6" DEEP x 6" WIDE TRENCH, BACKFILL AND COMPACT THE TRENCH AFTER STAPLING.
3. ROLL THE BLANKET (A) DOWN OR (B) HORIZONTALLY ACROSS THE SLOPE.
4. THE EDGES OF PARALLEL BLANKETS MUST BE STAPLED WITH APPROXIMATELY 2" OVERLAP.
5. WHEN BLANKETS MUST BE SPLICED DOWN THE SLOPE, PLACE BLANKETS END OVER END (SHINGLE STYLE) WITH APPROXIMATELY 4" OVERLAP. STAPLE THROUGH OVERLAPPED AREA, APPROXIMATELY 12" APART.

NOTE: ALL PERMANENT EROSION CONTROL BLANKETS ARE TO BE NORTH AMERICAN GREEN BIONET C1258M OR APPROVED EQUAL.


EROSION CONTROL MATTING DETAIL (FOR 3:1 SLOPES OR GREATER)




ANTI-TRACKING PAD DETAIL
NOT TO SCALE



DRAINAGE PIPE BEDDING DETAIL
NOT TO SCALE



HDPE FLARED END SECTION
NOT TO SCALE



TYPICAL LOAM & SEED SECTION DETAIL (FOR ALL DISTURBED AREAS)

SLOPE STABILIZATION DETAILS
NOT TO SCALE

ARCHER Surveying LLC
18 Providence Road, Brooklyn, CT
(860) 779-2240

CLA Engineers, Inc.
Civil • Structural • Surveying
317 Main Street Norwich, CT 06360
(860) 886-1966 Fax (860) 886-9165

No. DATE REVISION

A. KAUSCH & SONS, LLC

LOTS 019-37-17, 019-37-20 & 019-37-21
CHURCH ST. SITE DEVELOPMENT
BROOKLYN, CT

Project No. CLA-6639
Proj. Engineer R.A.D.
Date: 04/30/21
Sheet No. 4 of 4

NORTHEASTERN CONNECTICUT COUNCIL OF GOVERNMENTS

ENGINEERING PLAN REVIEW

PERTAINING TO A

3-LOT SUBDIVISION

(ASSESSOR'S MAP/LOT Nos. 019-37-17, 019-37-20 & 019-37-21)

CHURCH STREET

BROOKLYN, CT

(May 7, 2021)

The comments contained herein pertain to my review of plans for a proposed 3-lot residential subdivision located on Church Street in Brooklyn, Connecticut, consisting of four (4) sheets, prepared for A. Kausch & Sons by Archer Surveying, LLC and CLA Engineers, dated April 10, 2021 and April 30, 2021, respectively. Also reviewed were the CLA Drainage Report of April 2021 and the CLA Wetlands Report, dated May 3, 2021. Comments pertain to both wetlands and planning and zoning concerns.

Sheet 1 of 4 – Property Survey Plan

1. Location Map is missing a north arrow.
2. Note 1 under “Notes” does not include the accuracy of the topographic elevations shown on the plan. The accuracy needs to be included as part of this note.
3. Zoning criteria is missing on this plan.
4. A “property line symbol” covers some stone wall symbols but not others in the lots of interest. Why is this so?
5. Wetland delineation certification block and signature of the certified Connecticut soil scientist is missing on the plan.
6. A silt fence, compost/silt sock and/or hay bale sediment control symbol needs to be included in the “Legend.”

Sheets 2 & 3 of 4 – Grading & Site Design Plan

1. The area of disturbed wetlands is not noted on the plan (driveway crossing and underground utilities installation). The areas of disturbance need to be noted on the plan.
2. Underground utilities will disturb wetlands. The route of the utilities should be shown on the plan.

3. Different symbols are used for "Silt Fence." Use one symbol only and make changes to the plan to reflect this.
4. The drainage report for this project was also reviewed. It states that Wetlands Crossing 2 needs three (3) 15" pipes. The site plan and wetland crossing profile only show two (2) pipes. Therefore, an additional pipe needs to be added to the plan and profile along with distances to be maintained between the pipes.
5. Due to the proposed driveway being finished so close to the level of the wetlands, soil test pits should be dug to look for presence of groundwater and mottling, especially within the wetland crossings, to further validate the driveway cross section design depicted on Sheet 4 of 4.
6. Different symbols are used for "Silt Fence." Use one symbol only and make changes to the plan to reflect this.
7. Different symbols are used for "New Property Line." Use one symbol only and make changes to the plan to reflect this.

Sheet 4 of 4 – Notes & Construction Details

1. Any reference to CT DOT Form 817 is to be changed to the current Form 818 designation.

General Comments

2. Even though USDA NRCS soils types with boundaries are included in the wetlands report, they should also be included on the project plans.
3. An overall plan showing the "new" lot lines should be included in the plan set. As it is presented now, it is difficult to see how the proposed subdivision relates to the existing lot configurations.

Syl Pauley, Jr., P.E.

By: _____
Syl Pauley, Jr., P.E., NECCOG Regional Engineer