


LEGEND

- PROPERTY LINE
- - - PROPOSED PROPERTY LINE
- - - EASEMENT
- ○ ○ ○ ○ STONEWALL
- ○ ○ ○ ○ STONEWALL REMAINS
- - - 100' EXISTING INDEX CONTOURS
- - - 100' EXISTING CONTOURS
- #—#—# WETLANDS FLAG
- #—#—# BUILDING SETBACK
- SF—SF— SILT FENCE
- IRON PIN
- DRILL HOLE
- MONUMENT
- PROPERTY POINT
- UTILITY POLE



I have reviewed the inland-wetlands shown on this plan and they appear to be substantially the same as those which I delineated in the field.

Robert C Russo
Certified Soil Scientist




Notes

1. This survey has been prepared pursuant to the Regulations of Connecticut State Agencies Section 20-300b-20 and the "Standards for Surveys and Maps in State of Connecticut" as adopted by the Connecticut Association of Land Surveyors, Inc. on September 26, 1996
 - This Survey conforms to a Class "A-2" Horizontal Accuracy Class "T-2" Vertical Accuracy
 - Survey Type: Property Survey
 - Boundary Determination: Resurvey
 - Intent: Depict Existing Conditions with Respect to Property Lines
2. Parcels shown as lots 17, 20 and 21 on Assessors Tax Map 37 of the Brooklyn Assessors Office
3. Parcels shown as 7.00, Block D on Assessors Tax Map 47 of the Pomfret Assessors Office
4. Wetlands were flagged in the field by Robert Russo and field located by Archer Surveying LLC. Total Area of Wetlands Flagged and located: 218,287 +/- Sq.Ft., 6.39 +/- Acres.
5. Property is Located in the RA Zone: Area: 87,120 Sq.Ft. // 2.0 Acres Frontage: 150' Front/Rear Setback: 50' Side Setback: 40'
6. There is no proposed regulated activities within 500' of the boundary of an adjoining municipality.
7. The applicant is familiar with all the information provided in the application and is aware of the penalties for obtaining a permit through deception or through inaccurate or misleading information.


Map References

1. Town of Brooklyn, Plan showing land acquired from Annie Weldon by the State of Connecticut, Brooklyn - Pomfret Landing Rd, Scale: 1"=40', Date: September 1935
2. Plan of Brooklyn Manor, Darby Road and New Kimball Road, Brooklyn, Connecticut, Scale: 1"=40', Date: April 1980, Prepared by Kieltyka, Woods & Pike
3. Subdivision Map "White Brook Estates" Prepared for Eric Lehto, Church Street, Brooklyn, Connecticut, Date: June 2004, Scale: 1"=50', Prepared by Provost and Rovers Inc.
4. Plat of Bounds on Pomfret-Brooklyn Town Line, as Found 1930 and 1931, Scale: 80 Rods (1320') to Inch, Prepared by G. Perry
5. Map Showing Subdivision For Leonard Bissonette, Pomfret Landing Road, Brooklyn, Connecticut, Scale: 1"=40', Date: November 1973
6. Perimeter Survey Prepared for Jerry & Deb Sullivan, 28 Pomfret Land Road, Brooklyn, Connecticut, Date: September 2010, Scale: 1"=40', Prepared by Archer Surveying LLC
7. Property Survey - Boundary Line Modification, Prepared for A.Kausch and Sons LLC, Church Street/Pomfret Landing, Brooklyn, Connecticut, Date: April 2021, Scale: 1"=80', Prepared by Archer Surveying LLC
8. Property Survey - "First Time Split", Prepared for A. Kausch and Sons LLC, Church Street/Pomfret Landing, Brooklyn, Connecticut, Date: April 2021, Scale: 1"=80', Prepared by Archer Surveying LLC



To My Knowledge and Belief this map is substantially correct as noted hereon.

Paul M. Archer
Paul M. Archer LLS #10027
Date: 7-6-21



REVISIONS	
5/11/2021	Revisions per NECCOG Comments
6/01/2021	Addition of wetlands delineations
7/06/2021	Misc. Revisions

Property Survey


Prepared For:
A. Kausch & Sons LLC
Church Street & Pomfret Landing
Brooklyn, Connecticut

DRAWING SCALE: 1"=80'


ARCHER Surveying LLC
18 Providence Road, Brooklyn, CT
(860) 779-2240

Sheet No.	1 of 4	Project No.	1895	Date:	April 10, 2021
-----------	--------	-------------	------	-------	----------------

CONTINUE - SEE SHEET 3





PLAN




NOTE:
TOPSOIL AND GROUNDWATER DEPTHS WERE OBSERVED ON 5-18-21 AT THE APPROXIMATE LOCATIONS SHOWN ABOVE. GROUNDWATER DEPTH WAS BETWEEN 0-16" IN WETLAND AREAS, AND 16" AND GREATER IN UPLAND AREAS.


Wetland Crossing (Typical)
Shared Driveway
Horiz. & Vert. Scale: 1" = 4'



SHARED DRIVEWAY Wetland Crossing 1
STA 0+00 TO STA 1+00
Horiz. Scale= 1"= 40'
Vert. Scale= 1"= 10'



SHARED DRIVEWAY Wetland Crossing 2
STA 1+50 TO STA 3+00
Horiz. Scale= 1"= 40'
Vert. Scale= 1"= 10'



SHARED DRIVEWAY Wetland Crossing 3
STA 7+50 TO STA 9+00
Horiz. Scale= 1"= 40'
Vert. Scale= 1"= 10'

ARCHER Surveying LLC
18 Providence Road, Brooklyn, CT
(860) 779-2240

No.	DATE	REVISION
2	06/30/21	VARIOUS MODIFICATIONS
1	05/10/21	VARIOUS MODIFICATIONS

CLA Engineers, Inc.
CIVIL • STRUCTURAL • SURVEYING
317 Main Street Norwich, CT 06360
(860) 886-1966 Fax (860) 886-9165

A. KAUSCH & SONS, LLC
Project No. CLA-0639
Proj. Engineer R.A.D.
Date: 04/30/21
Sheet No. 2 of 4

LOTS 019-37-17, 019-37-20 & 019-37-21
CHURCH ST. SITE DEVELOPMENT
BROOKLYN, CT
GRADING & SITE DESIGN

SELECT FILL SPECIFICATION

SELECT FILL PLACED WITHIN AND ADJACENT TO LEACHING SYSTEM AREAS SHALL BE COMPRISED OF CLEAN SAND, OR SAND AND GRAVEL, FREE FROM ORGANIC MATTER AND FOREIGN SUBSTANCES. THE SELECT FILL SHALL MEET THE FOLLOWING REQUIREMENTS PER THE CONNECTICUT PUBLIC HEALTH CODE FOR USE WITHIN THE LEACHING AREA:

1. THE SELECT FILL SHALL NOT CONTAIN ANY MATERIAL LARGER THAN THE THREE (3) INCH SLEEVE.
2. UP TO 45% OF THE DRY WEIGHT OF THE REPRESENTATIVE SAMPLE MAY BE RETAINED ON THE #4 SLEEVE (THIS IS THE GRAVEL PORTION OF THE SAMPLE).
3. THE MATERIAL THAT PASSES THE #4 SIEVE IS THEN REWEIGHED AND THE SIEVE ANALYSIS STARTED.
4. THE REMAINING SAMPLE SHALL MEET THE FOLLOWING CRITERIA:

SIEVE SIZE	PERCENT PASSING WET SIEVE	PERCENT PASSING DRY SIEVE
#4	100	100
#10	70-100	70-100
#40	10-50*	10-75
#100	0-20	0-5
#200	0-5	0-2.5

* PERCENT PASSING THE #40 SIEVE CAN BE INCREASED TO NO GREATER THAN 75 IF THE PERCENT PASSING THE #100 SIEVE DOES NOT EXCEED 10 AND THE #200 SIEVE DOES NOT EXCEED 5.

SEPTIC NOTES

1. PROPOSED SEPTIC SYSTEM TO BE STAKED IN THE FIELD BY A LAND SURVEYOR LICENSED IN THE STATE OF CONNECTICUT.
2. A BENCHMARK SHALL BE SET WITHIN 10'-15' OF THE PROPOSED SEPTIC SYSTEM PRIOR TO CONSTRUCTION.
3. ALL WORK AND MATERIAL (SEPTIC TANK, DISTRIBUTION BOX, PIPE) SHALL CONFORM TO THE CONNECTICUT PUBLIC HEALTH CODE REGULATIONS AND STANDARDS FOR SUBSURFACE SEWAGE DISPOSAL SYSTEM.
4. SEWER LINE FROM FOUNDATION WALL TO SEPTIC TANK SHALL BE 4" SCHEDULE 40 PVC - ASTM D 1785 AND JOINTS PER HEALTH DEPT. CODE. PIPE FROM SEPTIC TANK TO DISTRIBUTION LINES SHALL BE 4" SOLID PVC CONFORMING TO STD-3034 AND SDR-35.
5. SYSTEMS SHALL BE SET LEVEL FOR ENTIRE LENGTH AND HAVE A CENTER TO CENTER SPACING AS CALLED FOR IN THE CONNECTICUT PUBLIC HEALTH CODE. THERE ARE PRESENTLY NO KNOWN WATER WELLS WITHIN 75' OF THE PROPOSED SEPTIC SYSTEMS.
6. CLEAR AND GRUB THE AREA WHERE THE SEPTIC SYSTEMS AND HOUSES ARE TO BE CONSTRUCTED. ALL TOPSOIL IS TO BE STRIPPED AND STOCKPILED FOR FUTURE USE.
7. ALL FILL MATERIAL SHALL BE CLEAN EARTH FREE OF STUMPS, ORGANICS, CONSTRUCTION DEBRIS AND TOPSOIL.
8. TOPSOIL SHALL BE RE-APPLIED OVER ALL FILL AREAS AND ALL DISTURBED AREAS TO PROVIDE A MINIMUM DEPTH OF FOUR INCHES IN ACCORDANCE WITH THE SLOPE STABILIZATION DETAILS.

DEEP TEST PIT DATA / SOIL DESCRIPTIONS

PERFORMED BY: Donovan Moe
 WITNESSED BY: NORTHEAST DISTRICT DEPARTMENT OF HEALTH DATE: 03/30/2021

TEST PIT: 1	TEST PIT: 2
0" - 10" Topsoil / Organics	0" - 10" Topsoil / Organics
10" - 16" Orange Brown Fine Sand Loam	10" - 27" Dark Brown Fine Sand
16" - 34" Tan Compact Sand Loam	27" - 48" Grey Compact Sand
34" - 78" Grey Sand & Gravel	48" - 70" Sand & Gravel
MOTTLES: 36"	MOTTLES: 32"
GROUNDWATER: 66"	GROUNDWATER: 62"
LEDGE: NO	LEDGE: NO
ROOTS: 46"	ROOTS: 32"
RESTRICTIVE: NO	RESTRICTIVE: NO

TEST PIT: 3	TEST PIT: 4
0" - 12" Topsoil / Organics	0" - 10" Topsoil / Organics
12" - 30" Tan Orange Fine Sand Loam	10" - 24" Tan Orange Fine Sand Loam
30" - 48" Grey Sand Layer	24" - 80" Saturated Grey Sand & Gravel
48" - 72" Sand & Gravel	
MOTTLES: 30"	MOTTLES: 28"
GROUNDWATER: 65"	GROUNDWATER: 74"
LEDGE: NO	LEDGE: NO
ROOTS: NO	ROOTS: 30"
RESTRICTIVE: NO	RESTRICTIVE: NO

PERCOLATION DATA
 PERC 1 - DEPTH 23"

TIME	DROP (INCHES)
11:10	6.0
11:12	7.0
11:14	8.0
11:16	8.5
11:18	9.25
11:20	9.5
11:22	10.0
11:25	11.0
11:28	11.5
11:31	12.0

PERCOLATION RATE > 6.0 MIN./IN.

NOTES:
 PERCOLATION TEST PERFORMED ON 3/30/2021
 PERFORMED BY Donovan Moe

PERCOLATION DATA
 PERC 2 - DEPTH 17"

TIME	DROP (INCHES)
11:04	6.25
11:10	8.25
11:16	9.75
11:22	10.625
11:34	12.125
11:46	13.125
11:58	14.625

PERCOLATION RATE > 8.0 MIN./IN.

NOTES:
 PERCOLATION TEST PERFORMED ON 3/30/2021
 PERFORMED BY Donovan Moe

CONCEPT SEPTIC SYSTEM DESIGN

PROPOSED LOT 1
 PRIMARY LEACHING AREA
 4 BEDROOM RESIDENCE
 PERCOLATION RATE: 8.0 MIN./INCH (NDDH FILE #21000307)
 LEACHING AREA REQUIRED: 557.5 SF

USE TRADITIONAL TRENCH
 EFFECTIVE LEACHING AREA OF LEACHING TRENCH 3.0 SF/LF
 REQUIRED LENGTH = 557.5 SF / 3 SF/LF = 186 LF

MLSS CALCULATION
 HYDRAULIC FACTORS
 DEPTH TO RESTRICTIVE LAYER = 32"
 SLOPE = 5.0%
 HYDRAULIC FACTOR (HF) = 32
 FLOW FACTOR (FF) = 1.0
 PERCOLATION FACTOR (PF) = 1.75 (LESS THAN 10.0 MIN./INCH)
 MLSS REQUIRED: 32 x 1.0 x 1.75 = 56.0 LF

PROPOSED SYSTEM
 USE 3 ROWS OF 65 LF
 LEACHING AREA PROVIDED = 585 SF

RESERVE LEACHING AREA
 USE SAME AS PRIMARY SYSTEM


PROPOSED LOT 2
 PRIMARY LEACHING AREA
 4 BEDROOM RESIDENCE
 PERCOLATION RATE: 8.0 MIN./INCH (NDDH FILE #21000307)
 LEACHING AREA REQUIRED: 557.5 SF

USE TRADITIONAL TRENCH
 EFFECTIVE LEACHING AREA OF LEACHING TRENCH 3.0 SF/LF
 REQUIRED LENGTH = 557.5 SF / 3 SF/LF = 186 LF

MLSS CALCULATION
 HYDRAULIC FACTORS
 DEPTH TO RESTRICTIVE LAYER = 28"
 SLOPE = 4.0%
 HYDRAULIC FACTOR (HF) = 34
 FLOW FACTOR (FF) = 1.0
 PERCOLATION FACTOR (PF) = 1.75 (LESS THAN 10.0 MIN./INCH)
 MLSS REQUIRED: 34 x 1.0 x 1.75 = 59.5 LF

PROPOSED SYSTEM
 USE 3 ROWS OF 65 LF
 LEACHING AREA PROVIDED = 585 SF

RESERVE LEACHING AREA
 USE SAME AS PRIMARY SYSTEM



PLAN

SCALE: 1"=40'

CONTINUE - SEE SHEET 2

ARCHER Surveying LLC
 18 Providence Road, Brooklyn, CT
 (860) 779-2240


<p>CLA Engineers, Inc. CIVIL • STRUCTURAL • SURVEYING 317 Main Street Norwich, CT 06360 (860) 886-1966 Fax (860) 886-9165</p>		<p>Project No. CLA-6639</p>
<p>2 06/30/21 VARIOUS MODIFICATIONS</p>	<p>1 05/10/21 VARIOUS MODIFICATIONS</p>	<p>Proj. Engineer R.A.D.</p>
<p>No. DATE REVISION</p>		<p>Date: 04/30/21</p>
<p>A. KAUSCH & SONS, LLC</p>		<p>Sheet No. 3 of 4</p>
<p>LOTS 019-37-17, 019-37-20 & 019-37-21 CHURCH ST. SITE DEVELOPMENT BROOKLYN, CT</p>		<p>GRADING & SITE DESIGN</p>

EROSION & SEDIMENTATION CONTROL NARRATIVE

1. THE EROSION & SEDIMENTATION CONTROL PLAN AND DETAILS HAVE BEEN DEVELOPED AS A STRATEGY TO CONTROL SOIL EROSION AND SEDIMENTATION DURING AND AFTER CONSTRUCTION. THIS PLAN IS BASED ON THE "2002 CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL" BY THE CONNECTICUT COUNCIL ON SOIL AND WATER CONSERVATION IN COOPERATION WITH THE CONNECTICUT DEP.
2. THE PROPOSED LOCATIONS OF SILTATION AND EROSION CONTROL MEASURES ARE SHOWN ON THE PLANS. THE CONTRACTOR SHALL PROVIDE SILT FENCE, STONE CHECK DAMS AND/OR OTHER EROSION CONTROL MEASURES AS NEEDED OR DIRECTED BY THE ENGINEER OR TOWN STAFF TO ADEQUATELY PREVENT SEDIMENT TRANSPORT.
3. EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO SITE DISTURBANCE.
4. THE CONTRACTOR SHALL INSPECT, REPAIR AND/OR REPLACE EROSION CONTROL MEASURES EVERY 7 DAYS AND IMMEDIATELY FOLLOWING ANY SIGNIFICANT RAINFALL OR SNOW MELT. SEDIMENT DEPOSITS MUST BE REMOVED WHEN WHEN DEPOSITS REACH APPROXIMATELY ONE HALF THE HEIGHT OF THE BARRIER. SEDIMENT CONTROL DEVICES SHALL REMAIN IN PLACE AND BE MAINTAINED BY THE CONTRACTOR UNTIL AREAS UPSLOPE ARE PERMANENTLY STABILIZED.
5. STAKED HAY BALE SILT BARRIERS OR SILT FENCE SHALL BE INSTALLED AROUND ANY TEMPORARY STOCKPILE AREAS. TEMPORARY VEGETATIVE COVER MAY BE REQUIRED (SEE NOTE).
6. INLET SEDIMENTATION CONTROL DEVICES SHALL BE INSTALLED UNDER THE GRATES OF ALL NEW CATCH BASINS AT THE TIME OF INSTALLATION, AND UNDER THE GRATES OF EXISTING CATCH BASINS IN THE CONSTRUCTION AREA.
7. CONTINUOUS DUST CONTROL USING WATER, CALCIUM CHLORIDE OR APPROVED EQUAL SHALL BE PROVIDED FOR ALL EARTH STOCKPILES, EARTH PILED ALONG EXCAVATIONS, SURFACES OF BACKFILLED TRENCHES AND GRAVELED ROADWAY SURFACES.
8. IF DEWATERING IS NECESSARY DURING ANY TIME OF CONSTRUCTION A CLEAR WATER DISCHARGE SHALL BE PROVIDED AS SHOWN IN THE HAY-BALE BARRIER DEWATERING DETAIL OR ALTERNATE METHOD PROPOSED BY THE CONTRACTOR AND APPROVED BY THE ENGINEER.
9. ALL DISTURBED AREAS SHALL BE RESTORED PER THE SLOPE STABILIZATION AND PERMANENT VEGETATION DETAILS. ALL DISTURBED AREAS THAT ARE SLOPED LESS THAN THREE HORIZONTAL TO ONE VERTICAL (3:1) SLOPE SHALL BE LOAMED, SEEDED, FERTILIZED AND MULCHED PER THE PERMANENT VEGETATIVE COVER SPECIFICATIONS. EROSION CONTROL MATTING SHALL BE PROVIDED ON ALL DISTURBED AREAS THAT ARE SLOPED MORE THAN THREE HORIZONTAL TO ONE VERTICAL (3:1).
10. IF FINAL SEEDING OF DISTURBED AREAS IS NOT TO BE COMPLETED BEFORE OCTOBER 15, THE CONTRACTOR SHALL PROVIDE TEMPORARY MULCHING (DORMANT SEEDING MAY BE ATTEMPTED AS WELL) TO PROTECT THE SITE AND DELAY PERMANENT SEEDING.
11. WHEN FEASIBLE, TEMPORARY SEEDING OF DISTURBED AREAS THAT HAVE NOT BEEN FINISHED GRADED SHALL BE COMPLETED PRIOR TO OCTOBER 15.
12. ANY EROSION WITHIN THE DISTURBED AREAS SHALL BE IMMEDIATELY REPAIRED AND STABILIZED. DURING THE CONSTRUCTION PHASE, INTERCEPTED SEDIMENT SHALL BE RETURNED TO THE SITE. POST SEEDING, INTERCEPTED SEDIMENT, IF ANY, SHALL BE DISPOSED OF IN A MANNER APPROVED BY THE TOWN AND ENGINEER.
13. EROSION AND SEDIMENTATION CONTROL MEASURES SHALL REMAIN IN PLACE UNTIL VEGETATION IS RE-ESTABLISHED OR SLOPES ARE STABILIZED AND REMOVAL IS APPROVED BY THE TOWN.
14. UNFORESEEN PROBLEMS WHICH ARE ENCOUNTERED IN THE FIELD SHALL BE SOLVED ACCORDING TO THE "2002 CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL" BY THE CONNECTICUT COUNCIL ON SOIL AND WATER CONSERVATION IN COOPERATION WITH THE CONNECTICUT DEP.
15. THE CONTRACTOR SHALL PROVIDE THE NAME AND EMERGENCY CONTACT INFORMATION FOR THE PROJECT PERSONNEL RESPONSIBLE FOR EROSION AND SEDIMENTATION CONTROLS PRIOR TO THE START OF CONSTRUCTION.

NOTE: THE CONTRACTOR SHALL CONTINUALLY STORE THE FOLLOWING MATERIALS ONSITE DURING CONSTRUCTION TO MEET UNEXPECTED EROSION NEEDS


- * 100 LF OF SILT FENCE
- * 10 HAY BALES
- * 10 CY OF WOOD CHIPS OR CRUSHED STONE



TYPICAL DRIVEWAY CROSS SECTION

NOT TO SCALE

REMOVE EXISTING TOPSOIL AND PROVIDE CRUSHED STONE TO CT DOT 818 M.02.05 AS NEEDED TO REACH SUB-BASE AT WETLAND CROSSINGS



HDPE FLARED END SECTION

NOT TO SCALE

TEMPORARY VEGETATIVE COVER

A TEMPORARY SEEDING OF RYE GRASS WILL BE COMPLETED WITHIN 15 DAYS OF THE FORMATION OF STOCKPILES. IF THE SOIL IN THE STOCKPILES HAS BEEN COMPACTED BY CONSTRUCTION OPERATIONS IT SHALL BE LOOSENEED TO A DEPTH OF 2 INCHES BEFORE THE FERTILIZER, LIME AND SEED IS APPLIED. 10-10-10 FERTILIZER AT A RATE OF 7.5 POUNDS PER 1000 S.F. LIMESTONE AT A RATE OF 80 LBS. PER 1000 S.F. SHALL BE USED. RYE GRASS APPLIED AT A RATE OF 1 LB. PER 1000 S.F. SHALL PROVIDE THE TEMPORARY VEGETATIVE COVER. STRAW FREE FROM WEEDS AND COARSE MATTER SHALL BE USED AT A RATE OF 70-90 LBS. PER 1000 S.F. AS A TEMPORARY MULCH. APPLY MULCH AND DRIVE TRACKED EQUIPMENT UP AND DOWN SLOPE OVER ENTIRE SURFACE SO CLEAT MARKS ARE PARALLEL TO THE CONTOURS.


PERMANENT VEGETATIVE COVER

TOPSOIL WILL BE REPLACED ONCE THE EXCAVATIONS HAVE BEEN COMPLETED AND THE SLOPES ARE GRADED AS SHOWN ON THE PLANS. PROVIDE SLOPE PROTECTION AS CALLED FOR ON THE PLANS AND DETAILS. TOPSOIL SHALL BE SPREAD AT A MINIMUM COMPACTED DEPTH OF 4 INCHES. ONCE THE TOPSOIL HAS BEEN SPREAD, ALL STONES TWO INCHES OR LARGER IN ANY DIMENSION WILL BE REMOVED AS WELL AS DEBRIS.

- APPLY AGRICULTURAL GROUND LIMESTONE AT THE RATE OF TWO TONS PER ACRE OR 100 LBS. PER 1000 S.F.
- APPLY 10-10-10 FERTILIZER OR EQUIVALENT AT A RATE OF 300 LBS. PER ACRE OR 7.5 LBS. PER 1000 S.F.
- WORK LIMESTONE AND FERTILIZER INTO THE SOIL TO A DEPTH OF 4 INCHES.
- INSPECT SEEDBED BEFORE SEEDING.
- IF TRAFFIC HAS COMPACTED THE SOIL, RETILL COMPACTED AREAS.
- APPLY THE FOLLOWING GRASS SEED MIX:


TYPICAL SEED MIXTURE

ALL DISTURBED AREAS	LBS./ACRE	LBS./1000 S.F.
KENTUCKY BLUEGRASS	20	0.45
CREeping RED FESCUE	20	0.45
PERENNIAL RYEGRASS	5	0.10
	45	1.00




TRENCH DETAIL: ELECTRICAL CONDUIT

NOT TO SCALE




EROSION CONTROL MATTING DETAIL (FOR 3:1 SLOPES OR GREATER)



TYPICAL LOAM & SEED SECTION DETAIL (FOR ALL DISTURBED AREAS)


SLOPE STABILIZATION DETAILS

NOT TO SCALE




STANDARD D-BOX

NOT TO SCALE




12' x 48' LEACHING TRENCH

NOT TO SCALE




PLAN




SECTION RIP-RAP SPLASH PAD DETAIL

NOT TO SCALE




ANTI-TRACKING PAD DETAIL

NOT TO SCALE




1,250 GALLON SEPTIC TANK

NOT TO SCALE



SILT FENCE SECTION

NOT TO SCALE



DRAINAGE PIPE BEDDING DETAIL

NOT TO SCALE

ARCHER Surveying LLC
18 Providence Road, Brooklyn, CT
(860) 779-2240

<p>CLA Engineers, Inc. Civil • Structural • Surveying</p> <p>317 Main Street Norwich, CT 06360 (860) 886-1066 Fax (860) 886-9165</p>		<p>Project No. CLA-6639</p> <p>Proj. Engineer R.A.D.</p> <p>Date: 04/30/21</p> <p>Sheet No. 4 of 4</p>
<p>1 05/10/21 VARIOUS MODIFICATIONS</p>	<p>NO. DATE REVISION</p>	<p>A. KAUSCH & SONS, LLC</p> <p>LOTS 019-37-17, 019-37-20 & 019-37-21 CHURCH ST. SITE DEVELOPMENT BROOKLYN, CT</p> <p>NOTES & CONSTRUCTION DETAILS</p>