
# Two Lot Resubdivision 40 Almada Drive Brooklyn, Connecticut


Prepared for
Paul Lehto
40 Almada Drive
Brooklyn, Connecticut, 06234

# **PROPERTY OWNER & APPLICANT**

PROPERTY OWNER & APPLICANT: LEHTO, PAUL R. 40 ALMADA DRIVE BROOKLYN, CT 06234

## LEGEND TO DRAWINGS






# INDEX TO DRAWINGS

DRAWING NO.	DESCRIPTION OF DRAWINGS
1	<b>Boundary Survey (Archer Surveying)</b>
2	<b>Existing Conditions (Archer Surveying)</b>
3	History Plan 1 (Archer Surveying)
4	History Plan 2 (Archer Surveying)
5	Subdivision Record Plan
6	Site Analysis Plan
7	Lot Development Plan - Lot 1 & Lot 2
8	Stormwater Management Plan and
	<b>Erosion &amp; Sedimentation Control Details</b>
9	Construction Details

March 31, 2021





The Subdivision Regulations of the Brooklyn Planning and Zoning Commission are a part of this plan.

Approval of this plan is contingent on completion of the requirements of said regulations, excepting any variances or modifications made by the Commission.

Any such variances or modifications are on file in the office of the Commission.


Adopted October 4, 2006


Effective October 30, 2006


FIRST SELECTMAN

M:\6000\6300\6383 Paradise Dr. Subdivision\Drawings\2 Lot Subdivision\6383 - 2 Lot Subdivision


CLA











## PROPOSED DEVELOPMENT

THE PROPOSED DEVELOPMENT IS A 2 LOT RESIDENTIAL SUBDIVISION ALONG ALMADA DRIVE AND PARADISE DRIVE IN BROOKLYN, CT. THERE ARE NO PROPOSED PUBLIC IMPROVEMENTS AS PART OF THE DEVELOPMENT. THE PROPOSED LIMITS OF DISTURBANCE HAVE BEEN SHOWN ON PLANS. THE PROPOSED DEVELOPMENT WILL DISTURB APPROXIMATELY 2.7 ACRES.

THERE IS NO PROPOSED INLAND WETLAND DISTURBANCE.
 THERE IS APPROXIMATELY 56,350 SF OF PROPOSED WORK WITHIN THE 125-FOOT INLAND WETLAND UPLAND REVIEW AREA.

3. THERE IS 100-YEAR FLOOD PLAIN LOCATED ON A PORTION OF THE PROPERTY, THERE IS NO PROPOSED WORK WITHIN THIS AREA. THE PROPERTY LIES WITHIN ZONE C "AREAS OF MINIMAL FLOODING". (FIRM MAP #0901640008A, EFFECTIVE DATE: JANUARY 3, 1985)

4. NO PORTION OF THE LOT LIES WITHIN THE COASTAL MANAGEMENT AREA.

NO PORTION OF THE LOT LIES WITHIN THE COASTAL MANAGEMENT AREA.


NO PORTION OF THE LOT LIES WITHIN THE AQUIFER PROTECTION AREA

7. THE RESIDENTIAL LOTS WILL BE SERVED BY ONSITE SEPTIC SYSTEMS. B. THE RESIDENTIAL LOTS WILL BE SERVED BY INDIVIDUAL WELLS.

## GENERAL NOTES

- CONTRACTOR SHALL CONTACT "CALL BEFORE YOU DIG" AT 811 AT LEAST 2 FULL WORKING DAYS PRIOR TO THE START OF CONSTRUCTION.
- 2. INFORMATION SHOWN ON THE DRAWINGS RELATING TO MATERIALS, CONDITIONS, AND/OR LOCATIONS OF EXISTING STRUCTURES AND UTILITIES HAS BEEN COMPILED FROM AVAILABLE INFORMATION INCLUDING FIELD SURVEY, UTILITY COMPANY AND TOWN RECORD MAPS AND DRAWINGS, AND IS NOT GUARANTEED ACCURATE OR COMPLETE.
- 3. THE CONTRACTOR SHALL EXCAVATE TEST PITS AS NEEDED OR AS DIRECTED TO VERIFY UTILITY INFORMATION.
- 4. MAINTENANCE AND PROTECTION OF TRAFFIC:
- A. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ALL MAINTENANCE AND PROTECTION OF TRAFFIC, TRAFFIC CONTROL, TEMPORARY SIGNING OR BARRICADES AND TEMPORARY LANE CLOSURES. CONTINUOUS ACCESS FOR BUSES AND EMERGENCY VEHICLES SHALL BE MAINTAINED AT ALL TIMES.
- B. PASSAGE OF TRAFFIC ON ROADWAYS: A MINIMUM OF ONE LANE FOR TRAFFIC SHALL BE MAINTAINED AT ALL TIMES. THE CONTRACTOR SHALL PERFORM HIS OPERATIONS TO MINIMIZE DISRUPTIONS TO TRAFFIC WITHIN THE PROJECT SITE.
- C. RESIDENTS OR BUSINESSES WITH DRIVES AFFECTED BY CONSTRUCTION SHALL BE NOTIFIED BY THE CONTRACTOR AT LEAST 48 HOURS BEFORE CONSTRUCTION BEGINS AND SHALL BE ALLOWED CONTINUOUS ACCESS TO THEIR PROPERTY.
- D. CERTIFIED FLAGMEN SHALL BE USED FOR TRAFFIC CONTROL AS NEEDED THROUGHOUT THE DURATION OF CONSTRUCTION.
- E. CONSTRUCTION SIGNS MUST CONFORM TO THE SIGNING REQUIREMENTS OUTLINED IN THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD)". ALL SIGN FACES SHALL BE REFLECTORIZED.
- 4. THE CONTRACTOR SHALL CONFINE HIS OPERATIONS AND ACTIVITIES FOR CONSTRUCTION PURPOSES WITHIN THE STREET LINES, EASEMENTS AND PROPERTY AS SHOWN ON THE DRAWINGS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO EXISTING PAVEMENT, ROADWAY, SIDEWALKS, ETC., OUTSIDE OF THE WORK AREA AND SHALL REPAIR SUCH DAMAGE.
- 5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE TEMPORARY AND PERMANENT SUPPORT OF ALL EXISTING UTILITY POLES IN AN ADJACENT TO THE CONSTRUCTION AREA AND SHALL COMPLY WITH ALL THE REQUIREMENTS AND SPECIAL DETAILS FOR THE SUPPORT OF UTILITIES REQUIRED BY UTILITY AGENCIES.
- 6. MATERIAL STOCKPILE AND STAGING AREAS: THE CONTRACTOR SHALL LOCATE STOCKPILE, MATERIAL STORAGE AND EQUIPMENT STORAGE AREAS AS SHOWN ON THE PLANS. PRIOR TO THE START OF CONSTRUCTION THE CONTRACTOR SHALL IDENTIFY THESE AREAS AND PROVIDE EROSION AND SEDIMENTATION CONTROL MEASURES AS REQUIRED. ADJUSTMENTS TO THESE LOCATIONS MAY BE MADE IN THE FIELD PROVIDED THAT EROSION AND SEDIMENTATION CONTROL MEASURES ARE FURNISHED & INSTALLED AND IN NO CASE MAY THEY BE RELOCATED WITHIN THE 125-FOOT INLAND WETLAND UPLAND REVIEW AREA OR BEYOND THE PROPOSED LIMITS OF DISTURBANCE.
- 7. IF BLASTING IS PERFORMED A PRE—BLAST SURVEY WILL BE REQUIRED. ANY AND ALL BLASTING SHALL CONFORM TO THE REGULATIONS SET FORTH BY THE TOWN AND SHALL BE APPROVED BY THE APPROPRIATE TOWN AGENCIES AND ADJACENT UTILITY OWNERS.
- 3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESETTING TO GRADE ALL FRAMES, GRATES,COVERS, VALVE BOXES, ACCESS COVERS, AND ALL OTHER ITEMS WHICH NORMALLY MUST HAVE A FIXED RELATION TO FINISHED GRADE.
- ALL WORK TO CONFORM TO THE STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR ROADS, BRIDGES AND INCIDENTAL CONSTRUCTION FORM 818, DATED JULY 2020, AS REVISED.
- 10. ALL FILL MATERIAL (BORROW) IMPORTED TO THE SITE SHALL BE "CLEAN FILL" IN ACCORDANCE WITH DEEP'S SOLID WASTE MANAGEMENT REGULATIONS (RCSA SECTION 22a-209-1).

	Soil Data
3	Ridgebury, Leicester, and Whitman soils, extremely stony
17	Timakwa and Natchaug Soils, 0 to 2 percent slopes
21A	Ninigret and Tisbury soils, 0 to 5 percent slopes
38C	Hinckley gravelly sandy loam, 3 to 15 percent slopes
46B	Woodbridge fine sandy loam, 2 to 8 percent slopes, very stony
52C	Sutton fine sandy loam, 2 to 15 percent slopes, extremely stony
62C	Canton and Charlton soils, 3 to 15 percent slopes, extremely stony
62D	Canton and Charlton soils, 15 to 35 percent slopes, extremely stony
73C	Charlton-Chatfield complex, 3 to 15 percent slopes, very rocky
73E	Charlton-Chatfield complex, 15 to 45 percent slopes, very rocky
75E	Hollis-Chatfield-Rock outcrop complex, 15 to 45 percent slopes
W	Water





Subdivision Plan Prepared for Paul R. Lehto #40 Almada Drive, Brooklyn, Connecticut

No. DATE

Two Lot Resubdivision 40 Almada Drive Brooklyn, Connecticut

Site Analysis Plan

B86-9165


Project No.
CLA-6383

Proj. Engineer
K.J.H.

Date:
3/31/2021

Sheet No.





## Conceptual Lot 1 Development

TEST PIT DATA NDDH File No. 12000186 Testing Conducted on 2/15/18 by Terre Bombard, R.S.

<u>TP 6A-1 (2018)</u> Mottles: N/O Ground Water: N/O Ledge: 67" 0-9" Topsoil/Roots

9-28" Very Fine Loamy Sand/Moist 28-67" Compact Very Fine Loamy Sand <u>TP 6A-2 (2018)</u> Mottles: 20" Ground Water: 20"

Ledge: 67" 0-8" Topsoil 8-20" Very Fine Loamy Sand/Wet 20-56" Groundwater

<u>TP 3 (2019)</u> Mottles: 30" Ground Water: N/O Ledge: N/O Roots: 42" 0-12" Topsoil 12-30" OB/YB Fine Sandy Loam 30-70" GR Sandy Loam Till. Mottled

## PERCOLATION TEST DATA Performed by CLA Engineers, Inc. on 9/28/20

Perc 6A-1: Depth = 24" Pre-soak: Yes

(Inches)

12"

15"

21"

22.5"

24"

Min. Perc Rate = 4 min./inch

18"

20"

Time

3:00

3:05

3:10

3:15

3:20

3:25

3:30

Measuredown Change

(inches)

-3

-3

-2

-1

-1.5

-1.5

SEPTIC SYSTEM DESIGN
PRIMARY LEACHING AREA
3 BEDROOM RESIDENCE PERCOLATION RATE: 4 MIN./INCH LEACHING AREA REQUIRED: <u>495 SF</u>

USE 12"x48" STONE TRENCH EFFECTIVE LEACHING AREA OF LEACHING TRENCH 3.0 SF/LF REQUIRED LENGTH = 495 SF / 3.0 SF/LF = 165 LF

DEPTH TO RESTRICTIVE LAYER = 20" SLOPE = 6 VF / 71 LF = 8.4% HYDRAULIC FACTOR (HF) = 30FLOW FACTOR (FF) = 1.5 PERCOLATION FACTOR (PF) = 1.0 (UP TO 10.0 MIN./INCH) MLSS REQUIRED:  $30 \times 1.5 \times 1.0 = 45 \text{ LF}$ 

PROPOSED SYSTEM
USE 3 ROWS OF 55 LF LEACHING AREA PROVIDED = 495 SF RESERVE LEACHING AREA USE SAME AS PRIMARY SYSTEM

## Conceptual Lot 2 Development

TEST PIT DATA NDDH File No. 12000186 Testing Conducted on 8/6/20 by Sherry McGann, R.S.

Ledge: 100" 0-13" Topsoil

13-32" OB Fine Sandy

32-100" GR Mottled Sandy

Loam Till

<u>TP 6-3</u> Mottles: 24" <u>TP 6-1</u> Mottles: 28" Ground Water: N/0 Ground Water: N/O Roots: 28" Roots: 24" Ledge: 94" 0-12" Topsoil Ledge: 84" 0-8" Topsoil 8-24" RB Fine Sandy 12-28" OB Fine Sandy 24-84" GR Mottled Sandy 28-94" GR Mottled Sandy Loam Till Loam Till <u>TP 6-2</u> <u>TP 6-4</u> Mottles: 32" Mottles: 30" Ground Water: N/O Ground Water: N/0 Roots: 32" Roots: 30"

# PERCOLATION TEST DATA Performed by CLA Engineers, Inc. on 8/6/20

Perc Rate = 4 min./inch

20	Perc 6-A: Presoak @ 12:22, 5"			Perc 6-B: Presoak @ 12:27 pm, 6.5"			
<u>TP 6-3</u> Mottles: 24"	Time	Measuredown (Inches)	Change (inches)	Time	Measuredown (Inches)	Change (inches)	
Ground Water: N/0 Roots: 24"	1:16	3.25	-	12:50	4.25	-	
Ledge: 84"	1:18	7.25	4	12:52	7.75	3.5	
0-8" Topsoil	1:20	9	1.75	12:54	11	3.25	
8-24" RB Fine Sandy Loam	1:22	11	2	12:56	13.25	2.25	
24-84" GR Mottled Sandy	1:24	12.25	1.25	12:58	14.75	1.5	
Loam Till	1:26	13.25	1	1:00	16.25	1.5	
<u>TP 6-4</u> Mottles: 30"	1:28	14.5	1.25	1:02	17.5	1.25	
Ground Water: N/O	1:30	15.5	1	1:04	18.75	1.25	
Roots: 30"	1:32	16.5	1	1:06	19.5	0.75	
Ledge: 89" 0-11" Topsoil	1:34	17	0.5	1:08	20.75	1.25	
11-30" YB/RB Fine Sandy	1:36	17.5	0.5	1:10	21.25	0.5	
Loam 30—89" GR Mottled Sandy	1:38	18	0.5	1:12	22.5	1.25	
Loam Till	1:40	18.5	0.5	Perc Rate = 4 min./inch			
	1:42	19	0.5				

SEPTIC SYSTEM DESIGN PRIMARY LEACHING AREA 3 BEDROOM RESIDENCE PERCOLATION RATE: 4 MIN./INCH

MLSS CALCULATION HYDRAULIC FACTORS

LEACHING AREA REQUIRED: 495 SF USE 12"x48" STONE TRENCH EFFECTIVE LEACHING AREA OF LEACHING TRENCH 3.0 SF/LF REQUIRED LENGTH = 495 SF / 3.0 SF/LF = 165 LF

DEPTH TO RESTRICTIVE LAYER = 24" SLOPE = 10 VF / 86 LF = 11.6% HYDRAULIC FACTOR (HF) = 26FLOW FACTOR (FF) = 1.5PERCOLATION FACTOR (PF) = 1.0 (UP TO 10.0 MIN./INCH) MLSS REQUIRED:  $26 \times 1.5 \times 1.0 = 39 \text{ LF}$ 

PROPOSED SYSTEM

USE 3 ROWS OF 55 LF

LEACHING AREA PROVIDED = 495 SF

RESERVE LEACHING AREA USE SAME AS PRIMARY SYSTEM

**LCLA** Engineers, Inc. CIVIL · STRUCTURAL · SURVEYING 317 Main Street Norwich, CT 06360 (860) 886-1966 Fax (860) 886-9165 No. DATE Subdivision Plan Prepared for Paul R. Lehto CLA-6383

#40 Almada Drive, Brooklyn, Connecticut Two Lot Resubdivision 40 Almada Drive Brooklyn, Connecticut

> Lot Development Plan Lot 1 & Lot 2

K.J.H. 3/31/2021 Sheet No.

Proj. Engineer

CLA

THE CONTRACTOR SHALL INSPECT, REPAIR AND/OR REPLACE EROSION CONTROL MEASURES EVERY 7

CONNECTICUT DEP. THE PROPOSED LOCATIONS OF SILTATION AND EROSION CONTROL MEASURES ARE SHOWN ON THE PLANS. THE CONTRACTOR SHALL PROVIDED SILT FENCE, STONE CHECK DAMS AND/OR OTHER EROSION CONTROL MEASURES AS NEEDED OR DIRECTED BY THE ENGINEER OR TOWN STAFF TO

ADEQUATELY PREVENT SEDIMENT TRANSPORT. EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO SITE DISTURBANCE.

DAYS AND IMMEDIATELY FOLLOWING ANY SIGNIFICANT RAINFALL OR SNOW MELT. SEDIMENT DEPOSITS MUST BE REMOVED WHEN WHEN DEPOSITS REACH APPROXIMATELY ONE HALF THE HEIGHT OF THE BARRIER. SEDIMENT CONTROL DEVICES SHALL REMAIN IN PLACE AND BE MAINTAINED BY THE CONTRACTOR UNTIL AREAS UPSLOPE ARE PERMANENTLY STABILIZED.

STAKED HAY BALE SILT BARRIERS OR SILT FENCE SHALL BE INSTALLED AROUND ANY TEMPORARY

STOCKPILE AREAS. TEMPORARY VEGETATIVE COVER MAY BE REQUIRED (SEE NOTE). INLET SEDIMENTATION CONTROL DEVICES SHALL BE INSTALLED UNDER THE GRATES OF ALL NEW CATCH BASINS AT THE TIME OF INSTALLATION, AND UNDER THE GRATES OF EXISTING CATCH BASINS IN THE CONSTRUCTION AREA.

CONTINUOUS DUST CONTROL USING WATER, CALCIUM CHLORIDE OR APPROVED EQUAL SHALL BE PROVIDED FOR ALL EARTH STOCKPILES, EARTH PILED ALONG EXCAVATIONS, SURFACES OF BACKFILLED

TRENCHES AND GRAVELED ROADWAY SURFACES. IF DEWATERING IS NECESSARY DURING ANY TIME OF CONSTRUCTION A CLEAR WATER DISCHARGE SHALL BE PROVIDED AS SHOWN IN THE HAY-BALE BARRIER DEWATERING DETAIL OR ALTERNATE

METHOD PROPOSED BY THE CONTRACTOR AND APPROVED BY THE ENGINEER. ALL DISTURBED AREAS SHALL BE RESTORED PER THE SLOPE STABILIZATION AND PERMANENT VEGETATION DETAILS. ALL DISTURBED AREAS THAT ARE SLOPED LESS THAN THREE HORIZONTAL TO ONE VERTICAL (3:1) SLOPE SHALL BE LOAMED, SEEDED, FERTILIZED AND MULCHED PER THE PERMANENT VEGETATIVE COVER SPECIFICATIONS. EROSION CONTROL MATTING SHALL BE PROVIDED ON

ALL DISTURBED AREAS THAT ARE SLOPED MORE THAN THREE HORIZONTAL TO ONE VERTICAL (3:1). 10. IF FINAL SEEDING OF DISTURBED AREAS IS NOT TO BE COMPLETED BEFORE OCTOBER 15, THE CONTRACTOR SHALL PROVIDE TEMPORARY MULCHING (DORMANT SEEDING MAY BE ATTEMPTED AS

WELL) TO PROTECT THE SITE AND DELAY PERMANENT SEEDING. WHEN FEASIBLE, TEMPORARY SEEDING OF DISTURBED AREAS THAT HAVE NOT BEEN FINISHED GRADED SHALL BE COMPLETED PRIOR TO OCTOBER 15.

12. ANY EROSION WHICH OCCURS WITHIN THE DISTURBED AREAS SHALL BE IMMEDIATELY REPAIRED AND STABILIZED. DURING THE CONSTRUCTION PHASE, INTERCEPTED SEDIMENT SHALL BE RETURNED TO THE SITE. POST SEEDING, INTERCEPTED SEDIMENT, IF ANY, SHALL BE DISPOSED OF IN A MANNER APPROVED BY THE TOWN AND ENGINEER.

EROSION AND SEDIMENTATION CONTROL MEASURES SHALL REMAIN IN PLACE UNTIL VEGETATION IS

RE-ESTABLISHED OR SLOPES ARE STABILIZED AND REMOVAL IS APPROVED BY THE TOWN. 14. UNFORESEEN PROBLEMS WHICH ARE ENCOUNTERED IN THE FIELD SHALL BE SOLVED ACCORDING TO THE "2002 CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL" BY THE CONNECTICUT COUNCIL ON SOIL AND WATER CONSERVATION IN COOPERATION WITH THE CONNECTICUT

THE CONTRACTOR SHALL PROVIDE THE NAME AND EMERGENCY CONTACT INFORMATION FOR THE PROJECT PERSONNEL RESPONSIBLE FOR EROSION AND SEDIMENTATION CONTROLS PRIOR TO THE START OF CONSTRUCTION.

16. THE WETLANDS ENFORCEMENT OFFICER SHALL BE NOTIFIED AT LEAST 2 BUSINESS DAYS PRIOR TO CONSTRUCTION TO INSPECT EROSION CONTROLS.

17. THE WETLAND ENFORCEMENT OFFICER SHALL BE NOTIFIED AT THE COMPLETION OF WORK FOR FINAL INSPECTION AND SIGN OFF OF PERMIT COMPLIANCE.

> NOTE: THE CONTRACTOR SHALL CONTINUALLY STORE THE FOLLOWING MATERIALS ONSITE DURING CONSTRUCTION TO MEET UNEXPECTED EROSION NEEDS

\* 100 LF OF SILT FENCE

\* 10 HAY BALES

\* 10 CY OF WOOD CHIPS OR CRUSHED STONE

## TEMPORARY SEDIMENT TRAP TO WATER QUALITY BASIN CONVERSION

THE WATER QUALITY BASINS ARE LOCATED AT A LOW POINTS IN THE DEVELOPED PORTION OF THE SITE TOPOGRAPHY AND WILL BE USED DURING CONSTRUCTION AS A TEMPORARY SEDIMENT TRAPS. THE TRAP WILL BE EXCAVATED TO THE FULL DEPTH PRIOR TO THE COMMENCEMENT OF OTHER SITE GRADING. THE HIGH-LEVEL RIP RAP OUTLET WILL BE INSTALLED AND WILL ALLOW WATER OUTFLOW AS THE BASIN ACCUMULATES SEDIMENTS. THE TRAP WILL BE INSPECTED AT LEAST ONCE PER WEEK AND WITHIN 24 HOURS AFTER ANY RAINFALL OF 0.5 INCHES OR GREATER. THE SEDIMENT TRAP WILL BE CLEANED WHEN SEDIMENT ACCUMULATION EXCEEDS ONE HALF OF THE AVAILABLE WET STORAGE CAPACITY. SEDIMENTS REMOVED FROM THE SEDIMENT TRAP WILL BE PLACED OUTSIDE OF THE UPLAND REVIEW AREA IN THE DESIGNATED STOCKPILE AREAS. WHEN THE SURROUNDING AREAS ARE GRADED THE SEDIMENT TRAP SHALL BE EXCAVATED TO AN ELEVATION 6" BELOW THE FINISHED GRADE. 6" OF PERVIOUS TOPSOIL IS TO BE PROVIDED AND ALL AREAS PLANTED WITH SEED MIXES SPECIFIED HEREIN.

## PERVIOUS TOPSOIL MIX FOR WATER QUALITY BASINS

THE FOLLOWING PERVIOUS TOPSOIL MIX SHALL BE USED IN THE STORMWATER TREATMENT BASINS. THE MATERIAL SHALL CONFORM TO THE REQUIREMENTS OF ARTICLE M.13.01.1 OF DOT FORM 817 WITH THE FOLLOWING GRADATION:

% PASSING 100%

#200

DO NOT COMPACT MATERIAL DURING INSTALLATION

60-80%

0%

## STORMWATER MANAGEMENT & POLLUTION PREVENTION PLAN

POLLUTION PREVENTION TEAM:
THE CONTRACTOR SHALL BE RESPONSIBLE FOR CARRYING OUT THE PROVISIONS OF THIS PLAN.

IMPERVIOUS SURFACES BEYOND THE WORK SITE SHALL BE SWEPT CLEAN OF SAND, SILT AND LITTER DAILY AT THE END OF THE WORK DAY.

CCESSORIES OR EQUIPMENT STORED OUTSIDE SHALL BE COVERED OR MAINTAINED TO MINIMIZE POSSIBILITY OF THESE MATERIALS OR THEIR RESIDUE PASSING TO STORM WATER.

NO WASHING OF VEHICLES, ACCESSORIES, EQUIPMENT, OR APPLIANCES AT THE WORK SITE.

MAINTENANCE AND INSPECTION: A. THE CONTRACTOR SHALL INSPECT, REPAIR AND/OR REPLACE EROSION CONTROL MEASURES EVERY 7 DAYS AND IMMEDIATELY FOLLOWING ANY SIGNIFICANT RAINFALL OR SNOW MELT.

B. SEDIMENT DEPOSITS MUST BE REMOVED WHEN WHEN DEPOSITS REACH APPROXIMATELY ONE HALF THE HEIGHT

C. REMOVE SEDIMENT DEPOSITS FROM TEMPORARY SEDIMENT TRAPS WHEN THE DEPOSITS REACH APPROXIMATELY ON

D. DAILY DUST CONTROL USING WATER, OR APPROVED EQUAL SHALL BE PROVIDED FOR ALL EARTH STOCKPILES, EARTH PILED ALONG EXCAVATIONS, SURFACES OF BACKFILLED TRENCHES AND GRAVELED SURFACES. SPILLS OR ACCIDENTAL DISCHARGES:

. COMPLY WITH STATE AND FEDERAL REGULATIONS TO CONTAIN AND CLEAN UP ANY SPILL OR DISCHARGE AND DISPOSE OF MATERIALS AT AN APPROVED FACILITY.

B. CONTACT CONNECTICUT DEEP OIL AND CHEMICAL SPILL RESPONSE DIVISION (860) 424-3338

C. THE FOLLOWING STEPS SHOULD BE PERFORMED AS SOON AS POSSIBLE:

a. STOP THE SOURCE OF THE SPILL b. CONTAIN THE SPILL c. COVER SPILL WITH ABSORBENT MATERIAL SUCH AS KITTY LITER, SAWDUST OR OIL ABSORBENT PADS. DO NOT

d. DISPOSE OF ABSORBER IN ACCORDANCE WITH LOCAL AND STATE REGULATIONS.

### POST CONSTRUCTION POLLUTION PREVENTION TEAM:

HALF OF THE STORAGE VOLUME.

THE PROPOSAL IS FOR THE TOWN OF BROOKLYN TO ACCEPT ALMADA DRIVE EXTENSION AS A TOWN ROAD THAT WILL BE INCORPORATED INTO THE TOWN MS4 OPERATIONS AND MAINTENANCE PROGRAM.

## TEMPORARY VEGETATIVE COVER

A TEMPORARY SEEDING OF RYE GRASS WILL BE COMPLETED WITHIN 15 DAYS OF THE FORMATION OF STOCKPILES. IF THE SOIL IN THE STOCKPILES HAS BEEN COMPACTED BY CONSTRUCTION OPERATIONS IT SHALL BE LOOSENED TO A DEPTH OF 2 INCHES BEFORE THE FERTILIZER, LIME AND SEED IS APPLIED. 10-10-10 FERTILIZER AT A RATE OF 7.5 POUNDS PER 1000 S.F. LIMESTONE AT A RATE OF 90 LBS. PER 1000 S.F. SHALL BE USED. RYE GRASS APPLIED AT A RATE OF 1 LB. PER 1000 S.F. SHALL PROVIDE THE TEMPORARY VEGETATIVE COVER. STRAW FREE FROM WEEDS AND COARSE MATTER SHALL BE USED AT A RATE OF 70-90 LBS. PER 1000 S.F. AS A TEMPORARY MULCH. APPLY MULCH AND DRIVE TRACKED EQUIPMENT UP AND DOWN SLOPE OVER ENTIRE SURFACE SO CLEAT MARKS ARE PARALLEL TO THE CONTOURS.

## PERMANENT VEGETATIVE COVER

TOPSOIL WILL BE REPLACED ONCE THE EXCAVATIONS HAVE BEEN COMPLETED AND THE SLOPES ARE GRADED AS SHOWN ON THE PLANS. PROVIDE SLOPE PROTECTION AS CALLED FOR ON THE PLANS AND DETAILS. TOPSOIL SHALL BE SPREAD AT A MINIMUM COMPACTED DEPTH OF 6 INCHES. ONCE THE TOPSOIL HAS BEEN SPREAD, ALL STONES TWO INCHES OR LARGER IN ANY DIMENSION WILL BE REMOVED AS WELL AS DEBRIS.

- APPLY AGRICULTURAL GROUND LIMESTONE AT THE RATE OF TWO TONS PER ACRE OR 100 LBS. PER 1000 S.F. APPLY 10-10-10 FERTILIZER OR EQUIVALENT AT A RATE OF 300 LBS. PER ACRE OR

7.5 LBS. PER 1000 S.F. WORK LIMESTONE AND FERTILIZER INTO THE SOIL TO A DEPTH OF 4 INCHES.

INSPECT SEEDBED BEFORE SEEDING. IF TRAFFIC HAS COMPACTED THE SOIL, RETILL COMPACTED AREAS. APPLY THE FOLLOWING GRASS SEED MIX:

## TYPICAL SEED MIXTURE

ALL DISTURBED AREAS LBS./1000 S.F LBS./ACRE KENTUCKY BLUEGRASS 0.45 CREEPING RED FESCUE 0.45 PERENNIAL RYEGRASS 0.10

TYPICAL SEED MIXTURE FOR STEEP SLOPES (2:1 OR GREATER) CT DEP SEED MIX NO. 6 <u>LBS./1000 S.F</u> CREEPING RED FESCUE REDTOP (STREEKER, COMMON) 0.05 PERENNIAL RYEGRASS 0.50 1.05

THE RECOMMENDED SEEDING DATES ARE: APRIL 1 - JUNE 15 AND AUGUST 15 - OCTOBER 15

IMMEDIATELY FOLLOWING SEEDING, FIRM SEED BED WITH A ROLLER AND MULCH WITH WEED FREE STRAW. IF PERMANENT VEGETATIVE COVER IS HAS NOT BEEN ESTABLISHED BY OCTOBER 15, APPLY A TEMPORARY VEGETATIVE COVER ON THE TOPSOIL.

PROVIDE 6" THICKNESS OF TOPSOIL OVER CLEAN FILL. INSTALLING BLANKETS, INCLUDING APPLICATION OF LIME,

6" TOPSOIL PER

COVER NOTES

PERMANENT VEGETATIVE -

UNDISTURBED AREA

FOR AT THE UNIT PRICE FOR LOAM, SEED, FERTILIZE & MULCH)

FERTILIZER, AND SEED MIX PER PERMANENT VEGETATIVE COVER NOTES. (SHALL BE PAID

END (SHINGLE STYLE) WITH APPROXIMATELY 4" OVERLAP. STAPLE THROUGH OVERLAPPED

BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE BLANKET IN 6" DEEP  $\times$  6" WIDE TRENCH, BACKFILL AND COMPACT THE TRENCH AFTER STAPLING.

5. WHEN BLANKETS MUST BE SPLICED DOWN THE SLOPE, PLACE BLANKETS END OVER

NOTE: ALL PERMANENT EROSION CONTROL BLANKETS ARE TO BE NORTH AMERICAN GREEN BIONET C125BN OR APPROVED EQUAL.

EROSION CONTROL MATTING DETAIL

(FOR 3:1 SLOPES OR GREATER)

TYPICAL LOAM & SEED SECTION DETAIL


(FOR ALL DISTURBED AREAS)


SLOPE STABILIZATION DETAILS

NOT TO SCALE

ROLL THE BLANKET (A) DOWN OR (B) HORIZONTALLY ACROSS THE SLOPE.

4. THE EDGES OF PARALLEL BLANKETS MUST BE STAPLED WITH APPROXIMATELY 2







SILT FENCE FILTER CLOTH TO BE SECURELY FASTENED TO GRADE STAKE

WITH STAPLES, 6" ON CENTER. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN ONE ANOTHER THEY SHALL OVERLAP BY 6" AND BE FOLDED. BALES SHALL BE PLACED IN A ROW WITH ENDS TIGHTLY ABUTTING THE


## SILT FENCE BACKED BY HAY BALES DETAIL NOT TO SCALE





 STORMWATER LOG ENDS SHALL BE TIED TOGETHER, OVERLAPPED AT LEAST 24" OR BE SECURED AS RECOMMENDED BY THE MANUFACTURER. STORMWATER SEDIMENT LOG (WATTLE) DETAIL




INLET SEDIMENT CONTROL DEVICE DETAIL









SILT FENCE FILTER CLOTH TO BE SECURELY FASTENED TO GRADE STAKE WITH STAPLES, 6" ON CENTER. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN ONE ANOTHER THEY SHALL

OVERLAP BY 6" AND BE FOLDED.

3. BALES SHALL BE PLACED IN A ROW WITH ENDS TIGHTLY ABUTTING THE ADJACENT BALES.

DEWATERING PLAN

A CLEAR WATER DISCHARGE SHALL BE PROVIDED AS FOLLOWS:

1. PUMP INLET SHALL BE PROTECTED WITH FILTER FABRIC & CRUSHED STONE.

PUMP SHALL BE STAGED OUTSIDE OF WETLANDS. THE WATER SHALL BE PUMPED TO A DEWATERING STRUCTURE WHICH SHALL
BE LOCATED AT LEAST 50 FEET FROM ANY REGULATED WETLAND AREA OR AS SHOWN ON THE PLANS.

THE DEWATERING STRUCTURE SHALL BE SIZED TO ACCOMMODATE PUMP DISCHARGE

RATE: REQUIRED VOLUME (C.F.) = PUMP DISCHARGE (G.P.M.) x 16

THE DEWATERING STRUCTURE SHALL DISCHARGED TO A VEGETATED AREA.

ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN AND PROPERLY DISPOSED OF WHEN ACCUMULATION REACHES HALF OF THE REQUIRED STORAGE VOLUME.

HAY BALE BARRIER DE-WATERING DETAIL

NOT TO SCALE

DEWATERING AREA SHALL BE RESTORED WITH NEW ENGLAND EROSION CONTROL SEED MIX.

CLA Engineers, Inc. CIVIL · STRUCTURAL · SURVEYING 317 Main Street Norwich, CT 06360

No. DATE

Subdivision Plan Prepared for Paul R. Lehto #40 Almada Drive, Brooklyn, Connecticut

(860) 886-1966 Fax (860) 886-9165

Two Lot Resubdivision 40 Almada Drive Brooklyn, Connecticut

Stormwater Management Plan and **Erosion & Sedimentation Control Details** 

K.J.H. 3/31/2021

CLA-6383

roj. Enginee

\CLA

## SEPTIC GENERAL NOTES

- ALL WORK AND MATERIAL (SEPTIC TANK, DISTRIBUTION BOX, PIPE, ETC.) SHALL CONFORM TO THE CONNECTICUT PUBLIC HEALTH CODE ON—SITE SEWAGE DISPOSAL REGULATIONS AND TECHNICAL STANDARDS FOR SUBSURFACE
- SEWAGE DISPOSAL SYSTEMS, AS REVISED. PROPOSED SEPTIC SYSTEMS SHALL BE STAKED IN THE FIELD BY A LAND SURVEYOR LICENSED IN THE STATE OF CONNECTICUT. A BENCHMARK SHALL BE SET WITHIN 10'-15' OF THE PROPOSED SEPTIC SYSTEM PRIOR TO
- 3. SEWER LINE FROM FOUNDATION WALL TO SEPTIC TANK SHALL BE 4" SCHEDULE 40 PVC ASTM D 1785 AND JOINTS PER HEALTH DEPT. CODE.
- 4. PIPE FROM SEPTIC TANK TO DISTRIBUTION LINES SHALL BE 4" SOLID PVC CONFORMING TO ASTMD-3034 AND
- 5. LEACHING SYSTEM ROWS SHALL BE SET LEVEL FOR ENTIRE LENGTH AND HAVE A CENTER TO CENTER SPACING AS CALLED FOR IN THE CONNECTICUT PUBLIC HEALTH CODE.
- THERE ARE PRESENTLY NO KNOWN WATER WELLS WITHIN 75' OF THE PROPOSED SEPTIC SYSTEMS. PROPOSED SEPTIC AREAS SHALL BE CLEARED AND GRUBBED. ALL TOPSOIL IN THE AREA SHALL BE STRIPPED
- AND STOCKPILED FOR FUTURE USE. ALL FILL MATERIAL SHALL BE CLEAN EARTH FREE OF STUMPS, ORGANICS, CONSTRUCTION DEBRIS AND TOPSOIL.
- TOPSOIL SHALL BE RE-APPLIED OVER ALL FILL AREAS AND ALL DISTURBED AREAS IN ACCORDANCE WITH THE SLOPE STABILIZATION DETAILS.


## SELECT FILL SPECIFICATION

SELECT FILL PLACED WITHIN AND ADJACENT TO LEACHING SYSTEM AREAS SHALL BE CLEAN MATERIAL COMPRISED OF SAND, OR SAND AND GRAVEL, FREE FROM ORGANIC MATTER AND FOREIGN SUBSTANCES. THE SELECT FILL SHALL MEET THE FOLLOWING REQUIREMENTS UNLESS OTHERWISE APPROVED BY THE DESIGN P.E. SELECT FILL EXCEEDING 6 PERCENT PASSING THE #200 SIEVE BASED ON WET SIEVE ANALYSIS CANNOT BE APPROVED BY THE DESIGN P.E.

- 1. THE SELECT FILL SHALL NOT CONTAIN ANY MATERIAL LARGER THAN THE THREE (3) INCH SIEVE. 2. UP TO 45% OF THE DRY WEIGHT OF THE REPRESENTATIVE SAMPLE MAY BE RETAINED (GRAVEL PORTION)
- ON THE #4 SIEVE. 3. THE MATERIAL THAT PASSES THE #4 SIEVE IS THEN REWEIGHED AND THE SIEVE ANALYSIS STARTED. 4. THE REMAINING SAMPLE SHALL MEET THE FOLLOWING GRADATION CRITERIA


		PERCENT	PASSING	
SIZE	WET	SIEVE	DRY	SIEVE
	100		100	
	70-	100	70-	100
	10-5	50*	10-	75
	0-2	0	0-5	
	0-5		0-2	.5
	SIZE	100 70- 10-9 0-2	SIZE WET SIEVE 100 70-100 10-50* 0-20	100 100 70-100 70- 10-50* 10- 0-20 0-5

\* PERCENT PASSING THE #40 SIEVE CAN BE INCREASED TO NO GREATER THAN 75 IF THE PERCENT PASSING THE #100 SIEVE DOES NOT EXCEED 10 AND THE #200 SIEVE DOES NOT EXCEED 5.



- DIMENSIONS MAY VARY DEPENDING ON TANK MANUFACTURER (UNITED
- CONCRETE SHOWN)
  CONCRETE 4,000 P.S.I. AT 28 DAYS STEEL REINFORCEMENT- ASTM A-615 GR. 60, A-185 OR A-497,
- CONSTRUCTION JOINT-SEALED WITH 1" DIA. BUTYL RUBBER OR EQUIVALENT.
- SEPTIC TANK SHALL MEET THE REQUIREMENTS OF SECTION 5 OF THE CT PUBLIC HEALTH CODE
- 6. PROVIDE RISERS AND ACCESS COVER TO WITHIN 12" OF FINISHED GRADE. TANK ACCESS COVERS TO REMAIN IN PLACE.


# 1,000 GALLON REGULAR DUTY SEPTIC TANK DETAIL





\* INCREASE TO 24" WHERE PERC RATE IS FASTER THAN 5.0 MIN/IN


12" x 48" LEACHING TRENCH DETAIL

NOT TO SCALE












NOT TO SCALE


STANDARD D-BOX WITH ELBOW DETAIL








TYPICAL DRIVEWAY DETAILS NOT TO SCALE



NOTES:

1. PROVIDE CONTINUOUS TACK COAT ALONG EDGE WHEN MATCHING EXISTING PAVEMENT 2. CONTRACTOR TO PROVIDE COMPACTION ON ALL TRENCH BACKFILLS, EXCAVATIONS AND PAVEMENT BASES TO NOT LESS THAN 95% OF THE DRY DENSITY FOR THAT MATERIAL WHEN TESTED IN ACCORDANCE WITH AASHTO

T180, METHOD D TYPICAL GRAVEL DRIVEWAY SECTION DETAIL NOT TO SCALE



NOTES:

1. PROVIDE CONTINUOUS TACK COAT ALONG EDGE WHEN MATCHING EXISTING PAVEMENT

2. CONTRACTOR TO PROVIDE COMPACTION ON ALL TRENCH
BACKFILLS, EXCAVATIONS AND PAVEMENT BASES TO NOT
LESS THAN 95% OF THE DRY DENSITY FOR THAT MATERIAL WHEN TESTED IN ACCORDANCE WITH AASHTO T180, METHOD D

TYPICAL BITUMINOUS DRIVEWAY SECTION DETAIL



Subdivision Plan Prepared for Paul R. Lehto #40 Almada Drive, Brooklyn, Connecticut

Two Lot Resubdivision 40 Almada Drive Brooklyn, Connecticut

Construction Details

CLA-6383 Proj. Engineer K.J.H. 3/31/2021 Sheet No.

CLA